

RESOLUTION NO. 3067

A RESOLUTION ADOPTING THE 2017 CITY OF BEND DOWNTOWN STRATEGIC PARKING MANAGEMENT PLAN

FINDINGS

- A. In October 2015 the City Council directed the initiation of a public process to assess and optimize Bend's public parking resources. The process would include studies and would occur in three phases: downtown, city-wide, and Galveston Avenue/Century Drive.
- B. For the first phase, the process included formation of the Downtown Stakeholder Advisory Committee (DSAC), which met ten times over the course of 19 months.
- C. The DSAC was assembled and intended to represent a variety of perspectives, including downtown residents and employees, downtown business and property owners, other community members, and representatives of the Old Bend and River West neighborhood associations.
- D. In April 2016, the guiding principles for the study, developed by the DSAC, were presented to and approved by the City Council.
- E. Consistent with the guiding principles, data collection occurred in spring and summer 2016.
- F. In April 2017, the implementation strategies informed by the data collection were presented to and approved by the City Council.
- G. The Downtown Strategic Parking Management Plan (Plan) is the result of this process, the guiding principles, collected data, implementation strategies, and the extensive work, input, and process guided by the Council and the DSAC.
- H. The Plan contains recommendations including, among other things, infrastructure upgrades, operations initiatives, creation of a Parking Demand Manager position, possible fee changes, refinement and adjustment of parking management zones and parking permit programs, updating data and other performance metrics, and other recommendations, strategies, and actions.

Based on these findings, the City of Bend resolves as follows:

1. The City Council supports and adopts the 2017 City of Bend Downtown Strategic Parking Management Plan and its goals, strategies, and recommendations.

2. The City Council directs staff to take appropriate action to implement and advance the goals, strategies, and recommendations reflected in the Plan.

Adopted by Roll Call Vote: June 6, 2017

YES: Casey Roats, Mayor
Sally Russell
Bill Moseley
Bruce Abernethy
Nathan Boddie
Justin Livingston
Barb Campbell

NO: NONE




Casey Roats, Mayor

Attest:



Robyn Christie, City Recorder

Approved as to form:



Mary A. Winters, City Attorney




CITY OF BEND

2017

City of Bend, Oregon Downtown Strategic Parking Management Plan

*Report of the Downtown Stakeholder Advisory Committee (DSAC)
Project Summary and Recommendations for Parking Management*

FINAL REPORT
May 31, 2017



ACKNOWLEDGMENTS

Downtown Stakeholder Advisory Committee

DeeDee Cochran	EID Business/Property Owner
Serena Dietrich	Business Representative Supporting Multi-Modal
Kevin English	At Large Community Member
Shantelle Flick	EID Employee
Tom Fisher	At Large Community Member
Jeff Huey	Accessible Community Representative
Sarah Jordon	EID Business
James Lewis	Deschutes County
Karen LeTourneau	EID Business/Property Owner/DBBA
Marie Matthews	At Large Community Member
Monte Payne	River West NA Representative
Parry Thomas	At Large Community Member
Doug Watson	Large Event Manager
Brett Yost	Old Bend NA Representative

City Project Staff

Carolyn Eagan	City of Bend
Nick Arnis	City of Bend
Tyler Deke	City of Bend
Katherine Montgomery	City of Bend

Consultant Team

Rick Williams	Rick Williams Consulting
Owen Ronchelli	Rick Williams Consulting
Pete Collins	Rick Williams Consulting
Phill Worth	Kittelsohn & Associates
Ashleigh Ludwig	Kittelsohn & Associates
Anne George	Anne George: Facilitation, Mediation + Public Involvement

Table of Contents

I.	INTRODUCTION	2
II.	EXECUTIVE SUMMARY	3
III.	FORMAT OF INFORMATION – GETTING TO SOLUTIONS	8
IV.	WHAT WE HEARD – PUBLIC INVOLVEMENT	9
V.	GUIDING PRINCIPLES – ELEMENTS OF PARKING MANAGEMENT	13
	A. City Role and Coordination	13
	B. Priority Users	15
	C. Active Capacity Management	15
	D. Information Systems (Supply- and Customer-Based)	16
	E. Integration with Other Modes.....	17
	F. Planning for Future Supply	18
	G. Financial Viability.....	18
VI.	PARKING INVENTORY SUMMARY	19
VII.	MEASURING PERFORMANCE	25
VIII.	KEY FINDINGS – PARKING UTILIZATION.....	26
	A. On-Street Data Collection - Methodology	26
	B. Off-street Data Collection - Methodology.....	26
	C. On-Street Occupancies – Spring 2016 (Thursday/Saturday)	27
	D. Peak-Hour Occupancy – Heat Map (Spring)	28
	E. On-Street Occupancies – Summer 2016 (Wednesday/Friday).....	31
	F. Peak-Hour Occupancy – Heat Map (Summer).....	32
	G. On-Street: Other Characteristics of Use (Seasonal Comparison)	35
	H. Off-Street Parking Occupancy	39
IX.	RECOMMENDED DOWNTOWN PARKING MANAGEMENT STRATEGIES	43
	A. Policy and Organizational Action Strategies	44
	B. Parking Management Strategies – Operations (Phase 1)	53
	C. Parking Management Strategies – Infrastructure (Phase 2)	68
X.	SUMMARY	73
	ATTACHMENT A	74

City Of Bend: Downtown Strategic Parking Management Plan

I. INTRODUCTION

The attractiveness of Bend and the vibrancy of downtown are undeniable. Impacts of the great recession are largely in the past and Bend's economy is growing once again. Demands for vehicle parking and levels of pedestrian activity, great bellwethers of a healthy downtown, have reached pre-recession levels. In recognition of this, Bend's City Council directed a public process to determine effective methods of optimizing public parking resources and enhancing the experience of visiting downtown. The Bend Downtown Strategic Parking Management Plan is the culmination of this effort and is presented in detail in this final report.

Downtown residents, employees, employers, and property owners were joined by community members as a Downtown Stakeholder Advisory Committee (DSAC). The City Council commissioned these individuals to liaise with their representative groups and work collaboratively to shape a parking management plan they would support through adoption and implementation. Over the course of 18 months and 10 committee meetings, these representatives crafted goals, weighed evidence, determined needs, and conceived strategies to address a broad range of challenges. The committee concluded with a multitude of recommended strategies to produce solutions that benefit all stakeholders and the community as a whole.

Goals and guiding principles were established to define desired outcomes and serve as a framework for determining balanced approaches to improving downtown parking conditions. A central tenet of the committee was to rely on data and technical analysis to verify the issues and prove the effectiveness of proposed solutions. Because issues often impacted stakeholders differently, the committee devised a set of strategies to produce a more balanced and complete solution.

The plan presented herein provides a comprehensive set of parking management strategies, sequenced to ensure a management structure is properly constructed, funded, staffed, and implemented. Plan priorities link directly back to the goals and guiding principles. Flexibility is embedded in the strategies to enable responsiveness and adaptation to changing conditions. Insight, support and guidance from a standing committee of downtown representatives ensures that a new Parking Demand Manager, Downtown Parking Advisory Committee (DPAC) and City Council are in regular communications with those most directly impacted and benefited by plan implementation. Ultimately the Parking Management Plan will successfully "get the right user to the right parking spot," ensuring convenience and efficiency.

II. EXECUTIVE SUMMARY

Rick Williams Consulting was retained by the City of Bend to conduct an overall evaluation of the downtown parking system and develop a comprehensive Strategic Parking Management Plan. The RWC team also includes Kittelson & Associates (KAI) and Anne E. George Facilitation, Mediation + Public Involvement (AG).

The evaluation entailed review of existing parking operations and previous study findings, public engagement/outreach, and comprehensive data collection. All recommended strategies have been informed by in-depth discussions and topic-specific work sessions with the Downtown Stakeholder Advisory Committee (DSAC), as well as additional community input.

This Executive Summary outlines the key strategies proposed for implementation in downtown Bend. More detailed summaries and descriptions of the process, data findings and the strategies themselves are provided herein, beginning on page 43 of this report. Additional information and summaries are included in the Attachments provided at the end of the report.

The consultant believes the strategies recommended and developed in concert with project staff, Downtown Stakeholder Advisory Committee, and the community effectively respond to the unique environment, goals, and objectives of Downtown Bend.



A. Findings – System Performance

Substantial data was collected, analyzed and reported to the Downtown Stakeholder Advisory Committee and to the Bend community through various public engagement efforts. Highlights of the discoveries made through these technical efforts include the following:

- **Solutions:** There is a finite supply of parking in downtown Bend. Currently, there is availability in the on-street and off-street supplies. New systems need to be implemented to direct users to available supplies. If Bend is to have a customer-first parking management system, the system must appeal to and accommodate customers and visitors, and identify safe and accessible parking for employees and residents.
- **Use:** Summer is the peak season, with the number of vehicle trips downtown and use of the supply about 12.5% higher than in spring.
- **Parking Behavior:** There is no significant change in parking behavior between the two seasons for either people parking long-term or customers and visitors. This includes average duration of stay, number of employee permits, rates of violation, and turnover.
- **High-Use Areas (On-Street):** In spring and summer, there is a defined area of high parking activity in the downtown core, which shows sustained occupancy rates of 85% or greater. This area of parking constraint operates much differently than the east side of downtown, which is underutilized in spring and summer.
- **Off-Street Parking Availability:** Although parking activity is higher in summer, the off-street system still has a meaningful amount of unused parking, particularly in the parking garage.
- **Shared Use:** There are opportunities for shared use of off-street parking facilities. For example, three publicly controlled lots¹ could accommodate employee and off-peak event parking.
- **The Mirror Pond lots** are consistently constrained at or above 85% occupancy. Strategies should be developed to address this.
- **Surrounding Neighborhoods:** Surrounding neighborhoods may benefit from a separate engagement process that investigates the trade-offs of neighborhood parking management to further protect resident and guest parking access.

¹ Includes the City-owned parking garage, the Newport Lot, and County parking facilities.

B. Policy and Organizational Action Strategies²

Incorporating parking system management into the City’s development policy ensures that the goals of the Parking Management Plan can be met. The following strategies should be implemented within **12 months** of plan adoption.

1. Formalize the Guiding Principles as policies in appropriate City documents.
2. Adopt the 85% Rule as the standard for measuring performance of the parking supply and triggering specific management strategies, rates, permit prices and efforts by discrete zone.
3. Centralize the management and administration of parking in a Parking Services Division, integrated with the broader program of transportation services management.³
4. Create the position of Parking Demand Manager for the City of Bend. Develop a job description and submit a service package to hire an appropriate individual.
5. Establish a Downtown Parking Advisory Committee to assist in implementation and ongoing review of the parking plan.
6. Evaluate collection of data to measure parking impacts in select neighborhoods adjacent to the downtown, as well as feasibility and cost of neighborhood permit programs (e.g., administration, process and stakeholder education).
7. Develop funding options to support parking management, maintain the existing parking supply, and support future growth, ensuring the financial feasibility of the system.
8. Create a cohesive pricing policy for on- and off-street parking in downtown Bend. Support new policy with a rate/fee study to inform appropriate adjustments to current pricing formats to cover the cost of managing the downtown parking system.
9. Evaluate and implement solutions to safety impediments that create inconvenient and inefficient connections to parking, e.g., lighting, sidewalk/paths, lot conditions, etc.

C. Parking Management Strategies - OPERATIONS

The following strategies should be implemented within **12 to 24 months** of plan adoption.

² These strategies would revise the municipal code to support long-term planning and efforts to “right-size” parking in new development. They will be developed in Phase 2 of the larger city-wide parking study, integrating specific recommendations related to the downtown. Recommendations from this process will be brought back to the DSAC and City Council for review and input.

³ The Parking Division must coordinate with transportation staff to achieve balanced access across all transportation modes.

10. Establish business-to-business and residential outreach on parking issues, including education and planning, and a *Customer First* Partnership with the Downtown Bend Business Association.
11. Identify off-street shared-use opportunities based on data from the 2016 parking study. Establish goals for transitioning permit users and long-term parkers out of on-street parking, begin outreach to opportunity sites, negotiate agreements, and sell permits.
12. Implement variable-rate pricing for on-street permits based on location, demand, and availability of parking. This will create pricing differentials between “premium” and underutilized locations.
13. Reduce or phase out the number of “2-Hour or as Otherwise Specified” on-street stalls in coordination with Strategies 11 and 12 above to simply “2-Hour Parking”.
14. Based on documented parking behavior, establish four distinct on-street parking management zones in the downtown parking district. Use 2016 or newer data to define the boundaries.
15. Eliminate free parking for the first two hours at the Mirror Pond lots.
16. Create a critical path timeline to a new parking brand that can be utilized at all City-owned lots and shared facilities, and in marketing/communications.
17. Standardize the design of on-street parking signage in the parking management district and incorporate the new brand/logo.
18. Rename all public parking facilities by address.
19. Establish best-practice protocols and performance metrics for enforcement personnel and support enforcement with appropriate technology.
20. Where practical, expand the bike parking network to connect parking and the downtown, encouraging employee bike commute trips and drawing customers to downtown businesses.
21. Develop a reasonable schedule of data collection—every two years—to assess performance of the parking supply and support the 85% Rule for decision-making.
22. Using data collected per **Strategy 21**, evaluate on-street pricing by zone in high-occupancy areas. If peak occupancy exceeds 85%, implement on-street pricing during enforcement hours where appropriate.
 - If on-street pricing is implemented, review on-street time stays established in **Strategy 14**.
23. Eliminate free parking in the public garage when garage occupancies exceed 85% and on-street parking is priced. Implement demand-based pricing for all hours of enforced parking—e.g., hourly, evening, weekend, overnight, and event rates.

D. Parking Management Strategies: INFRASTRUCTURE

The following strategies build upon and are facilitated by work completed in Strategies 1 through 23. They should be implemented within **24 to 48 months** of plan adoption.

24. Develop and implement improvements at the downtown public parking garage to enhance its appearance, identity, safety, revenue control, communications technology, and pedestrian access.
25. Solicit firms to establish wayfinding and dynamic signage systems in the public right of way, integrated with the off-street system and using the brand/logo developed per **Strategy 16**.
26. If existing parking becomes limited, explore expanding access capacity with new transit and parking.
27. Develop cost forecasts and feasible financing methods for preferred parking supply and transit/shuttle options.
28. Expand capacity as necessary and feasible.

The City and DPAC may elect to reorder, accelerate, or moderate strategies depending on community support and consensus, opportunity, and/or funding. All strategies will require consistent and dedicated management with active participation by the private sector.

E. Summary

The Bend Downtown Strategic Parking Management Plan is the culmination of efforts by the Downtown Stakeholder Advisory Committee and community members who contributed input to the issues, guiding principles, and final strategies that comprise the plan. The strategies are organized to follow a logical sequencing of activities that build on one another. They begin with efforts to organize, fund and staff the management program and then incrementally improve the efficiency and attractiveness of the parking system. A Downtown Parking Advisory Committee is recommended as a critical sounding board for the Parking Demand Manager. Monitoring of system performance is central to defining ongoing issues and selecting appropriate strategies to implement. Implementation of the plan is expected to provide a safe, secure, financially sound downtown parking system that is well-integrated with all modes of access to downtown.

The strategies envisioned here will be implemented over a minimum of four years, informed by the 85% Rule and documented parking demand. Overall, the strategies are designed to “get the right vehicle to the right parking spot” in a manner that supports the Guiding Principles established as a part of this plan.

III. FORMAT OF INFORMATION – GETTING TO SOLUTIONS

This project has allowed the City and stakeholders to take a fresh look at the parking situation in Bend with a view to improving the quality and ease of access in the downtown.

This report summarizes:

- Public Involvement (Section IV. WHAT WE HEARD – PUBLIC INVOLVEMENT)
- Guiding Principles for parking (Section V. GUIDING PRINCIPLES – ELEMENTS OF PARKING MANAGEMENT)
- Summary of downtown parking inventory (Section VI. PARKING INVENTORY SUMMARY)
- Measuring performance (Section VII. MEASURING PERFORMANCE)
- Key findings related to parking utilization (Section VIII. KEY FINDINGS – PARKING UTILIZATION)
- Recommended Parking Management Strategies (Section IX. RECOMMENDED DOWNTOWN PARKING MANAGEMENT STRATEGIES)

The strategies outlined within this document are intended to spark discussion between the City of Bend and downtown stakeholders on policies and actions that will support a vital and growing downtown. As the City and its partners consider these strategies, discussion of the “who, what, and how” of implementation will be essential, and it may be determined that strategies should be reordered or implemented concurrently. Such refinements will be based on opportunities and challenges that arise, momentum, resource identification, and broader community input. The plan presented here is a new approach to parking in downtown Bend, and changes can be expected.

IV. WHAT WE HEARD – PUBLIC INVOLVEMENT

Public Involvement Goals and Stakeholders

1. Public Involvement Goals

Early in the process, the following goals were identified for the public involvement plan.

- Inform the community about existing downtown parking conditions and foster the exchange of ideas;
- Document community interests and concerns;
- Identify parking management needs and objectives;
- Involve affected or interested stakeholders in the development of downtown parking management planning; and
- Develop a community supported Bend Downtown Parking Plan that will enhance the vitality of downtown Bend.

2. Stakeholder Identification

The project sought engagement from downtown stakeholders and the greater community throughout the study. With a focus on engaging those affected by or interested in the outcomes of the project, the project specifically targeted the following groups for their participation:

- Downtown business owners / managers/ organization directors
- Downtown employees
- Downtown business association
- Downtown property owners/developers
- Downtown residents
- Community at large
- Multimodal advocates
- Accessibility community

3. Community Involvement

The process was designed to be open, transparent, and engaging for stakeholders. Public involvement began with informational **Parking 101 meetings** for the community and the formation of a **Downtown Stakeholder Advisory Committee (DSAC)** comprising representative community stakeholders in early 2016. A **Technical Advisory Committee (TAC)** of City staff and community technical experts was also formed at that time. A **project website** was created to keep the community engaged and informed throughout the project.

In August 2016, downtown businesses, employees, property owners, and residents were invited to a series of informal **coffee klatches** following the creation of the DSAC-developed Guiding Principles for the study. In addition, **DSAC meetings** were open to the public and posted, and opportunities for community input were provided at every meeting. **Project updates** were also provided during the study to the Downtown Bend Business Association, the Bend Economic Development Advisory Board, the Bend Planning Commission, Old Bend Neighborhood Association, River West Neighborhood Association, and the Bend City Council.

The community was informed about meetings and events throughout the process via the website, press releases, social media announcements, event flyers throughout downtown, and emails to interested parties and individuals.

4. Public Involvement Activities

Downtown Bend Parking Study Website

A website was created to share study data and analysis, public meeting information, outreach summaries, reports, and public comments for the advisory committees.

Parking 101 Community Sessions

The project team offered three Parking 101 Sessions in February 2016 for the community at downtown locations. These sessions were best practices seminars and provided community members with opportunities to learn more about how other communities approach parking planning, as well as industry practices. The sessions also provided opportunities for the project team to hear concerns from community members about downtown parking and answer questions. Community members played a critical role in determining the study area and outcomes of the parking study.

Downtown Stakeholder Advisory Committee (DSAC)

The DSAC is a community advisory group appointed by the Bend City Council, representing downtown businesses, employees, property owners, residents, as well as at-large community members, the accessibility community, multimodal advocates, event planners, and Deschutes County. The committee was tasked with developing downtown parking strategies for parking management in the downtown area, with input from community stakeholders, the TAC, and the project management team. Over a period of 13 months, the DSAC held 10 meetings to identify concerns, review parking data, request additional data when needed, and develop a set of guiding principles for their task. The committee found agreement on a full set of downtown Bend parking management strategies following extensive discussion and public input. A complete listing of DSAC members is provided in the Acknowledgements page of this report.

Technical Advisory Committee

The Technical Advisory Committee (TAC) comprised technical experts in downtown development and parking management and included City staff, City officials, and community experts. The TAC supported both the project team and the DSAC in providing expert information and data.

Downtown Bend Engagement - Guiding Principles Coffee Klatches

In August 2016, the DSAC sought feedback on their “Draft Guiding Principles” from downtown businesses, employees, property owners, and other interested community members. A series of four coffee klatches were hosted at downtown businesses. This engagement was designed to help the DSAC obtain early feedback from downtown stakeholders on needs and priorities around parking. Over 120 businesses and offices were visited in advance of the klatches to encourage participation. The project team also posted flyers throughout downtown and provided announcements electronically via the Downtown Bend Business Association and project interested parties lists.

Sixteen stakeholders attended at least one coffee klatch or DBBA meeting on the Draft Guiding Principles. In addition, information about the Parking Study and how to stay updated and engaged was shared with over 200 downtown stakeholders via outreach efforts. Stakeholders shared generally positive feedback on the DSAC Guiding Principles. A summary of these events, “Downtown Bend Parking Study Downtown Stakeholder Engagement Summary August 2016” can be found in **Attachment F** of this document.

DSAC Communications with City Council

Bend City Council members were updated throughout the project. At the start of the study, the project team provided an update to Council that included project phasing, the study area, and a review of best practices in parking management on April 6, 2016.

The project management team returned to update the Council in August 2016 to present the Draft Guiding Principles the committee created to guide their process. The Council unanimously voted to support the DSAC Guiding Principles and the DSAC continued work on the study.

Representatives of the DSAC provided Council with an additional update on April 19, 2017, when they presented their draft strategies for Council. Council members were invited to ask questions and provide input to the DSAC as they worked to complete their strategies. Council indicated they supported the direction and work of the DSAC on their parking strategy development and encouraged the committee to continue to consider long-term parking needs in their report. The DSAC intends to present its final downtown Bend Parking Management Study Report to the Council on May 17, 2017, following a project public open house on May 11, 2017. The Bend City Council holds ultimate decision making authority for the adoption of the plan.

5. Additional Communications

As mentioned, the project team also presented project and DSAC updates to the Bend Economic Development Advisory Board and the Bend Planning Commission for their input and review in April 2017. Presentations were also provided to the Old Bend Neighborhood Association, River West Neighborhood Association, and the Downtown Bend Business Association during the study period.

6. Community Open House

A final **Community Open House** was held on May 11, 2017, to share DSAC Draft Strategies for downtown parking management with the community and seek community input for possible further refinement of DSAC parking strategies recommendations. A full summary of the community input received at the Open House can be found in APPENDIX E of the supplemental Appendix Report created to accompany this Final Report.

Additional Information

For additional information, including meeting summaries, as well as draft and final reports, please see the project website at <http://www.bendoregon.gov/parkingstudy>.

V. GUIDING PRINCIPLES – ELEMENTS OF PARKING MANAGEMENT

Parking is a vital tool in any downtown's economic development toolbox, and must be properly managed to ensure an efficient system of access that meets the needs of priority users. In downtown Bend, the priority user of the City-owned parking system has been identified as the customer and visitor. The Downtown Stakeholder Advisory Committee (DSAC) concluded that the goal of parking management in downtown should be:

"To support a vibrant, diverse, attractive, and uniquely identifiable downtown. The components of this plan need to be simple and intuitive for the user. The parking system must be safe, secure, financially sound and well-integrated with all modes of access to downtown. Access to downtown should not be cost-prohibitive to downtown users."

The Guiding Principles outlined here were developed by the DSAC over several work sessions, further informed through public outreach, and approved by the Bend City Council in August 2016. They are designed to encourage the use of parking resources to support economic development goals, and to effectively serve the diversity of people who come to downtown Bend. They have been organized into seven categories:

- City Role and Coordination
- Priority Users
- Active Capacity Management
- Information Systems (Supply- and Customer-Based)
- Integration with Other Modes
- Planning for Future Supply
- Financial Viability

Ideally, these Guiding Principles will establish a basis for consensus and provide near- and long-term direction for parking management in downtown Bend. They are presented here in no particular order or priority.

A. City Role and Coordination

1. **Primary Role (City of Bend)**. The City's primary role in providing parking will be to **prioritize and plan for customer and visitor access downtown, and facilitate residential and guest access in adjacent neighborhoods.**

The cost of providing parking, especially off-street, is very high, and the City cannot be responsible for providing parking to all users. The City must prioritize its public system for customers and visitors in commercial areas, and for residents and their guests in residential areas.

- 2. Primary Role (Private Sector). The private sector’s primary role will be to provide parking for employees and residents of the downtown.**

The private sector must take a lead role in providing transportation and parking options for downtown residents and employees. The City must complement this role through partnerships with the private sector, and by providing safe, reliable, and effective non-auto access to downtown.

- 3. Centralized Management. Management of public parking will be centralized to ensure optimal use.**

The City must be focused, coordinated, and strategic in the daily management of its parking supply, and deliver near- and long-term parking solutions that include participation from the private sector. This should be implemented through a Parking Services Division, led by a qualified and well-supported Parking Manager.

- 4. Effective Communications. High-quality, user-friendly communications will be provided to ensure customers and visitors can easily access parking near their destination.**

The Parking Services Division must ensure that signage and wayfinding direct users to available parking suited to their needs. This may require real-time monitoring of available parking. Parameters of use (permitted length of stay, pricing, etc.) must be clear and not detract from the image of downtown. To the greatest degree possible, communications systems should be reliable and easy to use and understand.

- 5. Stakeholder Support. A representative body of affected private and public constituents will routinely inform decision-making.**

Active participation by those affected guarantees understanding of and agreement on parking management. This will be best accomplished through a Parking Advisory Committee that reviews performance, serves as a sounding board for issues, and acts as a liaison to the broader stakeholder community.

- 6. Coordinated Management. Parking will be managed to support the unique character of existing and emerging downtown neighborhoods. Where appropriate, parking will be administered by defined area or district.**

The downtown comprises several unique economic enclaves (e.g., the core, areas with adjacent parks and periphery, buffer areas in commercial neighborhoods). As the areas differ economically, so too do the character and needs of their patrons. This may require a management approach tailored to each area.

B. Priority Users

1. **On-Street System (Downtown).** The most convenient on-street parking will be prioritized for customers and visitors.

The on-street parking system in the downtown must be formatted to ensure turnover and minimize conflicts between priority and other users. For the most part, employees and downtown residents should not park on-street, particularly when demand for customer/visitor parking is high. When demand is low or there is a surplus of available parking, the system can accommodate non-priority users.

2. **On-Street System (Adjacent Neighborhoods).** The most convenient on-street parking will be prioritized for residents and their guests.

As with on-street parking in the downtown, neighborhood parking must be formatted to ensure priority access and minimize conflicts between residential and other users. Residential areas may encompass public buildings such as churches or libraries; their users are also considered residents or guests. For the most part, employees should not park on-street, particularly when demand for resident/guest parking is high. When demand is low or there is a surplus of available parking, the system can accommodate non-priority users.

3. **On-street Turnover.** The on-street parking system is a finite resource and will be managed to ensure a turnover rate that supports a vital business district.

Growth in parking demand downtown will, over the long term, need to be accommodated by use of off-street locations. Longer-term parking, as by employees, must be managed so as not to conflict with short-term customer parking, particularly on-street. This will require parallel efforts by the City and private sector to increase alternative mode options.

4. **Off-street System.** Off-street parking resources, both public and private, will be coordinated to meet demand that cannot be met by safe and reliable walking, biking, transit use, and carpooling/ridesharing.

All parking strategies, particularly those that affect employees and residents, should be coordinated with the City's broader transportation demand management goals and objectives to ensure that users have reasonable options available. This effort should be pursued as a partnership between the City and the private sector.

C. Active Capacity Management

1. **Optimize Utilization.** The public parking system will be managed using the 85% Rule to inform and guide decision-making.

When 85% of the parking supply is routinely occupied during peak periods, more intensive and aggressive management strategies are called for. This “85% Rule” will facilitate decisions regarding time limits, enforcement, and other issues related to capacity management.

2. **Resolve Constraints. Parking demands in excess of 85% will require best practices to minimize constraints.**

Strategies to be triggered by the 85% Rule will be identified in the Downtown Strategic Parking Management Plan. The City and Parking Advisory Committee will commit to moving forward with recommended strategies when parking demand requires them. Changes to the status quo can be difficult, but continued constraints in parking and access will adversely impact the downtown’s success and ability to absorb growth.

3. **Shared Off-Street Parking. Shared parking will be encouraged in areas where parking is underutilized. This will require partnership with owners of private parking.**

Private parking facilities in some downtown locations may be underutilized. Efforts should be made to facilitate shared-use agreements and direct excess parking demand to these facilities. Parking data collected by the City should include capacity assessments of private facilities.

4. **Capacity Expansions. Capacity will be created through strategic management of existing public and private parking, reasonable enforcement, leveraging parking with alternative modes, and new supply.**

Active effort must be made to manage the parking system on a daily basis. This will require partnerships with the private sector to leverage existing off-street supplies and coordinate management to support the development and growth of alternative modes. Capacity expansion can be achieved through strategies that increase turnover and/or encourage alternative mode use, as well as code provisions and regulations that govern the creation of parking. These types of actions should be fully evaluated prior to building new parking supply.

D. Information Systems (Supply- and Customer-Based)

Supply-Based

1. **Monitor and Report Utilization. Performance measurements and reporting will be used to facilitate decision-making.**

Committing to a routine, objective system of measurement and reporting ensures that decision-making will be informed. Key metrics include occupancy, turnover, average duration of stay, rate of violation, and customer input. Performance monitoring also provides a basis for routine evaluation of program effectiveness.

Customer-Based

2. **Product Quality.** The on- and off-street parking systems and related programs, such as communications, will be safe, reliable, user-friendly, and attractive. They will complement the quality of downtown and attract visitors and customers.

The quality of the parking system and its supporting programs should reflect the quality of downtown Bend itself. On-street parking should be uniformly managed and enforced to ensure an intuitive, reasonable sense of time limits. Off-street facilities should be of uniform quality and identity to create a clear sense of safety, convenience, understandability, and integrate with the pedestrian environment. Communications systems should be cutting-edge, professional, and effectively coordinated. All systems should, to the highest degree possible, be reliable and easy to use and understand.

3. **System Communications.** Communications will be uniform and strategically coordinated. Existing information resources will be improved and new ones created.

Systems to improve understanding, awareness, and ease of use of parking should be upgraded. A clear schedule should be maintained for the dissemination of information, possibly coordinated through a partnership between the City, the Downtown Bend Business Association, and other entities. High-quality communication and marketing materials should be integrated into a comprehensive package of services to accurately inform and guide the parking public.

4. **Branding and Wayfinding.** The existing wayfinding system that links parking assets and provides directional guidance will be upgraded and expanded, preferably using a common brand/logo.

Parking resources should be clearly identified and explained through branding and signage. A common brand unifies marketing materials, signage systems, and other communications, simplifying customer recognition and use of the system.

E. Integration with Other Modes

1. **Downtown Multi-Modal.** Use of alternative travel modes, particularly by employees, will be encouraged and facilitated.

Private vehicles should not be the only option for accessing the downtown. Every parking stall occupied by an employee means a lower rate of turnover and less access for customers and visitors. Employees should be given reasonable access to parking, but encouraged to use alternative modes that include walking, biking, transit, and ridesharing. Nearby residents should be encouraged to use Bend's sidewalk and trail system. Community members from greater distances should be encouraged to bicycle and ride transit. Providing safe and reliable non-auto modes of access relieves pressure on the parking system, enhances the attractiveness of downtown, and accommodates nearly all types of users. This will require active partnerships with the private sector.

2. **Bicycle Parking. The broader bicycle network will be enhanced by increasing bike parking on- and off-street.**

The City of Bend's bike parking network should be as effectively formatted as the auto parking system. On- and off-street parking facilities for bicycles are efficient and low-cost.

3. **Connections to Remote Vehicle Parking. Remote parking locations and transit/bike connections will be explored to minimize the need for new parking structures.**

As the City explores new parking supply options, scenarios should include remote locations connected by transit and bike networks. Such options may be more cost-effective than structured parking and/or may be necessitated by land supply constraints in the downtown.

F. Planning for Future Supply

1. **Planning and Funding. Planning for future parking supply will be strategic and routinely evaluated to ensure the City is ready to respond to growth. Funding for new supply will require a varied package of resources and partnerships.**

The City must plan for its future needs and initiate long-term planning efforts to assemble funding and partnerships necessary to meeting them. Future needs include parking for bicycles as well as cars, and multiple modes should be addressed in any system. When considering parking supply needs, all modes should be evaluated in the effort to increase access to downtown.

G. Financial Viability

1. **Fiscal Stewardship. All parking operations will be financially sustainable.**

Parking revenues should cover the cost of operations, as well as provide a reasonable surplus. Ensuring the highest quality of access, convenience, safety, system maintenance, and service delivery will require multiple sources of revenue. These may include leases, enforcement fees, meter and other user fees, urban renewal funds, and/or partnerships with the private sector.

VI. PARKING INVENTORY SUMMARY

The consultant team inventoried the entire supply of on- and off-street parking in the downtown. This section summarizes that effort.⁴

Study Area

The study area was determined by the City of Bend and the consultant team during the initial project scoping process and approved by the DSAC at its April 7, 2016 meeting.

It is generally bounded by NW Portland Avenue on the north, with a southern boundary that includes portions of NW Franklin Avenue, NW Lava Road, and NW Idaho and Kansas Avenues. Parkway is on the east, with the western boundary moving from a small section of NW Riverside Boulevard north along the Deschutes River to NW Olney Avenue. **Figure A** (page 20) illustrates the study area.

It is important to note that the inventory study area (solid black line in **Figure A**) incorporates an area larger than the current downtown Parking District (broken black line). The purpose of the larger area was to capture information on parking patterns in areas adjacent to the Parking District, providing information on spillover, differences in duration of stay and/or occupancy, etc.


The study area also includes all parking that falls within the Downtown Economic Improvement District. The Downtown EID is represented by a solid red line in **Figure A**.

Total Supply (On- And Off-Street)

There are 5,803 total parking stalls in the study area, of which 1,805 are on-street and 3,998 off-street. The off-street stalls are distributed among 158 unique parking facilities.

⁴ Attachments B and C at the end of this report provide a detailed Parking Utilization Summary that includes the complete inventory and utilization analysis for both the spring and summer 2016 data collection efforts. This section provides a shortened version of those reports.

Figure A: Parking Area Study Boundary



2016

-  Parking Study Area
-  Economic Improvement District
-  Bend Parking District

RICK WILLIAMS CONSULTING
Parking & Transportation



Parking Inventory (On-Street)

On-street parking in the study area encompasses a total of 1,805 stalls. Table 1 analyzes on-street stalls by type for both the total inventory and the sample used in the 2016 parking study. The sample included 1,333 stalls (73.9% of the total supply) and represents a statistically valid subset of all on-street stalls (see Section VIII. KEY FINDINGS – PARKING UTILIZATION).

Table 1: Downtown Bend: On-Street Parking Inventory (total and sampled)

Stalls by Type	Inventory Area Stalls	% of Total	Sampled Stalls	% of Total
15 Minutes	22	1.2%	20	1.5%
30 Minutes	1	< 1%	1	< 1%
30 Minutes (Unless Otherwise Specified)	10	< 1%	10	< 1%
2 Hours	706	39.1%	678	50.9%
2 Hours (Unless Otherwise Specified)	242	13.4%	242	18.2%
No Limit	766	42.4%	326	24.5%
ADA 'Accessible'	41	2.3%	39	2.9%
Authorized Vehicles Only	9	< 1%	9	< 1%
Police Only	8	< 1%	8	< 1%
Total Parking Supply	1,805	100%	1,333	73.9%

As indicated in the table, on-street parking in the downtown includes a mix of time limits comprising of nine categories.

- All on-street parking is currently free.
- The most common stall type is No Limit, constituting 42.4% of the total supply. No Limit parking is unsigned.
- The second most common stall type allows for two-hour parking and comprises 39.1% of the total supply.
- Two-hour stalls marked "Unless Otherwise Specified" make up 13.4% of the total supply. They generally allow for a two-hour stay, but also accommodate employees with authorized permits, who may use these stalls for all-day parking.

- The number of stalls allowing all-day stays (i.e., No Limit and 2-Hour permit stalls) represents a large portion of the supply at 55.8%. When compared to on-street parking in other successful downtowns, the number of long-term stalls in Bend is unusual, especially given that customers and visitors have been envisioned as the priority users.

Summary (On-Street Inventory)

The on-street parking supply in downtown Bend covers a large area and comprises more than 1,800 stalls. Two-hour time-limited stalls in the core represent just 39% of the total supply. With more than half the supply given over to No Limit and employee permit parking, the current format favors long-term parking, unusual for a downtown with such a high level of retail activity. Observed occupancy levels are relatively high at present (see **Section VIII. KEY FINDINGS – PARKING UTILIZATION**), indicating that reformatting time limits to include more short-term parking should be considered as a means to support retail development and growth.

Parking Inventory (Off-Street)

During the inventory process, 158 off-street parking facilities with a total of 3,998 stalls were identified in the study area. For data collection purposes, 46 sites comprising 2,650 stalls were sampled, about 66% of the total supply. Sites were selected based on size, type, and location to ensure a representative sample.

Table 2 briefly summarizes the total and sampled off-street inventories. **Figure B** (page 24) color-codes sites by size. Actual use characteristics of the sampled off-street sites are summarized in **Section VIII. KEY FINDINGS – PARKING UTILIZATION**. A complete list of all 158 sites is provided in **Appendix A and B** of the Supplemental Appendix Report created to accompany this Final Report.

Table 2: Downtown Bend: Off-street Parking Inventory

Stall Type	All Stalls	% of Total	Sampled Stalls	% of Total
Off-Street	3,998 (158 sites)	100%	2,650 (46 sites)	66.3%

Summary (Off-Street Inventory)


There is a significant amount of parking in off-street facilities in the downtown. These lots account for a very large percentage of the downtown’s surface area, and present themselves as opportunity sites for future development. The majority of off-street parking is under private ownership. The City controls eight of the 158 parking facilities in the downtown, totaling 989 stalls, about 25% of the total off-street supply. City parking lots include:

Table 3: City Parking Facilities

Parking Facility	Stalls
Public Garage (NW Lava)	547
Newport Lot (NW Newport Avenue)	104
Mirror Pond North and South	176
NW Greenwood @ NW Wall Street	33
City Hall	20
Surface lot between NW Louisiana/NW Kansas	41
NW Louisiana across from City Hall	68

The current balance of private and public parking is not unusual for downtowns, but does mean that shared-use agreements can be more complex, involving negotiations and partnerships with individual owners of private lots.

Figure B: Downtown Bend: Study Area - Off-street Parking Supply



2016

Parking Study Area	Over 100 stalls	1 - 25 stalls
Parking Inventory Area	76 - 100 stalls	Unknown
Bend Parking District	51 - 75 stalls	
RICK WILLIAMS CONSULTING Parking & Transportation	26 - 50 stalls	

0 105 210 420 630 840 Feet


VII. MEASURING PERFORMANCE

Parking is considered to be constrained when 85% or more of the available supply is routinely occupied during the peak hour. In a constrained system, finding an available spot is difficult, especially for infrequent users such as customers and visitors. This can cause frustration and negatively affect perceptions of the downtown. Continued constraint can make it difficult to absorb and attract new growth, or to manage fluctuations in demand—for example, seasonal or event-based spikes.

Occupancy rates of 55% or less indicate that parking is readily available. While availability may be high, this may also indicate a volume of traffic inadequate to support active and vital businesses.

Occupancy rates between these two thresholds indicate either moderate (55% to 69%) or efficient (70% to 85%) use. An efficient supply of parking shows active use but little constraint that would create difficulty for users. Efficient use supports vital ground-level businesses and business growth, is attractive to potential new users, and is able to respond to routine fluctuations.

RWC's analysis of parking in Bend uses these categories to evaluate the performance of the system.



VIII. KEY FINDINGS – PARKING UTILIZATION

Data on utilization and occupancy of the parking system was collected over two days in each of two seasons, spring and summer. Data collection days were selected in consultation with the City and the DSAC, chosen to represent a typical day of robust activity during spring and summer. Survey days were:

Spring 2016

- Thursday, April 28
- Saturday, April 30

Summer 2016

- Wednesday, July 20
- Friday, July 22

This section summarizes key findings from that effort.⁵

A. On-Street Data Collection - Methodology⁶

Surveyors recorded the license plate numbers of all vehicles parked in the study area during each hour of the 10-hour period between 10:00 AM and 7:00 PM. This was done for each of the four survey days. As described in the Parking Inventory Summary (Section VI. PARKING INVENTORY SUMMARY), a total of 1,333 on-street stalls were surveyed, representing 73.9% of all on-street parking in the study area, a statistically valid sample.

All survey days were unaffected by adverse weather, as they were dry and sunny with temperatures in the high 70s–low 80s.

B. Off-street Data Collection - Methodology

Off-street facilities were surveyed on the same days and in the same manner over the same 10-hour period. As described in the Parking Inventory Summary (Section VI. PARKING INVENTORY SUMMARY), a total of 2,650 stalls were surveyed across 46 unique lots, representing 66.3% of all off-street parking in the study area, a statistically valid sample.


⁵ As with information related to the parking inventory, Attachments B and C, at the end of this report, provide detailed Parking Utilization Summary Data Reports.

⁶ A detailed technical memorandum (dated 3/23/2016) outlining the complete data collection methodology is provided in Attachment D at the end of this report.

C. On-Street Occupancies – Spring 2016 (Thursday/Saturday)

Figure C provides an hour-by-hour look at occupancy performance for each of the spring 2016 survey days (April 28 and April 30).

Figure C: Downtown Bend Hourly On-street Utilization (Spring 2016)



Weekday (Thursday, 4/28/2016)

- The weekday peak hour for on-street parking is from 2:00 to 3:00 PM. During this hour, 977 (73.3%) stalls are occupied, leaving 356 stalls empty.
- Occupancy rates decline in every hour between 3:00 PM and 6:00 PM before rising at 7:00 PM.
- Based on the performance measurement described in Section VII. MEASURING PERFORMANCE, peak parking utilization is efficient (between 70% and 85%).
- There are certain block faces and areas of the downtown where parking is constrained, which can create access problems for users (see Figure D, below).

Weekend (Saturday, 4/30/2016)

- The weekend peak hour for on-street parking is from 7:00 to 8:00 PM. During this hour, 762 stalls (57.2%) are occupied, leaving 571 stalls empty.

- Occupancy rates increase in eight of 10 hours, dropping slightly between 4:00 and 6:00 PM.
- Overall weekend vehicle activity is much less than weekday activity.
- Weekend evening activity (6:00 to 8:00 PM) is comparable to the weekday.
- Based on the performance measurement described in **Section VII. MEASURING PERFORMANCE**, parking utilization for most of the operating day is low (less than 55%), rising to moderate in the evening.
- Even with lower occupancy rates overall; there are certain block faces and areas of the downtown where parking is constrained, which can create access problems for users (see **Figure E**, below).


D. Peak-Hour Occupancy – Heat Map (Spring)

Figure D and **Figure E** (pages 29 and 30) illustrate on- and off-street peak hours for each of the spring survey days using a “heat map” format. Heat maps use color to show degree of use by block face, based on the diagram in **Section VII. MEASURING PERFORMANCE** above.



As both maps illustrate, there are concentrated pockets of constrained activity (an occupancy rate of 85% or greater) in the on-street system. Constrained areas can be found during the weekday in the south end of downtown and within the core north of NW Minnesota. On the weekend, constraints are concentrated in the core area between NW Franklin and NW Greenwood.

Though the maps show areas of low to moderate use, consistent with the occupancy rates in **Figure C** above, clusters of very high activity can create a perception by users of constraints in specific areas of the downtown.

Figure D: Downtown Bend Weekday (4/28/2016) Peak Hour Occupancy Heat Map



Combined Parking Utilization

	> 85%		> 85%
	84% - 70%		84% - 70%
	69% - 55%		69% - 55%
	< 55%		< 55%
	< 55%		Construction
	Parking Study Area		No Parking
	Bend Parking District		


RICK WILLIAMS CONSULTING
Parking & Transportation

April 28, 2016

1:30 - 2:30 PM
Peak Hour

0 95 190 380 570 760 Feet


Figure E: Downtown Bend Weekend (4/30/2016) Peak Hour Occupancy Heat Map



E. On-Street Occupancies – Summer 2016 (Wednesday/Friday)

Figure F provides an hour-by-hour look at occupancy performance for each of the summer 2016 survey days (July 20 and July 22).

Figure F: Downtown Bend Hourly On-street Utilization (Summer 2016)



Weekday (Wednesday, 7/20/2016)

- The peak hour for Wednesday on-street parking is from 2:00 to 3:00 PM. During this hour, 1,077 stalls (80.8%) are occupied, leaving just 256 stalls empty.
- Occupancy rates decline in every hour between 3:00 and 7:00 PM, falling from 80.7% to 63.1%.
- Based on the performance measurement described in Section VII. MEASURING PERFORMANCE, peak parking utilization is efficient (between 70% and 85%). When compared to the spring weekday peak of 73.3%, summer occupancy rates are 7.5 percentage points higher.

Weekday (Friday, 7/22/2016)

- The peak hour for Friday on-street parking is from 12:30 to 1:30 PM. During this hour, 996 stalls (74.7%) are occupied, leaving 337 stalls empty.

- Occupancy rates decrease in each hour between 2:00 and 6:00 PM, from 71.2% to 58.5%, then rise slightly to 60.6% at 7:00 PM.
- Overall, Friday vehicle activity is moderately lower than on Wednesday.
- Based on the performance measurement described in **Section VII. MEASURING PERFORMANCE**, peak parking utilization is efficient (between 70% and 85%).

F. Peak-Hour Occupancy – Heat Map (Summer)


Figure G and **Figure H** (pages 33 and 34) illustrate on- and off-street peak hours for each of the summer survey days in heat map format.

As both maps illustrate, there are concentrated pockets of constrained activity (an occupancy rate of 85% or greater) in the on-street system. For both days, constrained activity is significantly more widespread than in the spring survey.

Wednesday constrained areas include most block faces in the area between NW Greenwood and NW Idaho Avenues (see **Figure G**). This constrained area extends east to NW Harriman. Areas east of NW Harriman (between NW Greeley and NW Kearney Avenues) are much less constrained.

On Friday, constraints are similar to those demonstrated on Wednesday in the area between NW Greenwood and NW Idaho Avenues (see **Figure H**). However, the area east of NW Harriman (between NW Greeley and NW Kearney Avenues) is less constrained than on Wednesday.

Figure G: Downtown Bend Wednesday (7/20/2016) Peak Hour Occupancy Heat Map



Combined Parking Utilization

-  Parking Study Area
-  Bend Parking District

RICK WILLIAMS CONSULTING
Parking & Transportation

-  > 85%
-  84% - 70%
-  69% - 55%
-  < 55%

July 20, 2016

2:30 - 3:30 PM
Peak Hour





Figure H: Downtown Bend Friday (7/22/2016) Peak Hour Occupancy Heat Map



Combined Parking Utilization

Parking Study Area	> 85%	> 85%
Bend Parking District	84% - 70%	84% - 70%
RIK WILLIAMS CONSULTING Parking & Transportation	69% - 55%	69% - 55%
	< 55%	< 55%
		Construction
		No Parking

July 22, 2016
12:30 - 1:30 PM
Peak Hour

0 95 190 380 570 760 Feet

G. On-Street: Other Characteristics of Use (Seasonal Comparison)

Table 4 compares additional on-street performance metrics for 2016, including average duration of stay, total number of unique vehicles, number of vehicles moving to evade citations, and rate of violation.

Table 4: Downtown Bend- Characteristics of Use (Comparative by Season and Day)

Survey Day (season)	1 Average Length of Stay (including permit users)	2 Average Length of Stay (excluding permits)	3 Unique Vehicles	4 Moving to Evade	5 Turnover Rate (Including permits / excluding permits)	6 Violation Rate
Wednesday (Summer)	2 hr / 4 mins	1 hr /40 min	4,677	210	4.80 / 5.36	9.6%
Friday (Summer)	2 hr / 0 mins	1 hr /36 min	4,318	184	4.98 / 5.45	8.4%
Thursday (Spring)	2 hr / 4 min	1 hr /37 min	4,156	199	4.85 / 5.52	8.8%
Saturday (Spring)	1 hr / 43 min	1 hr /30 min	3,307	124	5.01 / 5.81	8.,4%

1. Average Duration of Stay (including permit users)

Bend allows holders of valid permits, typically employees, to park in stalls designated “2 HR – Unless Otherwise Specified.” The average duration of stay for all users reflects the impact of permit holders. As illustrated in Table 4, Column 1, the average duration of stay for all users does not vary much by season or day—for the most part; users are staying about two hours. The average stay on Saturday in spring is one hour and 43 minutes, which is most likely reflects a lower number of employees in the downtown.

2. Average Duration of Stay (excluding permit users)

A more accurate average duration of stay can be calculated when observed permits holders are removed from the equation. As Column 2 in the above table demonstrates, average stays drop 13-24 minutes, ranging from a high of one hour and 40 minutes on the summer Wednesday to a low of one hour and 30 minutes on the spring Saturday. These findings indicate that the current two-hour time-limited stalls meet the needs of the average customer or visitor.

3. Number of Unique Vehicles

The recording of license plate numbers allows us to identify the total number of unique vehicles using the on-street system on a given survey day.⁷ As Column 3 in the above table shows, 4,677 unique license plates were recorded on the summer Wednesday between 10:00 AM and 7:00 PM. This translates to approximately 468 vehicles arriving each hour over the course of an average business day in the study area. On the summer Friday, volume dropped by about 359 cars to 4,318.

It is clear that activity is much higher in summer than in spring. The spring Thursday saw 4,156 vehicles access the system, a difference of 521 vehicles (about 12.5%) when compared to the summer peak.

The lowest volume of activity was recorded on the spring Saturday, when 3,307 unique license plates were observed—a drop of 849 vehicles from the spring peak of 4,156.

Given that the studies were conducted using an inventory sample of 1,333 parking stalls, these daily totals indicate that overall vehicle activity is robust across all four data sets.

4. Moving to Evade

“Moving to evade” refers to moving vehicles between time-limited on-street stalls over the course of a day in order to avoid being cited. This metric can indicate abuse of the system, particularly if those moving their vehicles are employees. Users who shuffle their vehicle from one stall to the next reduce the number of on-street parking opportunities for visitors and customers, creating an artificial constraint on the system. Ideally, those wanting to park for longer periods of time would be directed to the permit program or off-street lots, preserving on-street stalls for higher turnover uses.

As Column 4 of Table 4 indicates, the number of vehicles found to be moving to evade ranged from 124 on the spring Saturday to 210 on the summer Wednesday. At the upper end, this represents 4.4% of all vehicles using the on-street system; at the lower end, it is 3.7%.

When these numbers are combined with the number of permits allowing all-day parking on-street, it can be argued that a meaningful percentage of long-term parkers are using the short-term supply.

⁷This does not represent all vehicles in the study area, as license plate numbers were not recorded in off-street facilities.

When these numbers are combined with the number of employee permits allowing all-day parking on-street, it can be argued that a meaningful percentage of long-term users are using the short-term supply. Moving these vehicles into the off-street system would reduce abuse of short-term stalls and improve turnover and visitor access on-street.

5. Turnover: Efficiency of the Parking System

In most cities, the primary time limit allows for calculation of an *intended turnover rate*. For example, if the intended use for a stall is two hours, the stall should be expected to turn over 5.0 times during a 10-hour survey period.⁸ If the turnover rate were demonstrated to be less than 5.0, the system would not be operating at its intended efficiency. A rate in excess of 5.0 would indicate a system that is operating at or above its intended efficiency.

As summarized in Column 5 of Table 4, the on-street parking system in downtown Bend maintains an average turnover rate that ranges from 4.80 on the summer Thursday to 5.01 on the spring Saturday when all users are included. Three of the four study days fall below the recommended industry standard of 5.0.

However, when permit holders are excluded, turnover rates exceed the industry target on all four survey days, from a low of 5.36 on the summer Thursday to a high of 5.81 on the spring Saturday.

Another way to look at the impact of turnover on vehicle trip capacity is to quantify the difference between the lowest observed rate of 4.80 (summer Wednesday, including permits) and the highest rate of 5.81 (spring Saturday, excluding permits). Table 5 illustrates this.

Table 5: Downtown Bend – Turnover and Vehicle Trip Capacity

Turnover Rate (TO)	Stalls Sampled (STALLS)	Employee Permits Parked on-street (peak hour)	Potential Vehicle Trip Capacity (TO X STALLS)
5.81 (4/30/2016)	1,333	17	7,744
4.80 (7/20/2016)	1,333	151	6,398
Net Daily Difference in Vehicle Trip Capacity			1,346

⁸ Calculated by dividing the average time stay into the 10-hour study day.

Permit holders are lowering the average rate of turnover, which translates into fewer vehicles having access to the on-street supply.

As the table demonstrates, use of employee permits is adversely affecting potential access by customers or visitors. Permit holders are lowering the average rate of turnover, which translates into fewer vehicles having access to the on-street supply. If permit parking were significantly reduced, the system could serve an additional 1,346 vehicles per day.

6. Excessive Time Stay (Rate of violation)

The parking industry sets a best-practice target for violations of 5-8% of unique vehicles.⁹ A violation is defined as a single vehicle parked in excess of the posted time limit. In Bend, the violation rate ranges from 8.4% to 9.6% (see Column 6, Table 4), just exceeding the high end of the recommended range. Small adjustments in deployment of enforcement personnel should be considered to lower the rate to less than 8.0%, particularly in summer when on-street occupancy rates are highest and supplies constrained.

A violation is defined as a single vehicle parked in excess of the posted time limit. In Bend, the violation rate ranges from 8.4% to 9.6%, just exceeding the high end of the recommended range.

Summary (on-street)

Data indicates that the on-street parking system has areas of constraint that can create access issues. Constraints vary by season, with summer months generating the most significant issues.

Overall, parking behavior does not vary much by day or season. Customer duration of stay is consistent at less than 2 hours, as is the level of compliance with time limits. The format of time limits is heavily weighted towards long-term stays, with more than 55% of the on-street supply in the study area dedicated to either No Limit parking or parking that allows all-day stays with a valid permit. The effect of this has been to reduce turnover of the supply and limit the overall capacity for vehicle trips to the downtown. A strategy to move permit holders into off-street facilities or use of alternative modes should be pursued.

Enforcement is good, but rates of violation are beyond the 5-8% range the parking industry recommends for efficient parking systems). In addition, as many as 210 vehicles per day are moving to

⁹ This is not an indication of the number of actual tickets that would be written, only a standard to measure whether existing enforcement deployment and protocols are maintaining a best-practice range of compliance.

avoid citations, a portion of which likely belong to employees not in the permit program. This further reduces turnover and contributes to parking constraints. More strategic deployment of enforcement personnel can address this.

Heat map data demonstrates that parking is very constrained on weekdays in summer, particularly between NW Greenwood and NW Idaho Avenues west of NW Harriman. Areas east of NW Harriman demonstrate lower occupancy rates, which is replicated in spring. This area should be considered for different treatment as new management strategies are developed.

H. Off-Street Parking Occupancy


A sample of 46 lots comprising 2,650 stalls was selected for data collection. This sample represents 66.3% of all off-street parking in the study area, and accurately reflects the overall system in terms of type, size, and location. As with the on-street system, occupancy counts were conducted at each lot every hour between 10:00 AM and 7:00 PM; unlike the on-street survey, however, license plate numbers were not recorded.

Heat map representations of the off-street system may be found on pages 29 and 30 (spring) and pages 33 and 34 (summer). Detailed data findings for each surveyed lot are provided in Spring and Summer Data Summary Reports located **Appendix A and B** of the Supplemental Appendix Report created to accompany this Final Report.

Spring 2016 (Thursday/Saturday)

Figure I provides an hour-by-hour look at occupancy performance for each of the spring 2016 survey days (April 28 and April 30).

Figure I: Downtown Bend: Off-street Hourly Occupancy Rates (Spring Comparative)



Weekday (Thursday, 4/28/2016)

- The peak hour for weekday off-street parking is from 3:00 to 4:00 PM. During this hour, 59.7% of off-street stalls are occupied.
- The very flat level of activity between 10:00 AM and 4:00 PM indicates employee use.
- Occupancy rates decline significantly after 5:00 PM.


Weekend (Saturday, 4/30/2016)

- The peak hour for weekend off-street parking is from 7:00 to 8:00 PM. During this hour, 34.6% of off-street stalls are occupied.
- As with the weekday data, flat levels of activity throughout the day, particularly between 10:00 AM and 5:00 PM, indicates employee use.
- Occupancy rates increase after 5:00 PM, indicating new users coming into the downtown for evening activities.

Summer 2016 (Wednesday/Friday)

Figure J provides an hour-by-hour look at occupancy performance for each of the summer 2016 survey days (July 20 and July 22).

Figure J: Downtown Bend: Off-street Hourly Occupancies (Summer Comparative)



Wednesday (July 20, 2016)

- The peak hour for Wednesday off-street parking is from 4:00 to 5:00 PM. During this hour, 65.4% of off-street stalls are occupied.
- Occupancy rates decline between noon and 2:00 PM, increasing between 3:00 PM and 5:00 PM, then dropping steadily through 7:00 PM.
- At the peak hour, there are 917 empty stalls in the surveyed off-street lots. When extrapolated to the entire off-street supply, this indicates approximately 1,383 stalls empty at the peak hour (see summarized findings in Table 6, below).

Friday (July 22, 2016)

- The peak period for Friday off-street parking is from 1:00 to 3:00 PM. During these hours, 60.8% of off-street stalls are occupied.
- Occupancy rates decrease each hour between 3:00 and 7:00 PM, falling from 56.3% to 38%.
- At the peak hour, there are 1,038 empty stalls in the surveyed off-street lots. When extrapolated to the entire off-street supply, this indicates approximately 1,567 stalls empty at the peak hour (see summarized findings in Table 6, below).

Overall, the off-street system shows moderate use. In just the sampled supply of 2,650 stalls, the number of empty stalls in the peak hour ranges from 917 on the summer Wednesday to 1,733 on the spring Saturday. If the sample data is extrapolated to the entire supply, this range increases to 1,383-2,615. Table 6 summarizes this finding.

Overall, the off-street system shows moderate use.

Table 6: Downtown Bend: Off-street Supply Capacity (Comparative Season/Day)

Survey Day (season)	Peak Hour (Occupancy)	Empty Stalls in Surveyed Supply (extrapolated)	City Garage
Wednesday (Summer)	4:00 – 5:00 PM <i>(65.4% occupancy)</i>	917 empty stalls <i>(1,383 extrapolated)</i>	174 empty stalls (< 68% occupied)
Friday (Summer)	1:00 – 3:00 PM <i>(60.8% occupancy).</i>	1,038 empty stalls <i>(1,567 extrapolated)</i>	156 empty stalls (< 71% occupied)
Thursday (Spring)	3:00 – 4:00 PM <i>(59.7% occupancy)</i>	1,067 empty stalls <i>(1,611 extrapolated)</i>	286 empty stalls (< 50% occupied)
Saturday (Spring)	7:00 – 8:00 PM <i>(34.6% occupancy)</i>	1,733 empty stalls <i>(2,615 extrapolated)</i>	285 empty stalls (< 50% occupied)

Data from the City’s public garage alone demonstrates that parking in this key facility is underutilized. Here the number of empty stalls at the peak hour ranges from 156 on the summer Friday to 285 on the spring Saturday.

Summary (off-street)

The 2016 data analysis of off-street parking in downtown Bend indicates that the system is operating at a moderate level of use. Regardless of season or day, at least 35% of the off-street supply is empty at the peak hour. Extrapolated to the entire supply, this means a minimum of 1,383 stalls are going unused during a period when the on-street system is both constrained and heavily used by employees and long-term parkers. This unused supply is a resource that could be capitalized on to manage and support future growth in parking demand.

IX. RECOMMENDED DOWNTOWN PARKING MANAGEMENT STRATEGIES

From discussions with the City and stakeholders, specific parking management strategies have been identified and are recommended for implementation. They are informed by evaluation of current policies and practices, stakeholder outreach, discussions with the DSAC, analysis of 2016 parking utilization data, and the consultants' experience with industry best practices.

Twenty-eight strategies have been developed for consideration. Strategies for operations and infrastructure are intended to be phased in over 48 months, beginning with adoption of the plan. They are presented in an order whereby each strategy builds upon the work and outcomes of previous strategies. Near-term strategies are intended to focus management and decision-making, leverage opportunities in the existing supply of parking, reformat pricing structures, better communicate options and expectations, and continue to use data to facilitate decision-making. Longer-term strategies include new approaches to pricing, infrastructure and access capacity needs, and funding.

Any and all strategies can be implemented on an accelerated schedule or be reordered based on opportunity and resources.

The discussion below is organized as follows:

- Policy and Organizational Action Strategies: Immediate/Near Term (0-12 months)
- Recommended Parking Management Strategies: Phase 1 (12 – 24 months)
- Recommended Parking Management Strategies: Phase 2 (24 – 48 months)

A summary of all recommended strategies is attached as an Implementation Schedule at the end of this report (ATTACHMENT A).

Cost estimates associated with strategies, where listed, are based on the consultant's knowledge and experience. Dollars are based on 2016 and may not reflect the current prices for services or materials available in Bend. The estimates are provided to give the City and stakeholders a framework for discussion, evaluation and planning.

A. Policy and Organizational Action Strategies

These strategies focus on policy and organization. Strategies proposed here should be adopted into the appropriate City of Bend policies, plans and regulations. It is recommended that they be adopted and implemented in the very near term (**within 12 months** of plan adoption).

STRATEGY 1:

Formalize the Guiding Principles as policies in appropriate City documents.

Incorporating these principles into City policy ensures that parking management goals established in this plan can be met. This will require actions by the City Council. The Guiding Principles are fully detailed in Section V. GUIDING PRINCIPLES – ELEMENTS OF PARKING MANAGEMENT, above.

Estimated Costs (STRATEGY 1):

It is estimated that costs associated with this strategy would be minimal and mostly expended in efforts of existing staff to develop resolutions and ordinances through routine city planning processes.

STRATEGY 2:

Adopt the 85% Rule as the standard for measuring performance of the parking supply and triggering specific management strategies, rates, permit prices and efforts by discrete zone.

When parking occupancy rates during the peak hour routinely reach or exceed 85%, the 85% Rule requires that additional strategies be implemented to reduce constraints.

Data from the 2016 parking study indicates that the on-street core area of the downtown is constrained during peak hours. Formalizing the 85% Rule as policy will ensure that a process is in place for evaluating and appropriately responding to parking constraints.

Estimated Costs (STRATEGY 2):

It is estimated that costs associated with this strategy would be minimal and mostly expended in efforts of existing staff to develop resolutions and ordinances through routine city planning processes.

STRATEGY 3:

Centralize the management and administration of parking in a Parking Services Division, integrated with the broader program of transportation services management.¹⁰

The success of any multi-faceted parking system depends on centralized, strategically coordinated management. This includes daily supervision of facilities, oversight of third-party vendors, financial

¹⁰ The Parking Division must coordinate with transportation staff to achieve balanced access across all transportation modes.

accounting and reporting, marketing and communications, customer service, and strategic and capital planning.

The current parking management system in Bend is neither centralized nor strategically coordinated. Given the complexity of the system and the level of technical and response capability called for in the Parking Management Plan, a single clear point of responsibility is needed. *Parking issues are too complicated and prevalent for status quo approaches to management.*

It is recommended that the City begin internal discussion on restructuring parking management, creating a Parking Services Division under the purview of a professional Parking Demand Manager who will direct daily operation of the system, implement policies and programs, and plan for growth.

Estimated Costs (STRATEGY 3):

At this time, costs associated with this strategy are unknown. There may be efficiencies, and there may be new costs (see **Strategy 4**, below). Any new costs must be supported by revenue from the parking system.

STRATEGY 4:

Create the position of Parking Demand Manager for the City of Bend. Develop a job description and submit a service package to hire an appropriate individual.

As indicated in **Strategy 3** above, a single person should be assigned to oversee all aspects of parking in the downtown. Consolidating parking operations in a single department under a Parking Demand Manager creates administrative and operational efficiencies; integrates on- and off-street parking, enforcement, and strategic planning; provides a point of accountability; and ensures that policy is fully implemented. The process for approving this service addition should be completed immediately (0–12 months) to facilitate near-term hiring or restructuring of an existing position (see discussion below).

Ideally, this person will staff a committee of stakeholders to routinely review parking activity (see **Strategy 5**). This group would use performance data to evaluate “action triggers” and implement appropriate strategies.

The Parking Demand Manager will need demonstrated experience in the following, which she or he will, at minimum, be responsible for:

- Coordinating and implementing all aspects of the Downtown Strategic Parking Management Plan.
- Overseeing all personnel (City and third-party) involved in the delivery of municipal parking services.
- Acting as liaison among businesses, users, and other agencies.

- Coordinating with Administrative Services to create consolidated financial reporting systems for parking.
- Creating biennial budgets for parking services.
- Overseeing third-party management agreements for parking operations or enforcement services in City facilities.
- Developing and negotiating contract agreements and ensuring contract compliance by third-party providers.
- Coordinating policy and code changes approved in the Parking Management Plan with relevant departments and divisions.
- Developing new signage and communications systems.
- Developing and implementing marketing and communications programs.
- Routinely assessing rates and fees and recommending adjustments based on demand dynamics.
- Overseeing data collection as defined by policy.
- Developing RFPs for parking services, equipment, and technology.
- Coordinating review and selection of service, equipment, and technology providers.
- Assessing further upgrades (e.g. signage, lighting, security, maintenance, enforcement) as necessary.
- Developing tracking and reporting systems to measure and monitor programs.
- Facilitating the work of a Downtown Parking Advisory Committee.

Improvements in efficiency, coordination, and communications could be made within the City's existing parking operations. Though the City currently has staff involved in the downtown parking program, the existing management format does not have a central point of responsibility. As mentioned above, this is of particular importance given the complex and dynamic nature of the parking strategies in this plan, and for this reason, the consultant team and DSAC has recommended creation of a new Parking Demand Manager position.

Estimated Costs (STRATEGY 4):

Costs associated with reorganizing parking management into a single division under a Parking Demand Manager are being developed by City staff for review by City Council during budget deliberations in May 2017. Any new costs must be supported by revenue from the parking system.

STRATEGY 5:

Establish a Downtown Parking Advisory Committee to assist in implementation and ongoing review of the parking plan.

The City should develop and approve a process through which a representative cross-section of downtown stakeholders *routinely* assists in the review and implementation of the Downtown Strategic Parking Management Plan. It is recommended that the City Council formally appoint members to the Parking Advisory Committee. The current Downtown Stakeholder Advisory Committee (DSAC) is an excellent example of the type of representation needed for a new Parking Advisory Committee.

A consistent schedule of meetings should be established, using this plan as a template for discussion.

Estimated Costs (STRATEGY 5):

Costs associated with this strategy should be low if it can be maintained as a volunteer effort, hosted by the City with programmed parking staff and/or downtown business interests through the Downtown Bend Business Association.

STRATEGY 6:

Evaluate collection of data to measure parking impacts in select neighborhoods adjacent to the downtown, as well as feasibility and cost of neighborhood permit programs (e.g., administration, process and stakeholder education).

Some residential streets outside the current parking boundary were included in the 2016 parking study. However, the work scope for the study did not provide for extensive evaluation of parking activity in residential areas bordering the downtown. Therefore, it was not possible to provide objective data on parking overflow or use of residential areas by non-residents, or to establish a baseline of purely residential parking occupancy rates.¹¹

The DSAC recognized the potential impacts of current and future parking demand in the downtown on adjacent neighborhoods. They also recognized that parking management in neighborhoods will require different solutions than in the downtown. The DSAC recommends that, in the near term, the City undertake a study in residential areas that:

- a. Engages stakeholders in discussions of parking impacts in adjacent neighborhoods and provides information on best-practice residential parking management strategies.
- b. Establishes boundaries of residential impact areas.



¹¹ Data on residential occupancy is best collected after mid-night to provide a ‘pure’ count of vehicles likely to be associated with adjacent residential properties. This data can then be compared to day time counts to determine the level of overflow.

- c. Collects data using methodologies appropriate to measuring residential parking demand.
- d. Uses data findings to develop targeted residential strategies. These could include:
 - Residential Parking Permit Programs
 - Reevaluation of parking time limits in residential areas.
 - Evaluation of surpluses and constraints in residential areas.
 - Shared parking programs in areas of surplus.

Estimated Costs (STRATEGY 6):

It is estimated that costs associated with a neighborhood parking study and engagement process would range from \$35,000 to \$50,000. Costs will be greatly affected by the size of the study area and extent of required data collection.

STRATEGY 7

Develop funding options to support parking management, maintain the existing parking supply, and support future growth, ensuring the financial feasibility of the system.

A wide range of funding sources and revenue streams could be used to implement an enhanced parking management plan and develop new parking or transit capacity in Bend. Given the cost of infrastructure, considering new funding mechanisms is prudent.

The list of potential sources here is not exhaustive, nor are these sources mutually exclusive. Funding for parking facilities, particularly garages, in emerging urban areas generally requires multiple sources, some of which may already be in place in Bend. The use of fees continues to evolve as various state laws or city ordinances are authorized. Implementation of fees should be reviewed by the City Attorney to determine their feasibility in light of applicable laws.

The funding options below assume a more detailed discussion of the role of the City in future funding of parking and transit, and public discussion regarding use of public funds to build and operate new systems.

Options Affecting Customers

User Fees

Many cities collect revenue through parking meters and/or sale of permits, and direct it to parking or transportation development enterprise funds. Transit or shuttle riders pay in the form of fares. These funds can be used to construct or bond for additional parking or transit capacity.

Event Ticketing Surcharges

Surcharges may be imposed in conjunction with local and regional facilities (e.g., performing arts, sports, and concert arenas) to support development of access systems. Fees are generally applied to ticket costs.

Parking Fines

Revenues are collected for parking violations and a portion directed to parking development enterprise funds.

Options Affecting Businesses

Parking and Business Improvement Area or District (BIA or BID)

An assessment on businesses rather than property owners, BIAs or BIDs can be based on assessed value, gross sales, square footage, number of employees, or other factors established by the local legislative authority. Salem, Oregon assesses a fee on businesses in its downtown parking district to support parking services. Portland assesses a business tax through the State of Oregon to support transit.

Options Affecting Property Owners

Special or Local Improvement District (SID/LID)

An SID or LID is a property tax assessment that requires buy-in by property owners within a specifically identified boundary. LIDs usually result from a petition process requiring a majority of owners to agree to an assessment for a specific purpose—in this case, a parking facility or transit infrastructure improvement.

Options Affecting Developers

Cash/Fee-in-Lieu

Developers may be given the option to pay a fee in lieu of providing parking with a new private development. Cash-in-lieu fees provide the developer access entitlements to public parking facilities near the development site.

Cash-in-lieu fees can be assessed up to the full cost of parking construction. Generally, these do not provide sufficient revenue to fully fund parking facilities, and are combined with other revenue sources.

If a cash-in-lieu fee is considered as a realistic funding source for new parking supply, there needs to be clarity and consensus on the intent and purpose of the fee and its use in increasing capacity either through new parking supply or through enhancement of alternative mode programs. Lack of specificity in this regard limits discussion of the type of fee, the rate, and the programs and strategies that would need to be in place to reach desired outcomes. A useful guide to the diversity of cash-in-lieu programs and their advantages and disadvantages is Donald Shoup, *Journal of Planning and Education Research*, 18:307-320, 1999.

Public/Private Development Partnerships

Development partnerships are generally associated with mixed-use projects in which parking is used to reduce the cost of private office, retail, or residential development. Public/private development can occur through a variety of arrangements, including:

1. Public acquisition of land and sale or lease of land/air rights not needed for parking to accommodate private use.
2. Private development of integrated mixed-use development with sale or lease-back of the public parking portion upon completion.
3. Responsibility for public sector involvement directly by the City, through a public development authority or other special purpose entity, such as a public facility district created for the project district or downtown area.

Options Affecting the General Public

General Obligation (GO) Bonds

Local jurisdictions may issue voted or non-voted bonds to develop parking or transit infrastructure, subject to overall debt limit requirements. With GO bonding, the municipality pledges its full faith and credit to repayment of the debt from general fund resources. In effect, general fund revenues would be reserved to repay debt that could not be supported by parking or transit revenues alone. Again, there may be imposed limits on the municipality for voter-approved or non-voted debt.

Refinancing GO Bonds

This involves refinancing existing debt at lower rates, and pushing the savings from the general fund to debt coverage for new infrastructure. In these times of lower interest rates, the City of Bend may have already maximized this option.

Revenue Bonds

Revenue bonds dedicate parking fees and other designated revenue sources to the repayment of bonds, but without pledging the full faith and credit of the issuing authority. Revenue bonding is not appropriate in situations where a local jurisdiction's overall debt limit is a factor and projected revenues are insufficient to cover required debt service.

63-20 Financing

A potential alternative to traditional GO bonds, revenue bonds, and LID bond financing, 63-20 financing allows a qualified nonprofit corporation to issue tax-exempt bonds on behalf of a government. Financed assets must be capital and must be turned over free and clear to the government by the time bonded indebtedness is retired. When a municipality uses this technique to finance a public facility, it can contract for the services of a nonprofit corporation as the issuer, and a builder. The issuer acts on behalf of the municipality, but has no real business interest in the asset being acquired.

State and Federal Grants

In the past, a variety of state and federal grant programs have been applied to funding parking and transit infrastructure in business districts. In the current environment of more limited government funding, there may no longer be readily identifiable programs suitable for parking facility development, though transit may be more feasible.

General Fund Contribution

Local jurisdictions may make either one-time capital or ongoing operating contributions to a downtown parking or transit/shuttle program.

Estimated Costs (STRATEGY 7):

This is very much a process task, requiring research and conversations with City policy- and decision-makers and legal counsel, and discussion with a range of potentially affected stakeholders and an assessment of future infrastructure needs and costs. For the purposes of this discussion, it is assumed that costs would be absorbed internally by the City and through implementation of the parking management plan.

STRATEGY 8:

Create a cohesive pricing policy for on- and off-street parking in downtown Bend. Support new policy with a rate/fee study to inform appropriate adjustments to current pricing formats to cover the cost of managing the downtown parking system.

Parking rates are a key element of parking management and sound fiscal policy. Understandably, adjusting rates is a controversial topic. It is critical that Bend establish a fair market rate that supports businesses and encourages neighborhood parking management and use of alternative modes. Bend does not currently have a routine, *policy-based* approach to evaluating and adjusting parking rates. To this end, it is recommended that the City establish a formal policy supported process that will provide a basis for rate-setting in both the on- and off-street systems, including enforcement.

In the last five years, a number of cities have instituted this process of regular adjustments. For example, SFpark in San Francisco adjusts on-street rates every six weeks in response to occupancy conditions as measured by in-pavement sensors. Seattle adjusts rates annually based on manual parking occupancy studies. Redwood City and San Mateo California have adopted similar approaches. A sample rate policy from South San Francisco, California is provided in **APPENDIX D** of the supplemental Appendix Report created to accompany this Final Report.

To support the new rate policy, it is recommended that the City initiate a rate/fee study that is scoped to review Bend's current rate/fee schedules and determine appropriate adjustments that reflect policy, guiding principles and actual demand and occupancy patterns.

Best practices suggest that a formal rate/fee study would be structured to evaluate:

- Coverage of operating and facility costs.
- Demand patterns, e.g., using an occupancy standard such as the 85% Rule as a trigger for adjusting rates upward or downward.
- Encouraging efficient use of the entire system, minimizing surpluses in the public off-street supply.

- Providing for future need as part of a comprehensive funding strategy. This includes normal capital planning and projected growth of the system.
- Rate/fee structures in comparable cities.

Estimated Costs (STRATEGY 8):

It is estimated that costs associated with developing a *formal policy* for Council review and approval would be expended in efforts of existing staff (with DPAC input) to develop resolutions and ordinances through routine city planning processes. A rate/fee study (if provided through a third party consultant) would range between \$15,000 and \$20,000. This strategy would assure that the financial viability of the system is maintained and reduce overall costs to the City, as revenue would be, at minimum, equal to expenses.

STRATEGY 9

Evaluate and implement solutions to safety impediments that create inconvenient and inefficient connections to parking, e.g., lighting, sidewalk/paths, lot conditions, etc.

The DSAC asserted early on that connections between the downtown core and parking assets outside the core are lacking. Infrequent users are especially inconvenienced by the lack of signage directing them to, through, and between the downtown and adjacent areas. Some pedestrian and parking facilities create negative safety perceptions, and alternative mode options that could allow users to park once and access all of the downtown easily are not strategically coordinated or managed.

It is recommended that the Downtown Parking Manager and DPAC undertake a comprehensive inventory and evaluation of impediments to connectivity and develop solutions for each. This might necessitate engaging a third party to assist in cataloguing issues, drafting solutions, and forecasting costs. Input from and participation by other relevant City divisions, as well as Cascades East Transit, will be important. An action plan would be developed for presentation to City Council and other affected entities for their review, consideration, and approval.

Potential elements of the action plan could include:

- Installing wayfinding signage at key access portals to direct users to available parking and help them find efficient routes between parking and their destinations.
- Evaluating improved transit connections between parking locations and destinations in and outside the core. This could entail rerouting of existing services and/or new shuttle/circulator programs.
- Improving bikeway links (e.g., safe routes/lanes, directional signage, bike parking).
- Improving pedestrian links.

Findings from this evaluation could help inform other longer term strategies—see **Strategies 20, 24, and 26**.

Estimated Costs (STRATEGY 9)

At this time, the costs associated with developing such an action plan are unknown. It would involve City staff time, work of the DPAC, coordination with other City divisions, and most likely the assistance of a third-party planning firm. For purposes of budgeting, costs for engaging a planning firm could range from \$20,000 to \$25,000.

B. Parking Management Strategies – Operations (Phase 1)

These strategies should be implemented within **12 to 24 months** of plan adoption.

STRATEGY 10

Establish business-to-business and residential outreach on parking issues, including education and planning, and a *Customer First* Partnership with the Downtown Bend Business Association.

This strategy is most likely an addendum to **Strategy 5**, which uses the Downtown Parking Advisory Committee as a source for targeted strategic communications to downtown businesses, employees, and the broader community. A program of routine visits to businesses, with informational materials and “open ears”, would be undertaken by a combination of existing staff or DPAC volunteers. Results would be catalogued and reported back to the work group. Similar programs are used in cities like Gresham (“Customer First”) and Oregon City (through the Oregon City Main Street Partnership).



*Example: Gresham, Oregon
Customer First Program Logo*

Outcomes could include:

- Improved education and communication of parking options to employees, residents, and visitors.
- Maps and other materials to identify parking and rules of use.
- Informational kiosks.
- Co-marketing opportunities with retail shops, hotels, restaurants, event venues.
- Alternative mode education and incentives.
- Interactive website.
- Tying communications to a new brand/logo (see **Strategy 16**).

Estimated Costs (STRATEGY 10)

It is estimated that costs associated with this strategy, including development of materials, could be adequately maintained for approximately \$7,500-10,000 annually.

STRATEGY 11

Identify off-street shared-use opportunities based on data from the 2016 parking study. Establish goals for transitioning permit users and long-term parkers out of on-street parking, begin outreach to opportunity sites, negotiate agreements, and sell permits.

The majority of parking in the downtown is off-street in privately owned parking assets. The 2016 parking study indicates that the number of *empty parking stalls* during the peak hour ranges from 1,383 to 2,615. This unused resource presents an opportunity to manage and support future growth in parking demand, and could be used to:

- Create designated parking for permit and long-term parkers that includes downtown opportunity areas and remote satellite lots.
- Incentivize employees to park in these areas.
- Improve the safety of these areas and connections to the downtown.
- Serve as a resource for event parking, particularly evenings and weekends.

Directing permit users to these facilities would open up on on-street parking stalls during normal peak hours. During events, this supply would also benefit overall access to the downtown and reduce on-street constraints. These efforts should be coupled with **Strategy 10** to increase awareness and create partnerships for use of shared parking supplies.

The City and DPAC should consider the following for completion within 24 months of plan adoption:

- a) Using data from the 2016 parking study; identify a subset of the 46 off-street facilities surveyed as potential shared-use opportunity sites. Criteria could include proximity to key downtown destinations, a meaningful supply of empty stalls, pedestrian/bike connectivity, safety and security issues, etc.
- b) Based on the above, develop a short list of opportunity sites and identify owners.
- c) Establish a target goal for the number of downtown employees to transition into opportunity sites.
- d) Begin outreach to owners of private lots.
- e) Negotiate shared-use agreements.
- f) Obtain agreements from downtown businesses to participate in an employee assignment program.

Estimated Costs (STRATEGY 11):

It is estimated that costs associated with this strategy would be mostly expended in efforts of existing staff to identify opportunity sites and conduct outreach to potential private sector participants. Planning may determine that funds are needed to create incentives and/or improve the condition of facilities and connections.

STRATEGY 12:

Implement variable-rate pricing for on-street permits based on location, demand, and availability of parking. This will create pricing differentials between “premium” and underutilized locations.

Variable-rate pricing uses rates to influence behavior. Facilities with low demand and/or less convenient locations would be priced lower than those with high demand or in close proximity to destinations. Effective use of variable-rate pricing results in better distribution of users across facilities, particularly those that are underused.

A map showing the City’s on-street permit parking program is provided on the next page (Figure K).

Current permits range from \$20 to \$50 per month, but the difference in rate is not correlated to demand or desirability of location. For instance, the monthly cost of a permit at the City’s Newport Lot is \$45 per month. Peak occupancy at this 104-stall lot is only 41%, leaving 61 or more stalls empty on most days. On-street permit parking in and around City Hall, which is more than 85% occupied at the weekday peak, costs just \$30 per month. These differentials are illustrated in Table 7.

It is recommended that the City’s Parking Demand Manager and DPAC reevaluate current parking permit rates to better correlate them to both location and demand. All rate evaluations should include input derived from Strategy 8, particularly findings of the recommended rate/fee study.


Table 7: Downtown Bend: Current Rate/Fee Schedule – Employee Permit Program

Area/Facility	Current Rate	Peak Occupancy Summer 2016
Newport Lot	\$45 per month	41%
Garage (Purple)	\$50 per month	71%
On-street (Green)	\$30 month	>85%
On-street (Yellow)	\$20 month	<55%
Hilltop (Purple)	\$25 month	78%

Estimated Costs (STRATEGY 12):

It is estimated that costs associated with this strategy would be mostly expended in efforts of the Parking Demand Manager and DPAC to review rates and recommend adjustments. As suggested in Strategy 8, the City could consider a third-party rate study, which would likely be in the range of \$15,000 - \$20,000. Rate changes could result in additional revenue for the City.

Figure K: Downtown Bend: City Parking Permit Program



STRATEGY 13:

Reduce or phase out the number of “2-Hour or as Otherwise Specified” on-street stalls in coordination with Strategies 11 and 12 above to simply “2-Hour Parking.”

There are currently 242 stalls in the downtown study area designated “2 Hours – Unless Otherwise Specified.” These stalls allow short-term visitor parking, but are used all day by users displaying a valid permit. These stalls are located in the green and yellow areas in Figure K, previous page. At the peak hour, more than 150 of these stalls are occupied by permit holders.

As described earlier, the use of on-street permits lowers the average rate of turnover and reduces access for customers and visitors. As Table 5 (page 37) illustrated, the system could serve an additional 1,346 vehicles per day if permit parking were significantly reduced, particularly in areas where occupancy rates exceed 85% in the peak hour.

It is recommended that the number of on-street stalls designated for permit use be reduced through a process guided by Strategy 11 (off-street shared use) and Strategy 12 (variable-rate pricing).

Estimated Costs (STRATEGY 13):

Costs associated with this strategy would be expended in replacing existing signage.

STRATEGY 14:

Based on documented parking behavior, establish distinct on-street parking management zones in the downtown parking district. Use 2016 and Strategy 21 occupancy data to define the boundaries.

Turnover data collected and illustrated on heat maps (Figure G and Figure H, pages 33 and 34) demonstrate that parking is very constrained downtown on summer weekdays (i.e., >85% for numerous hours of the day), particularly between NW Greenwood and NW Idaho Avenues west of NW Harriman. Areas east of NW Harriman show lower occupancy rates in both summer and spring. These areas should be considered for treatment as distinct management zones.

Each management zone would have a standard time limit. Exceptions would be allowed for very short-term (e.g. 15- or 30-minute) high-turnover stalls, loading zones, taxi pickup/drop-off areas, oversize vehicles, etc. The Parking Demand Manager and DPAC would review requests for exceptions.

Data from the 2016 parking study suggests the following changes to on-street formatting. Additional refinements could be made based on data collected per Strategy 21, below.

- Establish a 2-Hour standard time limit in a “core zone.”
- Establish a 3-Hour standard time limit in an “east zone.”
- Establish a 3-Hour standard time limit in areas of the parking district not covered by the core and east zones.

- Allow limited employee permit parking in the east zone, coordinated with Strategies 11 and 12 above.
- Establish a periphery zone adjacent to the parking district with a standard time limit appropriate to the residential nature of this area, coordinated with **Strategy 6** above.
- Create a process for requesting exceptions to standard time limits in the management zones, and for subsequent review by the Parking Demand Manager and DPAC.

Estimated Costs (STRATEGY 14):

Costs associated with this strategy would be expended in replacing existing signage.

STRATEGY 15:

Eliminate free parking for the first two hours at the Mirror Pond lots.

Spring and summer data from the 2016 parking study shows that the North and South Mirror Pond lots are at least 85% occupied for significant periods of the day. Observations from Diamond Parking and the DSAC indicate that free parking offered for the first two hours is often used by employees, who park at the lots for two hours before moving to on-street stalls. This takes parking capacity away from customers and visitors.

The lots also need upgrading to improve their appearance and safety. This could include better signage and lighting, and changes to the landscaping to improve sightlines and discourage loitering.

Once a Parking Demand Manager is brought on Board (**Strategy 4**) and a Downtown Parking Advisory Committee empaneled (**Strategy 5**), the current DSAC recommends eliminating two-hour free parking and developing an action plan and budget for the rate transition, to occur concurrently with physical upgrades to the lots. Other considerations forwarded for review by the Parking Demand Manager and DPAC include:

- Implementing progressive hourly parking, with a lower rate for the first two hours, then increasing rates for each additional hour.
- Limiting stays (e.g., a four-hour maximum).
- Extending parking restrictions to 8:00 p.m. to ensure access for priority users.

Estimated Costs (STRATEGY 15):

The existing revenue control system at the lots is capable of implementing the recommended rate change and/or a progressive hourly rate format. Costs associated with new signage, lighting, and landscaping would be developed in an action plan by the Parking Demand Manager and the DPAC.

STRATEGY 16:

Create a critical path timeline to a new parking brand that can be utilized at all City-owned lots and shared facilities, and in marketing/communications.

The Guiding Principles call for effective; high-quality branded communications (see Section V. GUIDING PRINCIPLES – ELEMENTS OF PARKING MANAGEMENT). Guiding Principle A.4 recommends that “to the highest degree possible, communications systems should be reliable and easy to use and understand.” Guiding Principle D calls for a parking system that links parking assets and communication systems under a common brand or logo.

The intent of these principles is to create a unified public parking system that is easily recognized through use of a common brand or logo, both at parking sites and, ideally, on a wayfinding system located throughout the downtown and on maps, websites, and other communications.

It is recommended that the City and DPAC engage a design firm to develop a parking brand for use at all of Bend’s public off-street facilities, and any shared-use facility that offers visitor access.

The design professional would:

- a) Work with the City and DPAC to create a new parking brand for Bend.
- b) Develop options and assist in developing a final recommended brand/logo.
- c) Develop cost estimates for the creation and placement of branded signage at all City-owned off-street sites and shared-use facilities.
- d) Assist in signage creation.

Estimated Costs (STRATEGY 16):

It is estimated that engaging a design consultant to carry out the tasks identified above would range from \$20,000 to \$25,000.

STRATEGY 17:

Standardize the design of on-street parking signage in the parking management district and incorporate the new brand/logo.



Examples: Parking Brand/Logos

Existing signage is inconsistent in design and color, is very small, and is difficult to read from the street. Clear, standardized on-street signage will simplify parking for customers and provide for uniform time limits in parking management zones (see **Strategy 14**).

It is recommended that in Phase 1, the City:

- Make all core-zone parking 2-Hour (per **Strategy 14**).
- Make all non-core zone parking 3-Hour or By Permit (per **Strategy 14**).
- Eliminate or greatly reduce No Limit stalls.



Current Bend On-street Signage

Additionally, a new brand/logo can be incorporated into the on-street system as a means of integrating the on- and off-street systems. This will require coordinating changes in the on-street system to the branding work in **Strategy 16**. A similar branding effort in Springfield, Oregon incorporated a stylized P into on- and off-street signage, as seen in the graphic at right.

Estimated Costs (STRATEGY 17):

The following estimates are based on information from other cities:

- A standard signage package consists of two poles with blade signs per block face, one at each end of the block with arrows pointing inward.

Unit Costs—Signage

- Only material costs are provided in these estimates
- Pole unit cost = \$470
- Blade sign unit cost = \$30
- Unit cost for poles includes hole boring

*Example: On-street “Brand”
Springfield, OR*



The number of signs needed would be identified through a signage inventory.

STRATEGY 18

Rename all public parking facilities by address.

Names like Newport, Centennial Garage, or Public Lot do not communicate useful information to users, particularly those who are unfamiliar with the downtown.

Industry best practices for naming off-street parking facilities suggest using an address or intersection associated with the main entrance. Portland, Oregon and Boulder, Colorado do a good job of identifying facilities in this manner—names like 10th & Walnut or 4th & Yamhill intuitively communicate location. Coupled with the system logo, these facilities can easily be integrated into branded communications, apps, wayfinding, and other materials.



Bend's current naming format is not customer-friendly or informative. The City should consider renaming its facilities as part of a broader effort to make the parking system more intuitive and easier to use. As shared-use facilities are developed and integrated into the City system, they can be renamed according to this convention. This effort would be coordinated with Strategies 11, 16, 17, and 24.



Estimated Costs (STRATEGY 18):

Initial costs would involve changing existing signage and marketing and promotional materials, estimated to range between \$5,000 and \$10,000.

Facility Identification: Boulder CO & Portland OR

STRATEGY 19:

Establish best-practice protocols and performance metrics for enforcement personnel and support enforcement with appropriate technology.

Enforcement is the foundation of sound parking management. Without enforcement, systems designed to encourage turnover and deter employees from parking on-street are ineffective.

Data from the 2016 parking study indicates that enforcement in Downtown Bend is generally good, but rates of violation are just over the high end of the recommended range for efficient parking systems of 5%-8%. Also, as many as 210 vehicles per day are moving to avoid citations, some of which are likely employees not in the permit program. Both factors adversely affect turnover and contribute to parking constraints. Deploying enforcement personnel more strategically can address this.

The DSAC recommends that additional consideration be given to strategies that:

- Revise “move to evade” policies to allow one move in the downtown area.
- Change enforcement hours to reflect actual demand trends.
- Increase fees and fines as necessary to ensure a violation rate of 5-8%.
- Create fees and fines by zone.

As the program evolves, specific enforcement goals for the on-street system should be adopted and tracked. Outlined below is a best-practice approach the City could integrate into its existing protocols and procedures.

Best Practices

The key goal for parking enforcement is promoting compliance with regulations designed to maximize the efficiency and safety of public parking. Emerging best practices combine enforcement with downtown ambassadors who provide information resources to users.



Example: Enforcement Hand Held Technology

Industry guidelines for efficient and effective parking enforcement include:

1. Parking enforcement officers (PEOs) should be routed such that a circuit of the enforcement area is completed every two hours.
2. Rate of violation should be less than 8%.
3. Handhelds should issue electronic tickets, have GPS capabilities, track stall inventory, and track and summarize customer warning programs. Handhelds should also integrate with real-time scofflaw databases. Ideally these are cloud-based.
4. Handheld units should store information for stolen vehicles, warrants, shuffling, and unpaid tickets.
5. PEOs should be dedicated to parking duties and only reassigned under special circumstances.
6. Street signs should clearly indicate the hours of enforcement.
7. Courtesy tickets should be issued to first-time offenders as a gentle reminder that they have overstayed the posted time limit. Courtesy tickets can also serve as a marketing piece, thanking parkers for coming downtown and directing them to areas or facilities where longer stays are allowed.
8. PEOs should be used as downtown "ambassadors" to assist parkers with directions, parking options, and use of the downtown.

Enforcement/Citation Rates

Costs of managing enforcement should not be combined with those of managing the on-street or off-street parking systems. Revenue from citations should cover all operating costs and future needs of the enforcement system. In other words, parkers who obey the rules should not be burdened, through parking rates, with the cost of dealing with those who violate the rules. While the cost of the

enforcement program should be included in the downtown parking fund, its expenses and revenues should be managed separately. The cost of the program should be fully burdened in the citation rate.

Fees for parking violations should be based on three criteria:

1. The cost of maintaining existing operations, including administration, personnel, back office, and equipment.
2. The reasonable cost of future needs, including system growth and replacement and technology improvements.
3. Targeted goals for rate of violation (less than 9%, with an ideal range of 5%-8%).

Fees should be evaluated every two years based on the above. To support this strategy, the City should:

- a. Review existing deployment routes to ensure the highest efficiency of coverage.
- b. Evaluate violation data and assess methods to lower the current rate of violation to at most 9%.
- c. Develop a reporting format that separates tickets by type, so that the number of tickets issued for parking violations in contrast to non-parking incidents (e.g., expired tags, jaywalking, moving violations, etc.) can be determined.
- d. Consider use of courtesy tickets as a means to communicate downtown parking “rules and procedures” and to direct potential users into off-street city facilities.
- e. Consider training PEOs as downtown ambassadors.
- f. Review citation fees every two years to ensure that revenue covers, at minimum, all operating costs for the enforcement program.

Estimated Costs (STRATEGY 19)

The City and DPAC should work closely with Diamond Parking to develop a PEO and technology plan that deploys labor and technology in a manner that limits stay violations to between 5% and 8%. New costs would be identified through this process. Staff time for establishing procedures for quantifying performance and reporting should be absorbed into existing staff capacity.

STRATEGY 20:

Where practical, expand the bike parking network to connect parking and the downtown, encouraging employee bike commute trips and drawing customers to downtown businesses.

When we talk about parking management, we’re not just talking about cars—communities throughout Oregon support bicycling as a key transportation strategy. What downtown Bend lacks at this time is sufficient “trip-end”



Example: Art Rack Baker City, OR

bike parking amenities on-street, off-street, and in private buildings. Providing adequate bicycle parking will expand the capacity of the overall parking supply downtown.

It is recommended that the City expand its approach to bike parking to include:

a. *Sidewalk bike parking*

Identify locations for added bike parking in pedestrian amenity zones.

b. *Bike corrals*

Identify locations for bike corrals on-street and in plaza areas adjacent to high-traffic businesses.¹²

c. *Bike parking on private property*

Identify areas on private property for bike parking improvements, especially for employees—e.g., interior bike cages, wall rack locations, and other secure areas.

d. *Identify funding/incentives*

Assemble funding sources necessary to implement a) – c).



Example: Bike Corral Ashland, OR



Example: Interior Wall Racks

It is assumed that these efforts would support future expansion of the City's bike lane network.

Estimated Costs (STRATEGY 20)

The cost of inventorying potential bike parking locations could be incorporated into **Strategy 21** below. Site identification could also be done through volunteer efforts and by working with downtown stakeholders and bike advocates. Costs are likely minimal.

Estimated unit costs for actual bike infrastructure:

- Staple or U racks: \$150-\$200
- Wall-mounted racks: \$130-\$150
- Bike Corral \$1,200¹³
- Art Rack variable based on design


12 Bike corrals can also be considered for seasonal use. Bozeman, Montana and Wenatchee, Washington are examples of cities that use bike corrals during non-winter months, converting spaces back to regular vehicle parking in the winter.

13 Based on City of Portland, Oregon cost estimate for six staple racks (12 bike parking spaces), striping, bollards, and installation.

STRATEGY 21

Develop a reasonable schedule of data collection— every two years—to assess performance of the parking supply and support the 85% Rule for decision-making.

Objective, up-to-date data on occupancy, seasonality, turnover, duration of stay, patterns of use, and enforcement will help the City and stakeholders make better-informed decisions as the downtown grows. The data gathered in the 2016 parking study is a baseline for future assessments of the parking supply.



The system for supplementing the baseline does not need to be elaborate, but it should be consistent, routine, and structured to answer relevant questions about the metrics listed above. Data can be collected in samples, and other measures of success can be gathered through third-party or volunteer processes. It is recommended that the City, with DPAC input and review:

- Conduct routine turnover and occupancy surveys of the on- and off-street facilities in downtown at least every two years.
- Replicate the 2016 parking study boundary to have an accurate data comparison.
- Determine a routine schedule and timeline for implementation.
- Use this data to inform ongoing decisions in an objective manner.

The methodology for conducting the 2016 parking study inventories and data analyses is provided in **APPENDIX C** of the supplemental Appendix Report created to accompany this Final Report.

Additionally, best practice methodologies for parking data collection can be found in Oregon Transportation & Growth Management’s *Parking Made Easy: A Guide to Managing Parking in Your Community*, specifically Chapter 7. See www.oregon.gov/LCD/TGM/docs/parkingprimerfinal71213.pdf.

Estimated Costs (STRATEGY 21)

It is estimated that a data inventory and turnover/occupancy study would range from \$45,000-\$50,000 if conducted by a third party. Costs can be minimized in subsequent surveys through use of the inventory database already in place, as well as through sampling and possible use of volunteers to collect data.

STRATEGY 22

Using data collected per Strategy 21, evaluate on-street pricing by zone in high-occupancy areas. If peak occupancy exceeds 85%, implement on-street pricing during enforcement hours where appropriate.

Data from the 2016 parking study demonstrated that the on-street system routinely exceeds the 85% occupancy standard for sustained periods during spring and summer months. **Strategies 10 – 20**, once implemented, are intended to significantly change how parking is used and communicated in the downtown. The impacts of these changes will be objectively quantified in **Strategy 21**. This will allow the City, the DPAC and the community to determine whether these constraints have been mitigated.

Once **Strategy 21** is complete, it is recommended that the Parking Demand Manager and DPAC evaluate paid parking on-street, particularly if frequent constraints are still seen.

Hourly on-street occupancy data can also be used to model potential revenue hours for different rate scenarios. Revenue hours can then be integrated into an expense/revenue pro forma to objectively estimate the feasibility of moving to an on-street pay-to-park program.

Paid parking can support higher turnover, decrease competition between employees and customers or visitors, create a more reasonable value relationship between parking and alternative modes, and provide revenue streams necessary to support operations, marketing/communications, program delivery, and infrastructure.

Actions to be considered include:

- a. Updating occupancy and parking utilization databases.
- b. Developing expense/revenue models to estimate the financial viability of new revenue collection technology.
- c. Determining appropriate revenue collection technology.
- d. Considering single meters versus pay stations.
- e. Considering pay-and-display versus pay-by-space.
- f. Considering seasonal pricing.
- g. Finalizing pricing format.
- h. Reaffirming time-limit formats and hours of operation (as informed by Strategies 14 and 17).
- i. Soliciting vendors for revenue collection technology.

Estimated Costs (STRATEGY 22)

It is assumed that the evaluation process would be incorporated into the routine schedule developed by the Parking Manager and DPAC. Data collection efforts are a part of **Strategy 21**. Based on several recent NW cities' experience, general equipment costs for revenue technology could be in the range of:

- Multi-Space Meters (pay stations) \$5,000-\$7,000 per unit (serving 8–14 spaces)
- Single-Space Meters \$500-\$700 per unit (serving one space)
- Back office support Varies by system and software selected

Strategy 23

Eliminate free parking in the public garage when garage occupancies exceed 85% and on-street parking is priced. Implement demand-based pricing for all hours of enforced parking—e.g., hourly, evening, weekend, overnight, and event rates.

If the decision is made to price on-street parking, the DSAC recommends that pricing also be implemented in the public garage. Pricing should be demand-based, integrated with on-street pricing, and varied to reflect the unique dynamics of weekday, evening, weekend, overnight, and event situations. In addition, providing the option of longer-term stays at lower rates than on-street parking will encourage turnover in the on-street system and offer convenience to customers and visitors seeking a longer stay.

Estimated Costs (STRATEGY 23)

The garage already has payment protocols for customers parking longer than three hours. However, new equipment and signage may be necessary to transition to a more complex rate format. Such costs will be a part of the infrastructure evaluation recommended in **Strategy 24** below. Over time, pricing at the garage will result in new revenue for the City.

C. Parking Management Strategies – Infrastructure (Phase 2)

It is anticipated that Phase 2 efforts will take place 24 to 48 months from initiation of the parking management plan. These strategies build upon and are facilitated by work completed in Phase 1. Phase 2 focuses on new equipment, capacity growth and management, communication systems, and finalizing funding sources explored in **Strategy 7**.

Any and all Phase 2 strategies can be accelerated or moderated as necessary depending on community support and consensus, opportunity, or funding. As with Phase 1, all strategies will require consistent and dedicated management and coordination, with active participation by the private sector.

STRATEGY 24

Develop and implement improvements at the downtown public parking garage to enhance its appearance, identity, safety, revenue control, communications technology, and pedestrian access.

Current systems at the City’s public garage are outdated and, at times, unreliable. Moreover, they do not provide data and reporting functions essential to high-level management and decision-making.



Example: On-site signage linked to counter system to display stall availability.

The DSAC concluded that upgrades to the garage’s operating systems are critical to the City’s ability to attract new users and establish a sense of safety and convenience. Systems must equip the City to accurately monitor use, calibrate rates, and manage daily and monthly access.

It is recommended that the Parking Demand Manager and the DPAC engage in a facility review of the garage and develop an action plan and budget to implement improvements. At minimum, the following should be evaluated:

- Lighting upgrades
- Entry/exit counter systems to track stall occupancy
- State-of-the-art pay stations
- Exterior signage displaying brand/logo (**Strategy 16**) and occupancy information
- Interior directional signage upgrades
- Pedestrian access (e.g., stairwells, elevator plaza) and internal vehicle circulation

New technologies offering real-time data on occupancy and use are readily available from companies such as Amano, Digital Technologies, Cale, Scheidt & Bachmann, and McGann. Upgraded systems will create significant efficiencies in time, resources, management, and decision-making.



Example: Pay on Foot in elevator lobby – Fountain Square Garage, Cincinnati OH

Estimated Costs (STRATEGY 24)

Recent RWC involvement in upgrading access, revenue control, and signage systems in garages in the Pacific Northwest allows for estimating various equipment systems. The Parking Demand Manager and DPAC will need to work with vendors to refine these estimates. RWC does not have expertise in costing lighting systems.

• Payment system kiosk (credit/debit capable)	\$15,000-\$25,000
• Pay-in-lane (per lane) (optional)	\$10,000-\$13,000
• Lane controllers - counter system (per lane)	\$2,500-\$3,500
• Accounting and revenue control software	\$19,000-\$22,000
• Monthly pass card reader system (per lane)	\$5,000-\$8,000
• Ticket tracking software	\$5,500-\$7,500
• Hotel system integration (e.g., through room keys)	\$25,000
• Exterior signage (per sign)	\$5,000-\$10,000
• Warranties	Varies by vendor
• Installation	Varies by vendor
• Routine vendor support (maintenance/service - monthly)	\$400-\$750

STRATEGY 25

Solicit firms to establish wayfinding and dynamic signage systems in the public right of way, integrated with the off-street system and using the brand/logo developed per Strategy 16.

Many cities brand their public parking facilities and use dynamic signage in the public right-of-way. These systems inform customers and direct them to available parking. Portland, Oregon, and San Jose, California are good examples (see photo at right).



Dynamic signage is linked to occupancy information collected at individual or multiple parking sites, usually through loop detector/parking counter systems. This information is displayed at building entry plazas and/or at major roadway access portals. The signs provide an address or facility name and real-time stall availability.

The most successful programs tie into a parking brand incorporated into both the on-site and right-of-way signage (see Strategy 16). Dynamic signage also complements parking apps and can be linked in real time to smartphones and/or websites.

As an alternative to dynamic signage, Bend could first explore using non-electronic branded wayfinding at key access portals into the downtown, with the intent of upgrading to dynamic signage at a future point. This could be a less costly and timelier means of introducing parking wayfinding.

Engaging a wayfinding firm would bring an industry professional to:

- a. Develop a signage package that incorporates a uniform design, logo, and color scheme (Strategy 16).
- b. Brand each off-street public facility with the logo package.
- c. Evaluate off-street facilities for installation of real-time counter systems that link to wayfinding signage.
- d. Identify key entry points into the downtown for placement of signage.
- e. Explore real-time communications linking multiple facilities, apps, websites, and other resources.
- f. Conduct a cost feasibility analysis.
- g. Establish an installation schedule.

Estimated Costs (STRATEGY 25)

It is assumed that costing for wayfinding would be incorporated into the solicitation.

STRATEGY 26

If existing parking becomes limited, explore expanding access capacity with new transit and parking.

As Bend's downtown grows, existing parking supplies and access to alternative modes will need to be expanded. Adding bicycle trip capacity was discussed above in Phase 1 (Strategy 20). In anticipation of growth, the City should evaluate other forms of access capacity as well, including improved transit and/or circulator options and new parking supply.

These types of capacity growth require sophisticated infrastructure and are very costly. It will be important for Bend to give adequate time and effort to determining the most beneficial and cost-effective formats for increasing capacity. Planning for, and finding funding for, new capacity is time-consuming, so focused and objective evaluation will greatly facilitate decision-making before constraints adversely impact the downtown.

Explore shuttle/circulator connections (remote connector)

Transit and shuttles could be especially valuable as a means to improve employee commute options, provide circulation through downtown for visitors, and link remote parking sites.

The City and DPAC should involve Cascades East Transit, Community Development, Growth Management, and the community in discussions regarding a transit option that would best serve the downtown and effectively shift an increasing number of trips onto transit. The City's 2013 *Public Transit Plan and Transit Corridor Land Use Assessment* can serve as a foundation for discussion and evaluation.



It is recommended that the Parking Demand Manager and DPAC:

1. Evaluate route options that will strengthen transit access for downtown employees.
2. Explore connections to remote parking in conjunction with data collection efforts in Strategy 21.
3. Determine appropriate levels of frequency, vehicle types, and seasonality of service.
4. Explore use of circulator shuttles versus existing transit.
5. Coordinate with Cascades East Transit.
6. Narrow to preferred option(s).



Identify new parking opportunity sites

Capacity can be added through construction of a new parking garage and/or new surface parking in locations outside the downtown, linked by transit. The consultant team conducted an inventory of all 158 downtown off-street parking sites in the 2016 parking study. Forty-six sites totaling 2,650 stalls were assessed for utilization, creating a list of potential opportunity sites for further evaluation. A map of those sites is provided at right (see also Figure B, page 24).


To date there has been no evaluation of potential “remote” sites.

It is recommended that the Parking Demand Manager and DPAC:

1. Establish parking need, coordinated with Strategies 22 and 27.
2. Evaluate downtown locations where new parking is possible.
3. Evaluate remote sites that could be connected via transit/shuttle.
4. Evaluate public/private partnerships.
5. Coordinate site evaluation with Community Development.
6. Coordinate with the Downtown Bend Business Association and Chamber of Commerce to develop contacts with potential partners in the private sector.
7. Engage local developers in the evaluation process.
8. Narrow to feasible site(s).

Estimated Costs (STRATEGY 26):

The City and DPAC may wish to retain third-party assistance in this process, particularly regarding the design and formatting of transit/shuttle systems. These systems will impact traffic and circulation and create land use issues. Identifying and locating potential parking sites could be accomplished internally, with assistance from the Downtown Bend Business Association, local developers, and Community Development. As an estimate, the City could incur costs of \$25,000-\$35,000 for route and system planning for new transit. The active involvement of Cascades East Transit could greatly reduce this estimate.



STRATEGY 27

Develop cost forecasts and feasible financing methods for preferred parking supply and transit/shuttle options.

Strategy 26 will provide information on recommended transit/shuttle and parking enhancements. Parking will have been evaluated as to location, size, and format. Transit/shuttles will have been evaluated as to format, frequency, and routing.

The appropriateness and feasibility of a range of funding options will have been explored and narrowed through work in Strategy 7. Funding options would then be applied to the preferred capacity enhancements to meet their cost forecast and support their implementation.

Estimated Costs (STRATEGY 27)

Initial third-party costing of garages and lots in the form of expense/revenue and financing pro formas can range from \$5,000 to \$7,500. This would be contingent on information already provided to a consultant from Strategy 26.

Costs of new parking supply will vary by type. Estimates from projects recently completed in the Pacific Northwest are provided below.

- Structured Underground \$35,000-\$45,000 per stall
- Structured Above Ground \$20,000-\$25,000 per stall
- Surface Lot \$ 5,000-\$7,000 per stall

NOTE: Does not include operating cost or full cost of land

RWC does not have expertise in costing transit/shuttle systems. These numbers would be provided as a function of Strategy 26.

STRATEGY 28

Expand capacity as necessary and feasible.

This strategy would be catalyzed by completion of Strategies 7, 26, and 27 and would complete Phase 2 of the Downtown Strategic Parking Management Plan. Within 36–48 months of plan initiation, the City and DPAC will have evaluated and researched the most beneficial and effective option(s) for expanding access capacity in the downtown, funded through a package of finance options that are cost-effective and publicly supported.

X. SUMMARY

The parking management strategies recommended here are intended to provide a template for action that leads to a more efficient and organized parking system for downtown Bend. The strategies would be coordinated by a single Parking Services Division led by a Parking Demand Manager, with insight and direction from the Downtown Parking Advisory Committee.

The strategies envisioned here will be implemented over a minimum of four years, informed by the 85% Rule and by parking demand as measured through routine data collection. Overall, the strategies are designed to “get the right parker to the right parking spot” in a manner that supports the Guiding Principles established as a part of this plan.

ATTACHMENT A

Action Strategies Implementation Summary

Actions and Implementation Schedule

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
POLICY ACTION STRATEGIES (Immediate/Near-Term)					
1 Formalize the Guiding Principles as policies in appropriate City documents.	✓			Provides decision-making framework and policy foundation for decisions/actions.	- Existing Staff
2 Adopt the 85% Rule as the standard for measuring performance of the parking supply and triggering specific management strategies, rates, permit prices and efforts by discrete zone.	✓			Data from the 2016 parking study indicates that many areas of the downtown (on or off-street) approach a high level of constraint at peak hours. Having the 85% Rule formalized in policy will assure that a process for evaluating and appropriately responding to parking activity is in place as constraints develop.	- Existing Staff time

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>3</p> <p>Centralize the management and administration of parking in a Parking Services Division, integrated with the broader program of transportation services management.</p>	✓			<p>The success of any multi-faceted parking system is dependent on administration, management, and communication of the City’s parking program at all levels. This includes daily management of facilities, oversight of third-party vendors, financial accounting and reporting, marketing/communications and customer service.</p>	<ul style="list-style-type: none"> - Existing Staff time - Potential for new management staff (Strategy 4)
<p>4</p> <p>Create the position of Parking Demand Manager for the City of Bend. Develop a job description and submit a service package to hire an appropriate individual.</p>	✓			<p>A single person should be assigned to oversee and manage all aspects of parking in the downtown, providing the community a single reference point for parking management.</p> <p>Any new costs are supported by revenues derived from the parking system.</p>	<ul style="list-style-type: none"> - Costs associated with organizational restructuring and hiring a Parking Manager are being developed by City staff for review by City Council during the City’s budget deliberations in May 2017.

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>5 Establish a Downtown Parking Advisory Committee to assist in implementation and ongoing review of the parking plan.</p>	✓			<p>The City should develop and approve a process through which a representative cross-section of downtown interests <i>routinely</i> assists the City in the review and implementation of the Downtown Strategic Parking Management Plan.</p>	<p>- There should be no additional costs associated with this recommendation if it can be initiated as a volunteer effort, hosted by the City and/or downtown business interests through the Downtown Bend Business Association.</p>
<p>6 Evaluate collection of data to measure parking impacts in select neighborhoods adjacent to the downtown, as well as feasibility and cost of neighborhood permit programs (e.g., administration, process and stakeholder education).</p>	✓			<p>The work scope for the 2016 Downtown parking study did not provide for extensive evaluation of parking activity in residential areas bordering the downtown. As such, it was not possible to provide objective data related to issues of overspill and/or use of residential areas by non-residential users.</p>	<p>- \$35 - \$50,000</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>7 Develop funding options to support parking management, maintain the existing parking supply, and support future growth, ensuring the financial feasibility of the system.</p>	✓			<p>There are a wide range of potential funding sources and revenue streams that could be used to support implementation of an enhanced parking management plan in the Bend downtown as well as to plan for and support development of new parking and/or transit capacity per Strategy 27.</p>	<ul style="list-style-type: none"> - Existing Staff time - Internal legal review and recommendation - DPAC consideration and recommendation - Public review and input - City Council approval
<p>8 Create a cohesive pricing policy for on- and off-street parking in downtown Bend. Support new policy with a rate/fee study to inform appropriate adjustments to current pricing formats to cover the cost of managing the downtown parking system.</p>	✓			<p>Bend does not currently have a routine or strategic approach to evaluating or adjusting its rates; for on-street permits, off-street rates and permits and citations.</p>	<ul style="list-style-type: none"> - Costs for developing a <i>formal policy</i> for Council review and approval would be expended in efforts of existing staff (with DPAC input) and routine city planning processes. - A rate/fee study (if provided through a third party consultant) would range between \$15,000 and \$20,000.

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>9 Evaluate and implement solutions to safety impediments that create inconvenient and inefficient connections to parking, e.g., lighting, sidewalk/paths, lot conditions, etc.</p>	✓			<p>The DSAC asserted that even though parking surpluses can be found throughout the downtown, connections between the core downtown and parking assets outside the core are lacking. An Action Plan should be developed for presentation to City Council and other affected entities for review, consideration and approval.</p>	<p>- Costs for engaging a third party planning firm could range from \$20,000 to \$25,000.</p>
PARKING MANAGEMENT ACTION STRATEGIES – OPERATIONS (PHASE 1)					
<p>10 Establish business-to-business and residential outreach on parking issues, including education and planning, and a <i>Customer First</i> Partnership with the Downtown Bend Business Association.</p>		✓		<p>Uses the Downtown Parking Advisory Committee as a source for targeted and strategic communications related to parking to downtown businesses, employees and the broader community.</p>	<p>- Estimated at \$7,500 - \$10,000 annually</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>11 Identify off-street shared-use opportunities based on data from the 2016 parking study. Establish goals for transitioning permit users and long-term parkers out of on-street parking, begin outreach to opportunity sites, negotiate agreements, and sell permits.</p>		✓		<p>The majority of parking in the downtown is off-street in privately owned parking assets. The 2016 parking study indicates that potential empty parking stalls in the peak hour in existing off-street facilities are significant. This presents an opportunity for Bend as this unused supply is a resource that could be captured to manage and support future parking demand growth.</p>	<p>- It is estimated that costs associated with this strategy would be mostly expended in efforts of existing staff and volunteers to review and identify opportunity sites and conduct outreach to potential private sector participants.</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>12</p> <p>Implement variable-rate pricing for on-street permits based on location, demand, and availability of parking. This will create pricing differentials between “premium” and underutilized locations.</p>		✓		<p>Variable-rate pricing uses rates to influence behavior. The outcome of effective use of variable-rate pricing is better distribution of users into facilities, particularly underused facilities. At present, Bend does not use this type of pricing.</p>	<ul style="list-style-type: none"> - It is estimated that costs associated with this strategy would be mostly expended in efforts of existing staff (Parking Demand Manager) and DPAC meetings to review and provide recommendations for rate re-calibration. - The City could consider a third-party rate study, which would likely be in the range of \$15,000 - \$20,000. - Overall, the rate changes could result in additional revenue to the City.

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>13</p> <p>Reduce or phase out the number of “2-Hour or as Otherwise Specified” on-street stalls in coordination with Strategies 11 and 12 above to simply “2-Hour Parking.”</p>		✓		<p>There are currently 242 stalls within the downtown study zone designated “2 Hours – Unless Otherwise Specified.” These stalls allow short-term visitor parking (2 hours) but also can be used all day by employees displaying a valid on-street parking permit. Data shows these stalls are having an adverse impact on turnover and customer/visitor access to the on-street supply.</p>	<p>- Estimated at \$30 per sign for replacement of existing time stay signage (plus labor to install)</p>
<p>14</p> <p>Based on documented parking behavior, establish distinct on-street parking management zones in the downtown parking district. Use 2016 and Strategy 20 occupancy data to define the boundaries.</p>		✓		<p>Data suggests that different sectors of the downtown perform differently. These unique areas should be considered for management as unique parking management zones, to reflect the nature of demand within them. 2016 data and data derived from Strategy 20 can help inform development of these zones.</p>	<p>- Estimated at \$30 per sign for replacement of existing time stay signage (plus labor to install)</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>15 Eliminate free parking for the first two hours at the Mirror Pond lots.</p>		✓		<p>Spring and Summer data from 2016 show that the North and South Mirror Pond lots are occupied at 85% or greater for significant periods of the day. Also, current conditions at the lot need to be upgraded to improve the visible appearance and safety of the lots. This would include improved signage, better lighting and changes to the landscaping to improve sightlines and discourage loitering in the lot.</p>	<p>-Costs associated with new signage, lighting/safety improvements and landscaping would be developed in an action plan by the Parking Demand Manager and the DPAC.</p>
<p>16 Create a critical path timeline to a new parking brand that can be utilized at all City-owned lots and shared facilities, and in marketing and communications.</p>		✓		<p>Create a brand that unifies the public supply of parking and is easily communicated, both at parking sites and, ideally, through a wayfinding system located throughout the downtown and on maps, websites and other communications and promotions.</p>	<p>- It is estimated that engaging a design consultant to carry out the tasks identified above would range from \$20,000 - \$25,000.</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>17</p> <p>Standardize the design of on-street parking signage in the parking management district and incorporate the new brand/logo.</p>		✓		<p>Creating more clarity in on-street parking would simplify parking for customers and allow a consistent time stay throughout the downtown that is supported by duration of stay findings from the 2016 parking study.</p>	<p>- Unit costs:</p> <ul style="list-style-type: none"> • Pole unit cost = \$470 • Blade sign unit cost = \$30 <p>- Unit costs would need to be calibrated to numbers identified through a signage inventory.</p>
<p>18</p> <p>Rename all public parking facilities by address.</p>	✓	✓		<p>Industry best practices for naming off-street parking facilities suggests using addresses associated with the main auto ingress point into a facility.</p>	<p>\$5,000 - \$10,000</p>
<p>19</p> <p>Establish best-practice protocols and performance metrics for enforcement personnel and support enforcement with appropriate technology.</p>		✓		<p>The foundation of sound parking management is enforcement. Without enforcement, systems designed to encourage turnover (time stays, pricing) and deter employees from maximizing on-street parking are ineffective.</p>	<p>- Work with Diamond Parking to develop a PEO and technology plan that deploys labor and technology in a manner that limits time stay violations to between 5% and 7%. New costs would be identified through this process.</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>20</p> <p>Where practical, expand the bike parking network to connect parking and the downtown, encouraging employee bike commute trips and drawing customers to downtown businesses.</p>		✓		<p>The downtown is lacking sufficient “trip-end” bike parking amenities, both on-street, off-street and in private buildings. Providing adequate bicycle parking will expand the capacity of the overall parking supply downtown.</p>	<p>Unit costs:</p> <ul style="list-style-type: none"> - Staple or U racks: \$150 - \$200 - Wall-mounted racks: \$130 - \$150 - Bike Corral: \$1,200 - Art racks: variable by design
<p>21</p> <p>Develop a reasonable schedule of data collection—every two years—to assess performance of the parking supply and support the 85% Rule for decision-making.</p>		✓	✓	<p>Objective, up-to-date data on occupancy, seasonality, turnover, duration of stay, patterns of use, and enforcement will help the City and stakeholders make better-informed decisions as the downtown grows.</p>	<ul style="list-style-type: none"> - It is estimated that a data inventory and turnover/occupancy study would range from \$45,000-\$50,000 if conducted by a third-party consultant.

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>22</p> <p>Using data collected per Strategy 21, evaluate on-street pricing by zone in high-occupancy areas. If peak occupancy exceeds 85%, implement on-street pricing during enforcement hours where appropriate.</p>		✓	✓	<p>Strategies 10 – 20, once implemented, are intended to significantly change how parking is used and communicated in the downtown. The impacts of these changes will be objectively quantified in Strategy 21. This will give the City, the DPAC and the community an opportunity to see if peak occupancies and constraints identified in the 2016 study have been mitigated through the recommended strategies through the first 24 months of the plan.</p>	<p>Unit costs:</p> <ul style="list-style-type: none"> - Multi-Space Meters (pay stations): \$5,000 - \$7,000 per unit - Single-Space Meters: \$500 - \$700 per unit - Back office support: Varies by system and software selected
<p>23</p> <p>Eliminate free parking in the public garage when garage occupancies exceed 85% and on-street parking is priced. Implement demand-based pricing for all hours of enforced parking—e.g., hourly, evening, weekend, overnight, and event rates.</p>		✓	✓	<p>If the decision is made to price on-street parking, the DSAC recommends that pricing also be implemented in the public garage. Pricing should be demand based, integrated with on-street pricing and varied to reflect the unique dynamics of weekday, evening, weekend, overnight and event situations.</p>	<p>New equipment and signage may be necessary to transition to a more complex rate format. Estimating these costs will be a part of the infrastructure evaluation recommended in Strategy 23. Over time, pricing at the garage will result in new revenue to the City.</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
PARKING MANAGEMENT ACTION STRATEGIES – INFRASTRUCTURE (PHASE 2)					
<p>24</p> <p>Develop and implement improvements at the downtown public parking garage to enhance its appearance, identity, safety, revenue control, communications technology, and pedestrian access.</p>			✓	<p>Current access, revenue control, lighting and communications systems at the City’s public garage are outdated and, at times, unreliable and beyond useful service lives. Moreover, management systems do not provide data and reporting functions that are essential for high-level management and decision-making.</p>	<p>- \$100,000 - \$150,000 depending on systems selected.</p>
<p>25</p> <p>Solicit firms to establish wayfinding and/or dynamic signage systems in the public right of way, integrated with the off-street system using City parking brand developed in Strategy 16.</p>			✓	<p>The most successful programs tie into a parking brand incorporated into both the on-site and right-of-way signage. This provides customers a visual cue that translates from their first encounter on the roadway to being able to conveniently identify a parking location with available parking.</p>	<p>- It is assumed that costing for wayfinding would be incorporated into the solicitation.</p>

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>26</p> <p>If existing parking becomes limited, explore expanding access capacity with new transit and parking.</p>			✓	<p>In anticipation of growth, the City should evaluate other forms of access capacity as well, including improved transit and/or circulator options and new parking supply. These types of capacity growth require sophisticated infrastructure and are very costly. It will be important for Bend to give adequate time and effort to determine the most beneficial and cost-effective formats for increasing the capacity of the downtown access system.</p>	<ul style="list-style-type: none"> - Identifying and locating potential parking sites could be accomplished internally, with assistance from the DBBA, local developers, and Community Development. As an estimate, the City could incur costs of \$25,000-\$35,000 for route and system planning for a new transit/shuttle options.

Strategy	Immediate Near Term (0 – 12 months)	Phase 1 (12 – 24 months)	Phase 2 (24 – 48 months)	Comment	Estimated Cost
<p>27 Develop cost forecasts and feasible financing methods for preferred parking supply and transit/shuttle options.</p>			✓	<p>Cost forecasting preferred transit and new parking supply options developed in Strategy 26 would be conducted at this time. These costs would be matched with potential funding options developed and narrowed in Strategy 7.</p>	<p>- \$5,000 - \$7,500 for garage cost pro-forma.</p> <p>Structured Underground: - \$35,000-\$45,000 per stall</p> <p>Structured Above Ground: - \$20,000-\$25,000 per stall</p> <p>Surface Lot: - \$ 5,000 - \$7,000 per stall</p> <p>- Transit or shuttle routes determined in Strategy 26.</p>
<p>28 Expand capacity expansion as necessary and feasible.</p>			✓	<p>This strategy would be catalyzed by completion of Strategies 7, 26 and 27 and would complete Phase 2 of the Downtown Strategic Parking Management Plan.</p>	<p>To be determined.</p>




CITY OF BEND

2017

City of Bend, Oregon Downtown Strategic Parking Management Plan **APPENDIX REPORT**

Report of the Downtown Stakeholder Advisory Committee (DSAC)

FINAL REPORT
May 31, 2017



RICK WILLIAMS CONSULTING
Parking & Transportation

Table of Contents

APPENDIX A – 2016 Spring Parking Data Summary.....	1
APPENDIX B – 2016 Summer Parking Data Summary	24
APPENDIX C – Parking Data Collection Methodology.....	47
APPENDIX D – Sample Parking Rate Policy – South San Francisco, CA.....	62
APPENDIX E – Downtown Parking Study Public Engagement Summary	69
APPENDIX F – May 11, 2017 Open House Summary.....	76

DOWNTOWN BEND PARKING STUDY
RAW DATA SUMMARY (April 28 and April 30, 2016)
 June 16, 2016

I. STUDY AREA

Figure A
Parking Study Area



2016

-  Parking Study Area
-  Economic Improvement District
-  Bend Parking District



II. INVENTORY


Table 1
2016 Bend Parking Inventory and Study Area

Stalls by Type	Inventory Area	% of Total	Study Area	% of Total
15 Minutes	22	1.2%	20	1.5%
30 Minutes	1	< 1%	1	< 1%
30 Minutes (Unless Otherwise Specified)	10	< 1%	10	< 1%
2 Hours	706	39.1%	678	50.9%
2 Hours (Unless Otherwise Specified)	242	13.4%	242	18.2%
No Limit	766	42.4%	326	24.5%
ADA 'Accessible'	41	2.3%	39	2.9%
Authorized Vehicles Only	9	< 1%	9	< 1%
Police Only	8	< 1%	8	< 1%
<i>On-Street Supply</i>	<i>1,805</i>	<i>100%</i>	<i>1,333</i>	<i>73.9%</i>
<i>Off-Street Supply</i>	<i>3,998 (158 sites)</i>	<i>100%</i>	<i>2,650 (46 sites)</i>	<i>66.3%</i>
Total Parking Supply	5,803	100%	3,983	68.6%

- There are 1,805 total on-street stalls within the original inventory area. RWC collected hourly license plate data counts for 1,333 stalls which are located within the black line boundary in Figure A above. This represents a 73.9% sample size of the on-street supply.
- There are a total of 3,998 off-street stalls within the original inventory area located in 158 unique parking sites. RWC collected hourly occupancy data for 2,650 of these stalls located on 46 sites. This represents a 66.3% sample size (for stalls) and 30% sample size (for locations). A full summary table of all lots and those lots surveyed is located in Table 5 at the end of this document.
- The majority of parking in the study area (69.1%) is either signed for two hours (50.9%) or 2 Hours "Unless Otherwise Specified (18.2%)."

III. ON-STREET UTILIZATION

Figure B
Hourly On-street Utilization (Comparative)



Weekday (Thursday, 4/28/2016)

- The peak hour for on-street parking (weekday) is between 2PM and 3PM. At this hour, 73.3% of all on-street stalls are occupied.
- Occupancies decline in every hour between 3PM and 6 PM, bumping upward at 7 PM.

Weekend (Saturday, 4/30/2016)

- The peak hour for on-street parking (weekend) is between 7PM and 8PM. At this hour, 57.2% of all on-street stalls are occupied.
- Occupancies increase in eight of the ten hours data was collected, dropping slightly between 4 PM and 6 PM.
- Overall weekend vehicle activity is much less than the weekday activity.
- Weekend evening activity (6 PM to 8 PM) is comparable to weekday.

Table 2
2016 Bend On-Street Parking Utilization (Comparative)

2016 Downtown Bend On-Street Parking Utilization – Comparative							
Type of Stall	Study Date	# of Stalls	Peak Hour	Peak Occupancy	Stalls Available	Average Length of Stay	Violation Rate
On-Street Peak	<i>Weekday</i>	1,333	1:30 – 2:30 PM	73.3%	351	2 hr./ 4 min	8.8%
	<i>Weekend</i>		6:30 – 7:30 PM	57.2%	563	1 hr./ 43 min	8.4%
Usage by Time Stay (by User Type)							
15 Minute	<i>Weekday</i>	20	11:30 AM – 12:30 PM 1:30 – 2:30 PM	70.0%	6	N/A	5.3%
	<i>Weekend</i>		12:30 – 1:30 PM	55.0%	9	N/A	5.0%
30 Minute	<i>Weekday</i>	11	6:30 – 7:30 PM	54.5%	5	N/A	8.7%
	<i>Weekend</i>		5:30 – 6:30 PM	72.7%	3	N/A	31.8%
2 Hour (Signed)	<i>Weekday</i>	678	12:30 – 1:30 PM	72.9%	172	1 hr./ 37 min	8.8%
	<i>Weekend</i>		6:30 – 7:30 PM	70.8%	184	1 hr./ 30 min	7.4%
2 Hour (Unless Otherwise Specified)	<i>Weekday</i>	242	1:30 – 2:30 PM	71.1%	68	2 hr./ 29 min	9.5%
	<i>Weekend</i>		6:30 – 7:30 PM	51.2%	117	1 hr./ 58 min	13.8%
Authorized Vehicle Only	<i>Weekday</i>	9	9:30 AM – 12:30 PM 1:30 – 3:30 PM	100%	0	5 hr./ 35 min	N/A
	<i>Weekend</i>		N/A	0%	9	N/A	N/A
Police Only	<i>Weekday</i>	8	1:30 – 2:30 PM	62.5%	3	1 hr./ 0 min	N/A
	<i>Weekend</i>		N/A	0%	8	N/A	N/A
ADA 'Accessible'	<i>Weekday</i>	39	12:30 – 1:30 PM	35.9%	25	1 hr./ 49 min	N/A
	<i>Weekend</i>		6:30 – 7:30 PM	35.9%	25	1 hr./ 19 min	N/A
No Limit	<i>Weekday</i>	326	11:30 AM – 12:30 PM	81.9%	56	3 hr./ 58 min	N/A
	<i>Weekend</i>		3:30 – 4:30 PM	36.8%	202	3 hr./ 6 min	N/A

Weekday (Thursday, 4/28/2016)

- The average time stay for all users is 2 hours/4 minutes. This includes those using permits and stalls with no time limits (see Table 3 below for additional detail).

- The average time stay for users of 2 Hour (Signed) stalls is 1 hour/37 minutes (weekdays) and 1 hour/30 minutes (weekend), which is indicative of a typical visitor trip.
- The impact of permit users in 2 Hour (Unless Otherwise Specified) stalls raises average time stays in these short term stalls to 2 hours/29 minutes (weekday) and 1 hour/58 minutes (weekend) .
- The overall violation rate is 8.8% of unique vehicles. Violation rates are highest in 2 hours – Or Otherwise Specified (9.5%). Industry standards would strive for a rate of between 5% and 7%.

Weekend (Saturday, 4/30/2016)

- The average time stay for all users is 1 hour/43 minutes. This includes those using permits and stalls with no time limits (see Table 3 below for more detail).
- Weekend peak hour occupancies in 2 Hour (Or Otherwise Specified) stalls drop considerably (51.2%) when contrasted to weekday occupancies (71.1%). This is likely due to the fact that there are significantly fewer permits in use on the weekend.
- The overall violation rate is 8.4% of unique vehicles. Violation rates area highest in 2 hours – Or Otherwise Specified (13.8%) and 30-minute (31.8%) stalls. Industry standards would strive for a rate of less than 7%.

Table 3
2016 Bend On-Street Parking - Characteristics of Use (Comparative)

Use Characteristics	Weekday			Weekend		
	All Users	Non-Permit Users	Permit Users	All Users	Non-Permit Users	Permit Users
Average length of stay per vehicle per occupied stall	2 hr./ 4 min	1 hr./ 49 min	4 hr./ 39 min	1 hr./ 43 min	1 hr./ 40 min	4 hr./ 18 min
Actual number of unique vehicles	4, 156	3,791	365	3,307	3,236	71
Actual turnover rate (number of cars to use a single occupied stall over a 10-hour period)	4.85	5.52	2.15	5.81	6.01	2.33
Number of non-permit vehicles parked 5 or more hours in time limited stalls (% of all unique license plates)		60 (1.4%)			36 (1.1%)	
ADA placards observed in non-ADA Accessible designated stalls (% of occupied stalls)			4 (< 1%)			3 (< 1%)
Permits displayed in time-limited stalls at the peak hour (% of occupied stalls); excludes handicap placards.			159 (16.5%)			17 (2.3%)
License plates observed moving from one space to another (% of non-permit unique vehicles)		199 (5%)			124 (3.8%)	

Weekday (Thursday, 4/28/2016)

- The average time stay for all users is 2 hour/4 minutes. Those without permits are parking for 1 hour/49 minutes. Permit users are parking for an average of 4 hours/39 minutes.
- For the most part, 2 hour stalls are accommodating actual time stay demand for visitors.
- Over the course of the 10 hour survey day, a total of 4,156 vehicles parked on-street. Of this total, 3,791 cars (91%) were visitor trips and 365 (9%) were vehicles using permits.
- The turnover rate for all users is 4.85, which is below the minimum industry standard of 5.0. The rate increases to 5.52 when permit holders (2.15) are factored out of the equation.
- 60 vehicles were parked in time limited stalls (e.g., 2 hour) for 5 or more hours. These vehicles did not display permits.
- Only 4 vehicles displaying ADA placards or plates parked in the general parking supply. This indicates that ADA needs are being met in available signed ADA "Accessible" stalls.


- 159 vehicles with permits were parked in 2 Hour (unless otherwise specified stalls) at the peak hour, this represented about 17% of all vehicles parked at that hour.
- 199 vehicles were observed moving from one stall to another (i.e., at least one move). This represents 5% of all vehicles using the on-street supply on the survey day.

Weekend (Saturday, 4/30/2016)

- The average time stay for all users is 1 hour/43 minutes. Those without permits are parking for 1 hour/40 minutes. Permit users are parking for an average of 4 hours/18 minutes.
- For the most part, 2 hour stalls are accommodating actual time stay demand for visitors.
- Over the course of the 10 hour survey day, a total of 3,307 vehicles parked on-street. Of this total, 3,236 cars (98%) were visitor trips and 71 (2%) were vehicles using permits.
- The turnover rate for all users is 5.81. The rate increases to 6.01 when permit holders (2.33) are factored out of the equation.
- 36 vehicles were parked in time limited stalls (e.g., 2 hour) for 5 or more hours. These vehicles did not display permits.
- Only 3 vehicles displaying ADA placards or plates parked in the general parking supply. This indicates that ADA needs are being met in available signed ADA "Accessible" stalls.
- 17 vehicles with permits were parked in 2 Hour (unless otherwise specified stalls), this represented less than 3% of all vehicles parked at that hour.
- 124 vehicles were observed moving from one stall to another (i.e., at least one move). This represents approximately 4% of all vehicles using the on-street supply on the survey day.

IV. OFF-STREET OCCUPANCIES

Figure C
Hourly Occupancies (Comparative)

*Weekday (Thursday, 4/28/2016)*

- The peak hour for off-street parking (weekday) is between 3PM and 4PM. At this hour, 59.7% of off-street stalls are occupied.
- The very flat level of occupancies between 10 AM and 4 PM indicates employee use. There is little variation in activity.
- Occupancies decline significantly after 5:00 PM.

Weekend (Saturday, 4/30/2016)

- The peak hour for off-street parking (weekend) is between 7PM and 8PM. At this hour, 34.6% of off-street stalls are occupied.
- As with the weekday data, the flat levels of occupancy throughout the day (particularly between 10 AM and 5 PM) indicates employee use.
- Occupancies increase after 5 PM, indicating new users coming into the downtown for evening activities.

Table 4
Summary of 46 Off-street Sites Surveyed (Comparative)

Lot Number	Facility Identification	Survey Date	# of Stalls	Peak Occupancy/ Hour	Stalls Available
2	Deschutes County	Weekday	27	92.6% 9:30 – 10:30 AM	2
		Weekend		40.7% 12:30 – 1:30 PM	16
10	Silvermoon Brewing	Weekday	53	52.8% 6:30 – 7:30 PM	25
		Weekend		24.5% 2:30 – 4:30 PM 6:30 – 7:30 PM	40
17	Deschutes Co. Annex Building	Weekday	80	82.5% 12:30 – 1:30 PM	14
		Weekend		23.8% 10:30 AM – 1:30 PM	61
18	Co Services Building	Weekday	33	66.7% 10:30 – 11:30 AM	11
		Weekend		30.3% 9:30 – 10:30 AM	23
21	Deschutes Co. Courthouse - 2 hr. customer parking	Weekday	11	72.7% 9:30 – 10:30 AM	3
		Weekend		18.2% 9:30 – 11:30 AM	9
22	Bank of Cascades	Weekday	46	60.9% 10:30 – 11:30 AM	18
		Weekend		13.0% 1:30 – 2:30 PM	40
23	70 Newport Chinese & Sushi bar/journey	Weekday	30	93.3% 6:30 – 7:30 PM	2
		Weekend		90.0% 4:30 – 5:30 PM	3
24	Permit Parking Only	Weekday	104	27.9% 1:30 – 2:30 PM	75
		Weekend		29.8% 9:30 – 10:30 AM	73
30	Public Parking - North Lot	Weekday	79	100% 5:30 – 6:30 PM	0
		Weekend		96.2% 6:30 – 7:30 PM	3
31	Public Parking - South Lot	Weekday	97	100% 6:30 – 7:30 PM	0
		Weekend		95.9% 6:30 – 7:30 PM	4

32	Bank of America	Weekday	17	47.1% 12:30 – 1:30 PM 4:30 – 5:30 PM	9
		Weekend		64.7% 6:30 – 7:30 PM	6
34	Public 2hr parking	Weekday	33	100% 5:30 – 6:30 PM	0
		Weekend		93.9% 5:30 – 7:30 PM	2
36	US Bank	Weekday	21	71.4% 6:30 – 7:30 PM	6
		Weekend		81.0% 1:30 – 3:30 PM	4
38	Permit Parking Only	Weekday	24	83.3% 9:30 – 10:30 AM 4:30 – 6:30 PM	4
		Weekend		100% 6:30 – 7:30 PM	0
39	Alpine Mortgage/Deschutes Land Trust	Weekday	14	85.7% 9:30 – 10:30 AM 2:30 – 3:30 PM	2
		Weekend		50.0% 2:30 – 3:30 PM	7
44	Gateway Plaza - Permit Only	Weekday	57	64.9% 2:30 – 3:30 PM	20
		Weekend		5.3% 2:30 – 3:30 PM	54
45	First American Title	Weekday	28	121.4% 2:30 – 3:30 PM	-6
		Weekend		35.7% 2:30 – 6:30 PM	18
67	Building 18	Weekday	8	100% 9:30 – 10:30 AM	0
		Weekend		12.5% 9:30 – 10:30 AM 12:30 – 1:30 PM	7
68	Foundry Church	Weekday	17	117.7% 6:30 – 7:30 PM	-3
		Weekend		29.4% 6:30 – 7:30 PM	12
69	Public Parking Garage	Weekday	547	49.5% 11:30 AM – 12:30 PM	276
		Weekend		47.9% 6:30 – 7:30 PM	285
71	Wells Fargo	Weekday	24	100% 6:30 – 7:30 PM	0

		Weekend		100% 6:30 – 7:30 PM	0
72	Bank of Cascades	Weekday	14	92.9% 1:30 – 4:30 PM	1
		Weekend		92.9% 10:30 – 11:30 AM	1
76	Chase Bank	Weekday	35	51.4% 3:30 – 4:30 PM	17
		Weekend		60.0% 6:30 – 7:30 PM	14
80	Amerititle	Weekday	41	53.7% 2:30 – 3:30 PM	19
		Weekend		24.4% 6:30 – 7:30 PM	31
81	Alexander Drake	Weekday	95	75.8% 9:30 – 10:30 AM	23
		Weekend		26.3% 9:30 – 11:30 AM	70
82	DoubleTree	Weekday	79	89.9% 6:30 – 7:30 PM	8
		Weekend		72.2% 5:30 – 6:30 PM	22
85	Jameson Building	Weekday	40	47.5% 4:30 – 5:30 PM	21
		Weekend		17.5% 5:30 – 6:30 PM	33
89	Hawthorne Square Parking	Weekday	62	62.9% 12:30 – 2:30 PM	23
		Weekend		8.1% 5:30 – 7:30 PM	57
95	SEND Transportation/Salon Art of Beauty	Weekday	19	89.5% 2:30 – 3:30 PM	2
		Weekend		15.8% 10:30 – 11:30 AM	16
104	Old St. Francis McMenamins Guests Only	Weekday	25	100% 2:30 – 3:30 PM 6:30 – 7:30 PM	0
		Weekend		100% 3:30 – 5:30 PM	0
112	City Hall	Weekday	20	40.0% 9:30 – 10:30 AM	12
		Weekend		10.0% 6:30 – 7:30 PM	18
115	Customer 2hr Free Parking	Weekday	13	53.9% 10:30 – 11:30 AM 3:30 – 4:30 PM	6

		Weekend		115.4% 5:30 – 6:30 PM	-2
118	City Employee Vehicles Only	Weekday	39	84.6% 10:30 – 11:30 AM	6
		Weekend		79.5% 12:30 – 1:30 PM	8
125	2 hr. parking/ Permit Parking	Weekday	68	100% 10:30 – 11:30 AM 2:30 – 3:30 PM	0
		Weekend		25.0% 6:30 – 7:30 PM	51
126	School District Permit Parking Only	Weekday	45	97.8% 9:30 – 10:30 AM 11:30 AM – 12:30 PM 3:30 – 4:30 PM	1
		Weekend		28.9% 4:30 – 5:30 PM	32
129	Boys and Girls Clubs of Bend	Weekday	33	100% 9:30 – 11:30 AM	0
		Weekend		33.3% 10:30 – 11:30 AM	22
131	2 hr. parking/ Permit Parking	Weekday	41	97.6% 10:30 – 11:30 AM 12:30 – 1:30 PM	1
		Weekend		56.1% 6:30 – 7:30 PM	18
132	Hawthorn Healing Arts Center	Weekday	17	58.8% 10:30 AM – 12:30 PM	7
		Weekend		0% 9:30 AM – 7:30 PM	17
135	Church Parking	Weekday	31	67.7% 12:30 – 1:30 PM	10
		Weekend		16.1% 9:30 – 10:30 AM	26
149	First United Methodist Church	Weekday	35	82.9% 4:30 – 5:30 PM	6
		Weekend		40.0% 9:30 – 10:30 AM	21
150	Deschutes Historical Museum	Weekday	41	85.4% 12:30 – 1:30 PM	6
		Weekend		22.0% 2:30 – 3:30 PM	32
154	Deschutes Library Parking Only	Weekday	64	95.3% 2:30 – 3:30 PM	3
		Weekend		18.8% 12:30 – 1:30 PM	52

155	Worrell Wayside Park	Weekday	82	80.5% 9:30 – 10:30 AM	16
		Weekend		6.1% 9:30 – 11:30 AM 1:30 – 2:30 PM 3:30 – 4:30 PM	77
156	Deschutes Services Building	Weekday	120	95.0% 9:30 – 10:30 AM	6
		Weekend		11.7% 10:30 – 11:30 AM 1:30 – 2:30 PM	106
157	Wall Street Services Building	Weekday	209	77.0% 10:30 – 11:30 AM	48
		Weekend		5.3% 10:30 – 11:30 AM	198
Off-Street Supply Studied (46 sites)		Weekday	2,650	59.7% 2:30 – 3:30 PM	1,069
		Weekend		34.6% 6:30 – 7:30 PM	1,732
Total Off-Street Supply		Weekday	3,998	59.7% 2:30 – 3:30 PM	1,611
		Weekend		34.6% 6:30 – 7:30 PM	2,615

V. PEAK HOUR HEAT MAPS

FIGURE C
Weekday (4/28/2016) Peak Hour



Combined Parking Utilization


	> 85%		> 85%
	84% - 70%		84% - 70%
	69% - 55%		69% - 55%
	< 55%		< 55%
	< 55%		Construction
			No Parking

RICK WILLIAMS CONSULTING
Parking & Transportation

April 28, 2016
1:30 - 2:30 PM
Peak Hour

0 95 190 380 570 760 Feet

FIGURE D
Weekend (4/30/2016) Peak Hour



VI. COMPLETE OFF-STREET INVENTORY

Table 5
Summary of 158 Off-street Sites (surveyed sites in red)

Lot Number	Facility Identification	# of Stalls	% of Total
1	Tax Drop Box	30	< 1%
2	Deschutes County	27	< 1%
3	Law Firm Parking	10	< 1%
4	State Fire Marshal Truck - Gated	26	< 1%
5	Century Link	22	< 1%
6	Francis, Hansen, Martin	18	< 1%
7	Vacant Lot	8	< 1%
8	Vacant Lot	10	< 1%
9	Naus	20	< 1%
10	Silvermoon Brewing	53	1.3%
11	Oxiliary	11	< 1%
12	Carl W Hopp/academic De Ballot Classique	14	< 1%
13	Bend Theatre for young people	4	< 1%
14	Bendtel Inc	22	< 1%
15	Olde Towne Pizza	9	< 1%
16	MJ Tavern/Nelson Laundry	10	< 1%
17	Deschutes Co. Annex Building	80	2.0%
18	Co Services Bldg	33	< 1%
19	True Gospel United Pentecostal Church	6	< 1%
20	Public Safety Bldg	34	< 1%

21	Deschutes Co. Courthouse - 2 hr. customer parking	11	< 1%
22	Bank of Cascades	46	1.2%
23	70 Newport Chinese & Sushi bar/journey	30	< 1%
24	Permit Parking Only	104	2.6%
25	Columbia Bank/RBC Wealth Mgmt. Upper Structure	33	< 1%
26	1133 NW Wall Lower Structure	28	< 1%
27	1183 NW Wall (behind/below)	33	< 1%
28	1197/1199 Oregrown	8	< 1%
29	325 Building	3	< 1%
30	North Lot	79	2.0%
31	South Lot	97	2.4%
32	Bank of America	17	< 1%
33	Permit Parking Only	18	< 1%
34	Public 2hr parking	33	< 1%
35	Private Permit Only	10	< 1%
36	US Bank	21	< 1%
37	Crabtree and Ramsdorf Employees	11	< 1%
38	Permit Parking Only	24	< 1%
39	Alpine Mortgage/Deschutes Land Trust	14	< 1%
40	Bank of Cascades	11	< 1%
41	Peterkin Associates	3	< 1%
42	Cole Brett	7	< 1%
43	Unmarked Lot	45	1.1%

44	Gateway Plaza - Permit Only	57	1.4%
45	First American Title	28	< 1%
46	Irving Professional Building	10	< 1%
47	Only for Old Cigar	8	< 1%
48	Unmarked	3	< 1%
49	Unmarked	3	< 1%
50	I Mortgage	26	< 1%
51	Unmarked	3	< 1%
52	Pfeifer and Associates	5	< 1%
53	Mom's Tattoos	5	< 1%
54	Resort Resources	7	< 1%
55	Lucas Hovie Parking	10	< 1%
56	Cascade Network	9	< 1%
57	Law Office	5	< 1%
58	Zivney Parking	4	< 1%
59	Bend Counseling And Bio Feed	6	< 1%
60	Gravel Lot	24	< 1%
61	Cascade Transitions Crest Staff and Client	64	1.6%
62	Lerr, Oliver & Company	4	< 1%
63	Thomas E Wold D.M.O	10	< 1%
64	Niswonger, Reynolds Chapel	15	< 1%
65	Medical Cannabis	7	< 1%
66	A Muse Studio	7	< 1%

67	Building 18	8	< 1%
68	Foundry Church	17	< 1%
69	Public Parking Garage	547	13.7%
70	On Point Credit Union	19	< 1%
71	Wells Fargo	24	< 1%
72	Bank of Cascades	14	< 1%
73	Fresh Bread	12	< 1%
74	Reserved	13	< 1%
75	Reserved for Tenant Parking	16	< 1%
76	Chase Bank	35	< 1%
77	Permit Parking Only	7	< 1%
78	Connecting Point Computer	20	< 1%
79	Private Parking Under Ground		
80	Amerititle	41	1.0%
81	Alexander Drake	95	2.4%
82	DoubleTree	79	2.0%
83	Accounting Group	9	< 1%
84	Residential	5	< 1%
85	Jameson Building	40	1.0%
86	Residential	10	< 1%
87	Retail/Commercial	18	< 1%
88	Law Office	6	< 1%
89	Hawthorne Square Parking	62	1.6%

90	Residential	12	< 1%
91	Mixed Use/Retail	9	< 1%
92	Unknown	9	< 1%
93	Unknown	2	< 1%
94	Law Office	7	< 1%
95	SEND Transportation/Salon Art of Beauty	19	< 1%
96	Residential	8	< 1%
97	Saving Grace Counseling	5	< 1%
98	The Steele Law Firm	2	< 1%
99	Three Rivers	7	< 1%
100	Shelton Kelley Realtor	15	< 1%
101	American Family Insurance	4	< 1%
102	Putient Healthcare	6	< 1%
103	Christmas Preserce Retail	7	< 1%
104	Old St. Francis Mcmenamims Guests Only	25	< 1%
105	Reserved Stalls	32	< 1%
106	Pangea International Cuisine, Thump Coffee, Fire in Bend	14	< 1%
107	Reserved for Brooks Resources Corporation	15	< 1%
108	Reserved for McMenamims	12	< 1%
109	Salud Parking	2	< 1%
110	Reserved for Remax	3	< 1%
111	Tenant/The Broker Network	9	< 1%
112	City Hall	20	< 1%

113	Authorized Vehicles Only	22	< 1%
114	The Oregon Store	10	< 1%
115	Customer 2hr Free Parking	13	< 1%
116	City Employee Parking Only	28	< 1%
117	Tenant Parking Only	23	< 1%
118	City Employee Vehicles Only	39	1.0%
119	Park Building Office Suites	5	< 1%
120	Law Offices Brothers, Hawn and Coughlin	7	< 1%
121	Sundowner Capital Management + LLC	3	< 1%
122	Lara House Bed and Breakfast	6	< 1%
123	Deschutes Library Parking Only Alley	15	< 1%
124	Law Office Alley-Lis Fancherr Attn.	4	< 1%
125	2 hr. parking/ Permit Parking	68	1.7%
126	School District Permit Parking Only	45	1.1%
127	Education Center Bend/La Pine school district	12	< 1%
128	Bend Community Radio Entrance	8	< 1%
129	Boys and Girls Clubs of Bend	33	< 1%
130	No Name	4	< 1%
131	2 hr. parking/ Permit Parking	41	1.0%
132	Hawthorn Healing Arts Center	17	< 1%
133	Residential	16	< 1%
134	Residential Rental	6	< 1%
135	Church Parking	31	< 1%

136	Mixed Use/Commercial	10	< 1%
137	Commercial	12	< 1%
138	Kate's Place	15	< 1%
139	Law Office	8	< 1%
140	Small World Collection	3	< 1%
141	Chop Hair	2	< 1%
142	Tuner Automotive	8	< 1%
143	Old Stone Church Parking	21	< 1%
144	ReVive	6	< 1%
145	Cascade Summit Insurance	5	< 1%
146	Retail/Commercial	3	< 1%
147	Engineering	9	< 1%
148	Griffen Heating and Cooling	13	< 1%
149	First United Methodist Church	35	< 1%
150	Deschutes Historical Museum	41	1.0%
151	School St Helens/ Broadway - Amity Creek Magnet School	10	< 1%
152	Trinity Episcopal Church	1	< 1%
153	Trinity Episcopal Church	12	< 1%
154	Deschutes Library Parking Only	64	1.6%
155	Worrell Wayside Park	82	2.1%
156	Deschutes Services Building	120	3.0%
157	Wall Street Services Building	209	5.2%
158	Wall Street Services Fleet Parking Only	59	1.5%

	Total Off-Street Supply (158 sites)	3,998	100%
	Off-Street Supply Studied (46 sites)	2,650	66.3%

DOWNTOWN BEND PARKING STUDY
RAW DATA SUMMARY (July 20 and July 22, 2016)
 August 18, 2016


I. STUDY AREA

Figure A
Parking Study Area



2016

-  Parking Study Area
-  Economic Improvement District
-  Bend Parking District



II. INVENTORY

Table 1
2016 Bend Parking Inventory and Study Area

Stalls by Type	Inventory Area	% of Total	Study Area	% of Total
15 Minutes	22	1.2%	20	1.5%
30 Minutes	1	< 1%	1	< 1%
30 Minutes (Unless Otherwise Specified)	10	< 1%	10	< 1%
2 Hours	706	39.1%	678	50.9%
2 Hours (Unless Otherwise Specified)	242	13.4%	242	18.2%
No Limit	766	42.4%	326	24.5%
ADA 'Accessible'	41	2.3%	39	2.9%
Authorized Vehicles Only	9	< 1%	9	< 1%
Police Only	8	< 1%	8	< 1%
<i>On-Street Supply</i>	1,805	100%	1,333	73.9%
<i>Off-Street Supply</i>	3,998 (158 sites)	100%	2,650 (46 sites)	66.3%
Total Parking Supply	5,803	100%	3,983	68.6%

On-street


- There are 1,805 total on-street stalls within the original inventory area.
- RWC collected hourly license plate data counts for 1,333 stalls which are located within the black line boundary in Figure A above. This represents a 73.9% sample size of the on-street supply.
- The majority of parking in the study area (69.1%) is either signed for two hours (50.9%) or 2 Hours "Unless Otherwise Specified (18.2%)."

Off-street

- There are a total of 3,998 off-street stalls within the original inventory area located in 158 unique parking sites.
- RWC collected hourly occupancy data for 2,650 of these stalls located on 46 sites. This represents a 66.3% sample size (for stalls) and 30% sample size (for locations). A full summary table of all lots and those lots surveyed is located in Table 5 at the end of this document.

III. ON-STREET UTILIZATION

Figure B
Hourly On-street Utilization (Comparative)



Weekday (Wednesday, 7/20/2016)

- The peak hour for on-street parking (Wednesday) is between 2PM and 3PM. At this hour, 80.8% of all on-street stalls are occupied.
- Occupancies decline in every hour between 3PM (80.7%) and 7 PM (63.1%).

Weekday (Friday, 7/22/2016)

- The peak hour for on-street parking (Friday) is between 1PM and 2PM. At this hour, 74.7% of all on-street stalls are occupied.
- Occupancies decrease in each hour between 2PM (71.2%) and 6PM (58.5%), rising slightly at 7PM (60.6%).
- Overall Friday vehicle activity is much less than activity found for Wednesday.
- Weekend evening activity (6 PM to 8 PM) is comparable to weekday.

Table 2
2016 Bend On-Street Parking Utilization (Comparative)

2016 Downtown Bend On-Street Parking Utilization – Comparative							
Type of Stall	Study Date	# of Stalls	Peak Hour	Peak Occupancy	Empty Stalls	Average Length of Stay	Violation Rate
On-Street Peak	Wednesday	1,333	1:30 – 2:30 PM	80.8%	253	2 hr/ 4 min	9.6%
	Friday		12:30 – 1:30 PM	74.7%	334	2 hr/ 0 min	8.4%
Usage by Time Stay (all users)							
15 Minute	Wednesday	20	5:30 – 6:30 PM	75.0%	5	N/A	6.7%
	Friday		1:30 – 2:30 PM	95.0%	1	N/A	2.7%
30 Minute	Wednesday	11	2:30 – 3:30 PM	54.5%	5	N/A	9.7%
	Friday		5:30 – 7:30 PM	63.6%	4	N/A	2.7%
2 Hour (Signed)	Wednesday	678	12:30 – 1:30 PM 2:30 – 3:30 PM 5:30 – 6:30 PM	76.5%	145	1 hr/ 40 min	9.4%
	Friday		12:30 – 1:30 PM	78.2%	138	1 hr/ 36 min	8.4%
2 Hour (Unless Otherwise Specified)	Wednesday	242	2:30 – 3:30 PM	75.6%	59	2 hr/ 21 min	10.9%
	Friday		10:30 – 11:30 AM	68.2%	73	2 hr/ 13 min	9.7%
Authorized Vehicle Only	Wednesday	9	1:30 – 2:30 PM	100%	0	3 hr/ 40 min	N/A
	Friday		10:30 – 11:30 AM	77.8%	2	2 hr/ 55 min	N/A
Police Only	Wednesday	8	9:30 – 10:30 AM 1:30 – 4:30 PM	25.0%	6	2 hr/ 30 min	N/A
	Friday		6:30 – 7:30 PM	25.0%	6	1 hr/ 45 min	N/A
ADA 'Accessible'	Wednesday	39	3:30 – 4:30 PM	48.7%	20	1 hr/ 33 min	N/A
	Friday		10:30 – 11:30 AM 12:30 – 1:30 PM	30.8%	27	1 hr/ 48 min	N/A
No Limit	Wednesday	326	1:30 – 2:30 PM	88.0%	39	3 hr/ 50 min	N/A
	Friday		11:30 AM – 12:30 PM	83.4%	54	4 hr/ 6 min	N/A

Weekday (Wednesday, 7/20/2016)

- The average time stay for all users is 2 hours/4 minutes. This includes those using permits and stalls with no time limits (see Table 3 below for additional detail).
- The average time stay for users of 2 Hour (Signed) stalls is 1 hour/40 minutes, which is indicative of a typical visitor trip.
- The impact of permit users in 2 Hour (Unless Otherwise Specified) stalls raises average time stays in these short term stalls to 2 hours/21 minutes.
- The overall violation rate is 9.6% of unique vehicles. Violation rates are highest in 2 hours – Or Otherwise Specified (10.9%). Industry standards would strive for a rate of between 5% and 7%.

Weekday (Friday, 7/22/2016)

- The average time stay for all users is 2 hours. This includes those using permits and stalls with no time limits (see Table 3 below for more detail).
- Friday peak hour occupancies in 2 Hour (Or Otherwise Specified) stalls drop considerably (68.2%) when contrasted to Wednesday occupancies (75.6%). This is likely due to the fact that employee permit demand drops as early weekend activities begin.
- The overall violation rate is 8.4% of unique vehicles. Violation rates area highest in 2 hours – Or Otherwise Specified (9.7%). Industry standards would strive for a rate of less than 7%.

Table 3
2016 Bend On-Street Parking - Characteristics of Use (Comparative)

Use Characteristics	Wednesday			Friday		
	All Users	Non-Permit Users	Permits Users	All Users	Non-Permit Users	Permit Users
Average length of stay per vehicle per occupied stall	2 hr/ 4 min	1 hr/ 52 min	5 hr/ 2 min	2 hr/ 0 min	1 hr/ 50 min	4 hr/ 25 min
Actual number of unique vehicles	4,677	4,375	302	4,318	4,032	286
Actual turnover rate (number of cars to use a single occupied stall over a 10-hour period)	4.84	5.36	1.99	4.98	5.45	2.27
Number of non-permit user vehicles parked 5 or more hours in time limited stalls (% of all vehicles)		76 (1.6%)			40 (0.9%)	
ADA placards observed in non-handicap designated stalls (% of occupied stalls)			2 (<1.0%)			0 (0%)
Permits displayed in time-limited stalls (% of occupied stalls); excludes ADA placards.			151 (14.0%)			133 (13.3%)
Occurrence of license plates observed moving from one space to another (% of non-permit unique vehicles)		210 (5%)			184 (4.6%)	

Weekday (Wednesday, 7/20/2016)

- The average time stay for all users is 2 hour/4 minutes. Those without permits are parking for 1 hour/52 minutes. Permit users are parking for an average of 5 hours/2 minutes.
- For the most part, 2 hour stalls are accommodating actual time stay demand for visitors.
- Over the course of the 10 hour survey day, a total of 4,667 vehicles parked on-street. *This is an increase of 511 vehicles over data collected during the spring peak day (or 12.3%).*
- On the survey day, 4,375 vehicles (93.4%) can be associated with visitor trips; 303 (6.6%) are associated with vehicles displaying permits.
- The turnover rate for all users is 4.84, which is below the minimum industry standard of 5.0. The rate increases to 5.36 when permit holders (1.99) are factored out of the equation.


- 76 vehicles were parked in time limited stalls (e.g., 2 hour) for 5 or more hours. These vehicles did not display permits.
- Only 2 vehicles displaying ADA placards or plates parked in the general parking supply. This indicates that ADA needs are being met in available signed ADA “Accessible” stalls.
- 151 vehicles with permits were parked in 2 Hour (unless otherwise specified stalls) at the peak hour, this represented about 14% of all vehicles parked at that hour.
- 210 vehicles were observed moving from one stall to another (i.e., at least one move). This represents 5% of all vehicles using the on-street supply on the survey day.

Weekday (Friday, 7/22/2016)

- The average time stay for all users is 2 hours. Those without permits are parking for 1 hour/50 minutes. Permit users are parking for an average of 4 hours/25 minutes.
- For the most part, 2 hour stalls are accommodating actual time stay demand for visitors.
- Over the course of the 10 hour survey day, a total of 4,318 vehicles parked on-street. *This is an increase of 162 vehicles over data collected during the spring peak day (or 3.9%).*
- On the survey day, 4,032 vehicles (93.3%) can be associated with visitor trips; 286 (6.7%) are associated with vehicles displaying permits.
- The turnover rate for all users is 4.98. The rate increases to 5.45 when permit holders (2.27) are factored out of the equation.
- 40 vehicles were parked in time limited stalls (e.g., 2 hour) for 5 or more hours. These vehicles did not display permits.
- No vehicles displaying ADA placards or plates parked in the general parking supply on the survey day. This indicates that ADA needs are being met in available signed ADA “Accessible” stalls.
- 133 vehicles with permits were parked in 2 Hour (unless otherwise specified stalls), this represented less than 13.3% of all vehicles parked at that hour.
- 184 vehicles were observed moving from one stall to another (i.e., at least one move). This represents approximately 4.6% of all vehicles using the on-street supply on the survey day.

IV. OFF-STREET OCCUPANCIES

Figure C
Hourly Occupancies (Comparative)

*Weekday (Wednesday, 7/20/16)*

- The peak hour for off-street parking (Wednesday) is between 4PM and 5PM. At this hour, 65.4% of off-street stalls are occupied.
- Occupancies decline between noon and 2PM, increasing between 3PM and 5PM, and then dropping steadily through the 7PM survey hour.
- At the peak hour, there are 917 empty stalls within surveyed off-street lots. If this data is extrapolated to the entire off-street supply, it is estimated that there are 1,383 stalls empty off-street at the peak hour (see summarized findings in **Table 4**, page 13).

Weekday (Friday, 7/22/16)

- The peak hour for off-street parking (Friday) is between 1PM and 3PM. During these hours, 60.8% of off-street stalls are occupied.
- Occupancies decrease in each hour from 3PM (56.3%) to 7PM (38%).
- At the peak hour, there are 1,038 empty stalls within surveyed off-street lots. If this data is extrapolated to the entire off-street supply, it is estimated that there are 1,567 stalls empty off-street at the peak hour (see summarized findings in **Table 4**, page 13).

Table 4
Summary of 46 Off-street Sites Surveyed (Comparative)

Lot Number	Facility Identification	Survey Date	# of Stalls	Peak Occupancy/ Hour	Empty Stalls
2	Deschutes County	Wednesday	27	85.2% 2:30 – 3:30 PM	4
		Friday		74.1% 4:30 – 5:30 PM	7
10	Silvermoon Brewing	Wednesday	53	32.1% 6:30 – 7:30 PM	36
		Friday		54.7% 6:30 – 7:30 PM	24
17	Deschutes Co. Annex Bldg	Wednesday	80	82.5% 11:30 AM – 12:30 PM	14
		Friday		77.5% 10:30 – 11:30 AM	18
18	Co Services Bldg	Wednesday	33	78.8% 9:30 – 10:30 AM	7
		Friday		30.3% 9:30 – 10:30 AM	23
21	Deschutes Co. Courthouse - 2 HR customer parking	Wednesday	11	81.8% 10:30 – 11:30 AM 1:30 – 2:30 PM	2
		Friday		72.7% 10:30 – 11:30 AM	3
22	Bank of Cascades	Wednesday	46	65.2% 10:30 – 11:30 AM	16
		Friday		54.4% 10:30 – 11:30 AM	21
23	70 Newport Chinese & Sushi bar/journey	Wednesday	30	96.7% 5:30 – 6:30 PM	1
		Friday		93.3% 5:30 – 6:30 PM	2
24	Permit Parking Only	Wednesday	104	41.4% 6:30 – 7:30 PM	61
		Friday		27.9% 5:30 – 6:30 PM	75
30	North Lot	Wednesday	79	100% 11:30 AM – 12:30 PM	0
		Friday		97.5% 12:30 – 1:30 PM 6:30 – 7:30 PM	2
31	South Lot	Wednesday	97	100% 4:30 – 5:30 PM	0
		Friday		97.9% 12:30 – 1:30 PM	2

32	Bank of America	Wednesday	17	58.8% 4:30 – 5:30 PM	7
		Friday		52.9% 12:30 – 1:30 PM 4:30 – 6:30 PM	8
34	Public 2hr parking	Wednesday	33	93.9% 5:30 – 7:30 PM	2
		Friday		97.0% 6:30 – 7:30 PM	1
36	US Bank	Wednesday	21	52.4% 12:30 – 1:30 PM	10
		Friday		66.7% 6:30 – 7:30 PM	7
38	Permit Parking Only	Wednesday	24	95.8% 10:30 – 11:30 AM 3:30 – 4:30 PM	1
		Friday		75.0% 10:30 – 11:30 AM	6
39	Alpine Mortgage/Deschutes Land Trust	Wednesday	14	78.6% 10:30 – 11:30 AM	3
		Friday		78.6% 9:30 – 10:30 AM	3
44	Gateway Plaza - Permit Only	Wednesday	57	52.6% 9:30 – 11:30 AM 3:30 – 4:30 PM	27
		Friday		61.4% 11:30 AM – 12:30 PM	22
45	First American Title	Wednesday	28	114.3% 3:30 – 4:30 PM	-4
		Friday		103.6% 11:30 AM – 12:30 PM	-1
67	Building 18	Wednesday	8	100% 9:30 – 11:30 AM	0
		Friday		75.0% 9:30 AM – 3:30 PM	2
68	Foundry Church	Wednesday	17	52.9% 11:30 AM – 1:30 PM	8
		Friday		47.1% 1:30 – 2:30 PM	9
69	Public Parking Garage	Wednesday	547	68.2% 3:30 – 4:30 PM	174
		Friday		71.5% 1:30 – 2:30 PM	156
71	Wells Fargo	Wednesday	24	91.7% 3:30 – 4:30 PM	2
		Friday		83.3% 1:30 – 2:30 PM	4

72	Bank of Cascades	Wednesday	14	64.3% 9:30 AM – 1:30 PM	5
		Friday		78.6% 1:30 – 2:30 PM	3
76	Chase Bank	Wednesday	35	51.4% 4:30 – 5:30 PM	17
		Friday		71.4% 5:30 – 6:30 PM	10
80	Amerititle	Wednesday	41	73.2% 2:30 – 3:30 PM	11
		Friday		41.5% 1:30 – 2:30 PM	24
81	Alexander Drake	Wednesday	95	88.4% 10:30 – 11:30 AM	11
		Friday		76.8% 10:30 – 11:30 AM	22
82	DoubleTree	Wednesday	79	88.6% 5:30 – 6:30 PM	9
		Friday		92.4% 9:30 – 10:30 AM	6
85	Jameson Building	Wednesday	40	57.5% 10:30 – 11:30 AM	17
		Friday		47.5% 12:30 – 1:30 PM	21
89	Hawthorne Square Parking	Wednesday	62	61.3% 10:30 – 11:30 AM	24
		Friday		37.1% 10:30 AM – 12:30 PM	39
95	SEND Transportation/Salon Art of Beauty	Wednesday	19	94.7% 9:30 – 10:30 AM 3:30 – 4:30 PM	1
		Friday		73.7% 9:30 – 11:30 AM	5
104	Old St. Francis McMenamins Guests Only	Wednesday	25	92.0% 6:30 – 7:30 PM	2
		Friday		96.0% 6:30 – 7:30 PM	1
112	City Hall	Wednesday	20	60.0% 5:30 – 6:30 PM	8
		Friday		25.0% 2:30 – 4:30 PM	15
115	Customer 2hr Free Parking	Wednesday	13	84.6% 2:30 – 6:30 PM	2
		Friday		69.2% 6:30 – 7:30 PM	4

118	City Employee Vehicles Only	Wednesday	39	97.4% 5:30 – 6:30 PM	1
		Friday		92.3% 1:30 – 3:30 PM	3
125	2 hr parking/ Permit Parking	Wednesday	68	98.5% 10:30 AM – 12:30 PM 1:30 – 3:30 PM	1
		Friday		88.2% 11:30 AM – 12:30 PM	8
126	School District Permit Parking Only	Wednesday	45	97.8% 1:30 – 2:30 PM	1
		Friday		84.4% 10:30 – 11:30 AM	7
129	Boys and Girls Clubs of Bend	Wednesday	33	100% 9:30 – 10:30 AM 11:30 AM – 12:30 PM 1:30 – 3:30 PM	0
		Friday		93.9% 10:30 AM – 12:30 PM	2
131	2 hr parking/ Permit Parking	Wednesday	41	95.1% 10:30 – 11:30 AM 1:30 – 3:30 PM	2
		Friday		97.6% 9:30 AM – 1:30 PM	1
132	Hawthorn Healing Arts Center	Wednesday	17	41.2% 10:30 – 11:30 AM	10
		Friday		17.7% 9:30 AM – 12:30 PM 1:30 – 2:30 PM	14
135	Church Parking	Wednesday	31	90.3% 12:30 – 1:30 PM	3
		Friday		71.0% 12:30 – 1:30 PM	9
149	First United Methodist Church	Wednesday	35	82.7% 10:30 – 11:30 AM	6
		Friday		20.0% 12:30 – 1:30 PM	28
150	Deschutes Historical Museum	Wednesday	41	82.9% 1:30 – 2:30 PM	7
		Friday		65.9% 1:30 – 2:30 PM	14
154	Deschutes Library Parking Only	Wednesday	64	100% 1:30 – 3:30 PM	0
		Friday		75.0% 1:30 – 2:30 PM	15

155	Worrell Wayside Park	Wednesday	82	91.5% 2:30 – 3:30 PM	7
		Friday		79.3% 9:30 – 10:30 AM	17
156	Deschutes Services Building	Wednesday	120	94.2% 10:30 – 11:30 AM	7
		Friday		95.0% 10:30 – 11:30 AM	6
157	Wall Street Services Building	Wednesday	209	77.0% 9:30 – 10:30 AM	48
		Friday		56.5% 11:30 AM – 12:30 PM	91
Off-Street Supply Studied (46 sites)		Wednesday	2,650	65.4% 3:30 – 4:30 PM	917
		Friday		60.8% 12:30 – 2:30 PM	1,038
Total Off-Street Supply		Wednesday	3,998	65.4% 3:30 – 4:30 PM	1,383
		Friday		60.8% 12:30 – 2:30 PM	1,567

V. PEAK HOUR HEAT MAPS

FIGURE D
Wednesday (7/20/2016) Peak Hour

City of Bend - Downtown Bend





FIGURE E
Friday (7/22/2016) Peak Hour

City of Bend - Downtown Bend



VI. COMPLETE OFF-STREET INVENTORY

Table 5
Summary of 158 Off-street Sites (surveyed sites in red)

Lot Number	Facility Identification	# of Stalls	% of Total
1	Tax Drop Box	30	< 1%
2	Deschutes County	27	< 1%
3	Law Firm Parking	10	< 1%
4	State Fire Marshal Truck - Gated	26	< 1%
5	Century Link	22	< 1%
6	Francis, Hansen, Martin	18	< 1%
7	Vacant Lot	8	< 1%
8	Vacant Lot	10	< 1%
9	Naus	20	< 1%
10	Silvermoon Brewing	53	1.3%
11	Oxiliary	11	< 1%
12	Carl W Hopp/academic De Ballot Classique	14	< 1%
13	Bend Theatre for young people	4	< 1%
14	Bendtel Inc	22	< 1%
15	Olde Towne Pizza	9	< 1%
16	MJ Tavern/Nelson Laundry	10	< 1%
17	Deschutes Co. Annex Building	80	2.0%
18	Co Services Bldg	33	< 1%
19	True Gospel United Pentecostal Church	6	< 1%
20	Public Safety Bldg	34	< 1%

21	Deschutes Co. Courthouse - 2 hr. customer parking	11	< 1%
22	Bank of Cascades	46	1.2%
23	70 Newport Chinese & Sushi bar/journey	30	< 1%
24	Permit Parking Only	104	2.6%
25	Columbia Bank/RBC Wealth Mgmt. Upper Structure	33	< 1%
26	1133 NW Wall Lower Structure	28	< 1%
27	1183 NW Wall (behind/below)	33	< 1%
28	1197/1199 Oregrown	8	< 1%
29	325 Building	3	< 1%
30	North Lot	79	2.0%
31	South Lot	97	2.4%
32	Bank of America	17	< 1%
33	Permit Parking Only	18	< 1%
34	Public 2hr parking	33	< 1%
35	Private Permit Only	10	< 1%
36	US Bank	21	< 1%
37	Crabtree and Ramsdorf Employees	11	< 1%
38	Permit Parking Only	24	< 1%
39	Alpine Mortgage/Deschutes Land Trust	14	< 1%
40	Bank of Cascades	11	< 1%
41	Peterkin Associates	3	< 1%
42	Cole Brett	7	< 1%
43	Unmarked Lot	45	1.1%

44	Gateway Plaza - Permit Only	57	1.4%
45	First American Title	28	< 1%
46	Irving Professional Building	10	< 1%
47	Only for Old Cigar	8	< 1%
48	Unmarked	3	< 1%
49	Unmarked	3	< 1%
50	I Mortgage	26	< 1%
51	Unmarked	3	< 1%
52	Pfeifer and Associates	5	< 1%
53	Mom's Tattoos	5	< 1%
54	Resort Resources	7	< 1%
55	Lucas Hovie Parking	10	< 1%
56	Cascade Network	9	< 1%
57	Law Office	5	< 1%
58	Zivney Parking	4	< 1%
59	Bend Counseling And Bio Feed	6	< 1%
60	Gravel Lot	24	< 1%
61	Cascade Transitions Crest Staff and Client	64	1.6%
62	Lerr, Oliver & Company	4	< 1%
63	Thomas E Wold D.M.O	10	< 1%
64	Niswonger, Reynolds Chapel	15	< 1%
65	Medical Cannabis	7	< 1%
66	A Muse Studio	7	< 1%

67	Building 18	8	< 1%
68	Foundry Church	17	< 1%
69	Public Parking Garage	547	13.7%
70	On Point Credit Union	19	< 1%
71	Wells Fargo	24	< 1%
72	Bank of Cascades	14	< 1%
73	Fresh Bread	12	< 1%
74	Reserved	13	< 1%
75	Reserved for Tenant Parking	16	< 1%
76	Chase Bank	35	< 1%
77	Permit Parking Only	7	< 1%
78	Connecting Point Computer	20	< 1%
79	Private Parking Under Ground		
80	Amerititle	41	1.0%
81	Alexander Drake	95	2.4%
82	DoubleTree	79	2.0%
83	Accounting Group	9	< 1%
84	Residential	5	< 1%
85	Jameson Building	40	1.0%
86	Residential	10	< 1%
87	Retail/Commercial	18	< 1%
88	Law Office	6	< 1%
89	Hawthorne Square Parking	62	1.6%
90	Residential	12	< 1%

91	Mixed Use/Retail	9	< 1%
92	Unknown	9	< 1%
93	Unknown	2	< 1%
94	Law Office	7	< 1%
95	SEND Transportation/Salon Art of Beauty	19	< 1%
96	Residential	8	< 1%
97	Saving Grace Counseling	5	< 1%
98	The Steele Law Firm	2	< 1%
99	Three Rivers	7	< 1%
100	Shelton Kelley Realtor	15	< 1%
101	American Family Insurance	4	< 1%
102	Putient Healthcare	6	< 1%
103	Christmas Preserce Retail	7	< 1%
104	Old St. Francis Mcmenamims Guests Only	25	< 1%
105	Reserved Stalls	32	< 1%
106	Pangea International Cuisine, Thump Coffee, Fire in Bend	14	< 1%
107	Reserved for Brooks Resources Corporation	15	< 1%
108	Reserved for McMenamims	12	< 1%
109	Salud Parking	2	< 1%
110	Reserved for Remax	3	< 1%
111	Tenant/The Broker Network	9	< 1%
112	City Hall	20	< 1%
113	Authorized Vehicles Only	22	< 1%

114	The Oregon Store	10	< 1%
115	Customer 2hr Free Parking	13	< 1%
116	City Employee Parking Only	28	< 1%
117	Tenant Parking Only	23	< 1%
118	City Employee Vehicles Only	39	1.0%
119	Park Building Office Suites	5	< 1%
120	Law Offices Brothers, Hawn and Coughlin	7	< 1%
121	Sundowner Capital Management + LLC	3	< 1%
122	Lara House Bed and Breakfast	6	< 1%
123	Deschutes Library Parking Only Alley	15	< 1%
124	Law Office Alley-Lis Fancherr Attn.	4	< 1%
125	2 hr. parking/ Permit Parking	68	1.7%
126	School District Permit Parking Only	45	1.1%
127	Education Center Bend/La Pine school district	12	< 1%
128	Bend Community Radio Entrance	8	< 1%
129	Boys and Girls Clubs of Bend	33	< 1%
130	No Name	4	< 1%
131	2 hr. parking/ Permit Parking	41	1.0%
132	Hawthorn Healing Arts Center	17	< 1%
133	Residential	16	< 1%
134	Residential Rental	6	< 1%
135	Church Parking	31	< 1%
136	Mixed Use/Commercial	10	< 1%

137	Commercial	12	< 1%
138	Kate's Place	15	< 1%
139	Law Office	8	< 1%
140	Small World Collection	3	< 1%
141	Chop Hair	2	< 1%
142	Tuner Automotive	8	< 1%
143	Old Stone Church Parking	21	< 1%
144	ReVive	6	< 1%
145	Cascade Summit Insurance	5	< 1%
146	Retail/Commercial	3	< 1%
147	Engineering	9	< 1%
148	Griffen Heating and Cooling	13	< 1%
149	First United Methodist Church	35	< 1%
150	Deschutes Historical Museum	41	1.0%
151	School St Helens/ Broadway - Amity Creek Magnet School	10	< 1%
152	Trinity Episcopal Church	1	< 1%
153	Trinity Episcopal Church	12	< 1%
154	Deschutes Library Parking Only	64	1.6%
155	Worrell Wayside Park	82	2.1%
156	Deschutes Services Building	120	3.0%
157	Wall Street Services Building	209	5.2%
158	Wall Street Services Fleet Parking Only	59	1.5%
	Total Off-Street Supply (158 sites)	3,998	100%
	Off-Street Supply Studied (46 sites)	2,650	66.3%

RICK WILLIAMS CONSULTING

Parking & Transportation

PO Box 12546

Portland, OR 97212

Phone: (503) 459-7638

E-mail: rick@rickwilliamsconsulting.com

MEMORANDUM

TO: Carolyn Eagan, City of Bend
FROM: Rick Williams, Owen Ronchelli, and Pete Collins, RWC
 Joe Bessman, Phill Worth, and Matt Kittelson, KAI
DATE: March 23, 2016 (v.3)

Project: Downtown Bend Parking Study
Subject: Phase 1: Task 1.4.1 - Data Collection Methodology Report - FINAL


This memorandum presents the methodology for collecting and assessing on- and off-street parking supply and demand data, including loading and unloading areas, within the downtown Bend Parking Study Area. It describes the inventory, data collection, data entry, and data analysis processes, the type of information that will be generated, and how this will be used to evaluate existing and projected parking conditions in the study area.

I. INVENTORY

The parking inventory will serve as a baseline for evaluating existing and projected parking conditions in the study area, cataloging the total number of off-street and on-street parking stalls by location and type. The inventory area map provided by City of Bend staff (**Attachment A**) will be used to establish initial boundaries for the inventory. Revisions to the study area may be made based on input from the Project Management Team (PMT), Technical Advisory Committee (TAC), and Downtown Stakeholder Advisory Committee (DSAC).

Methodology for On-Street Inventory

1. Use of aerial map to identify all on-street parking stalls in study area.
2. Assign a unique number to each city block within the area (see **Figure 1** at right).
3. Format the inventory template to include each block face, with the appropriate number of stalls designated by time restriction (see example, **Attachment B**). The template will include columns that identify:
 - a. Block # (see **Figure 2**, next page)
 - b. Space # (see **Figure 2**)
 - c. Time of day (usually in one-hour increments over the period that the City elects to conduct its survey, e.g. 7:00 a.m.–7:00 p.m.)
 - d. Type of space by time restriction.

Figure 1 : Assigning Block Numbers the

4. Conduct field verification to catalog all on-street spaces in the study area. Use a measuring wheel to estimate the number of stalls on block faces that lack striping.
5. Incorporate initial and field-verified counts into the final inventory template.

Methodology for Off-Street Inventory

1. Use of aerial map to identify all parking sites in the study area.
2. Correlate the map to GIS shape files of tax lots to determine the relationship of buildings to parking areas (see example, **Figure 3**).
3. Assign unique descriptors to each building/parking site.
4. Create an inventory template that includes information on each site—descriptor, building name, address, type of use, number of parking stalls, etc. The template will be created in Microsoft Excel.
5. Use aerial maps to count stalls by site.
6. Incorporate these initial counts into the inventory template (see example, **Attachment C**).
7. Record issues related to specific sites (e.g., tree cover, shade, etc.,) that limit a full count of stalls on site. These issues will be resolved through field verification.
8. Conduct field verification to catalog all off-street spaces in the study area.

Figure 2: Parking Inventory Diagram




Figure 3: Example Mapping of Off-street Inventory



II. DATA COLLECTION

Data collection will provide the information necessary to evaluate existing and projected parking conditions in the study area. Data will include the total number of vehicles parked in the study area over the course of the selected data collection day(s), with stalls denoted by location and type.

Methodology for On-Street Data Collection

1. Field-verify all information from the inventory related to on-street stalls.
2. Finalize an on-street inventory/data collection template (see example, **Attachment B**).
3. Develop route maps based on the most efficient format for collecting data (see example, **Attachment D**).
 - a. At sites where stalls are time-limited, data collection templates will be modified to allow for the collection of hourly license plate data, as requested.
4. Collaborate with the DSAC to determine data collection survey dates and hours.
5. Schedule surveyors.
6. Surveyors will survey each on-street stall in the study area on days representing a “typical weekday” and a “typical weekend day”. Surveyors will record the license plate number for any vehicle parked in a time-limited stall.
7. Data will be collected each hour on the hour for a period of at least 10 hours.

Methodology for Off-Street Data Collection

1. Collaborate with all advisory groups to determine an appropriate process for notifying affected private property sites of the data collection effort.
2. Field-verify all information related to parking sites.
 - a. Field verification will address issues raised in the inventory phase and identify sites with unique characteristics to be surveyed during data collection (e.g., time-limited visitor stalls, handicap stalls, etc.).
3. Finalize an off-street inventory template.
4. Develop route maps based on the most efficient format for collecting data at off-street parking sites.
5. Develop templates to collect occupancy information over a 10-hour study period (see **Attachment B**).
 - a. At sites where stalls are time-limited, data collection templates will be modified to allow for the collection of license plate data.
6. Collaborate with PMT/TAC to determine data collection survey sites, dates and hours.
7. Schedule surveyors.

8. Surveyors will collect occupancy data at all sites on days representing a “typical weekday” and a “typical weekend day,” to be determined with PMT/TAC.
 - a. Data will be collected each hour on the hour for a period of at least 10 hours.
 - b. In facilities with time-limited parking stalls, both occupancy and license plate data will be recorded.
9. Surveyors will record all data in templates developed for each unique site.

III. DATA ENTRY

1. All data from on- and off-street templates will be entered into a database for analysis.

IV. DATA ANALYSIS

Data will be analyzed and evaluated to derive findings for the following metrics.

Parking Supply

Parking supply data for on- and off-street facilities will be organized by location, type, and accessory use.

Parking Demand

Parking demand data will be analyzed to determine the total number of vehicles parked in the study area, cataloged by location, type, and accessory use and described in terms of occupancy, duration of stay, and turnover, as applicable. These factors, described below, can be quantified for the entire study area and/or sub-areas to provide more specificity regarding use in unique nodes of the downtown.

a. Occupancy

Occupancy is the total number of occupied parking stalls in the study area and is most commonly shown as a percentage of overall system capacity. Occupancy can be calculated for the combined study area, for sub-areas, and/or for individual lots or garages. Where time-restricted and other stall types exist, additional information on occupancy of these stalls is provided.

A parking system is generally considered to be full or at its effective capacity when occupancies reach or exceed 85% in the peak hour. Where more than 85% of stalls are occupied, users may be discouraged from parking, or may add to congestion by circling the area in search of available spaces.

b. Duration of Stay

Duration of stay is the average length of time a vehicle remains in a parking stall. For this study, duration of stay is sampled in one-hour increments. Duration of stay information can be used to calibrate posted time stays to accommodate priority users (e.g., retail customers). It can also be used to identify the total

number of vehicles, or percentage of vehicles, that violate posted time restrictions when enforcement hours are in effect, and the rate of vehicle turnover (see below). Duration of stay is calculated by dividing the total number of vehicle hours parked by the total number of unique vehicles captured in the data.

c. Turnover

Turnover reflects the total number of vehicles using a parking stall over the course of a day, and is typically measured over a 10-hour period. Parking managers use turnover as a measuring stick for the efficiency of a parking system. For instance, if a stall has a 2-hour time restriction, its intended minimum rate of turnover is 5 (10-hour day divided by 2-hour stall). If turnover were demonstrated to be less than 5, the system would be deemed inefficient. A rate greater than 5 would indicate a system operating very efficiently.

d. Number of Unique Vehicles

Number of Unique Vehicles is a measure of how many customers, visitors, and employees are accessing the parking district, and can be used as a baseline for commercial growth—more customers and visitors correlates to a more vibrant district. A “unique vehicle” is captured in license plate numbers recorded each hour of the survey.

e. Stays of Five Hours or More

Stays of Five Hours or More can be used to estimate the number of employees using on-street stalls, which is helpful when designing and implementing a district-specific parking management plan and/or calibrating enforcement.

f. Rate of Violation

Data will be analyzed to determine the percentage of vehicles that exceed posted time stays. This information can be correlated to actual enforcement data for the survey days, comparing the observed number of violations to actual citations issued. The parking industry targets violation rates of 5-7% as a measure of efficiency. When violation rates are below 5%, enforcement may be over-provided and customers may perceive the area as not customer-friendly. When rates exceed 7%, the system is considered inefficient and enforcement may need to be increased.

g. Moving to Evade


Moving to Evade is measured by capturing unique license plates that move throughout the study area over the course of a survey day. Such vehicles often belong to employees who move them every few hours to avoid parking off-street or in areas where pricing is in place.

V. SUMMARY

The methodologies outlined in this memorandum have been presented to the PMT, TAC, and DSAC for review and input. Refinements and revisions have been made to this document, which inform the inventory and data collection effort. This completes the requirements for Task 4 -1.4.1 - of the Phase 1 scope of work.

ATTACHMENT A

Preliminary Inventory and Data Collection Area



ATTACHMENT B

EXAMPLE: Off-street Inventory Sheet and Data Collection Template

Lot ID	Facility Identification	# of Stalls	9:30 AM	10:30 AM	11:30 AM	12:30 PM	1:30 PM	2:30 PM	3:30 PM	4:30 PM	5:30 PM	6:30 PM
114_1	North Lot	79	41	56	56	55	54	55	57	73	79	75
114_2	South Lot	97	31	42	52	63	59	55	62	77	92	97
126_1	Wells Fargo	24	16	16	23	21	16	14	16	14	20	24
129_1	Bank of Cascades	14	11	11	10	11	13	13	13	12	7	12
130_1	Chase Bank	35	7	15	13	6	9	14	18	13	8	6
137_1	Old St. Francis Mcmenamins Guests Only	25	21	22	20	16	20	25	24	20	22	25
137_2	Reserved Stalls	32	6	10	12	14	12	11	11	10	11	7
138_1	City Hall	20	8	7	0	1	3	6	5	0	1	0
138_4	Customer 2hr Free Parking	13	3	7	4	6	6	7	7	6	5	4
139_3	City Employee Vehicles Only	39	24	33	29	29	29	29	32	18	16	12
146_1	2 hr parking/ Permit Parking	68	65	68	65	65	66	68	66	52	22	20
146_2	School District Permit Parking Only	45	44	43	44	42	41	41	44	31	12	9
146_5	Boys and Girls Clubs of Bend	33	33	33	31	31	30	28	27	23	5	4
147_1	2 hr parking/ Permit Parking	41	39	40	39	40	38	35	39	33	30	11
147_2	Hawthorn Healing Arts Center	17	9	10	10	8	8	6	7	6	2	1
164_1	First United Methodist Church	35	5	6	26	28	15	8	13	29	14	9
167_1	Deschutes Historical Museum	41	11	26	24	35	30	22	27	20	10	10
171_1	Deschutes Library Parking Only	64	27	51	50	54	57	61	56	35	20	7
118_2	Permit Parking Only	24	20	17	15	13	13	17	16	20	20	17
118_3	Alpine Mortgage/Deschutes Land Trust	14	12	11	10	8	10	12	7	5	3	4
119_2	Gateway Plaza - Permit Only	57	28	27	30	33	35	37	33	21	8	11
119_3	First American Title	28	26	29	29	29	30	34	29	17	9	10
124_1	Building 18	8	8	5	5	5	4	7	5	4	1	1


ATTACHMENT C

Example: Inventory of Off-street Stalls

Lot Number	Lot Descriptor	Stall Total by Lot	% of Total Area Stalls
23/24	2 HR Public Parking (Burnham Lot)	20	11.6%
39	Stevens Marine	8	4.7%
40	Ferguson	12	7.0%
41	B & B Print Source	9	5.2%
42	Mannings Auto	14	8.1%
43	Henderson Auto	41	23.8%
44	Wyatt Fire Protection	9	5.2%
45	Tigard Vision Center (Visitor/Front Lot)	22	12.8%
46	Tigard Vision Center (Employee/Back Lot)	27	15.7%
47	Scott Hookland LLP	10	5.8%
	Total Off-Street Parking Stalls (10 sites)	172	100.0%

ATTACHMENT D

Example: Data Collection Route Map (All Routes)



Downtown Everett Parking Study


September 2015

RICK WILLIAMS CONSULTING
Parking & Transportation

 Downtown Everett Study Boundary




Example: Data Collection Route Map (Single Route)



Downtown Everett Parking Study


ROUTE 1

RICK WILLIAMS CONSULTING
Parking & Transportation



- Route Study Boundary Area
- Block Number Identification
- Blockface Identification
- Walking Direction

- Beginning of Route
- End of Route



October 2015

Sample Rate Policy – South San Francisco, CA

(On –street, Permits, Citations)

A key element of parking management and sound fiscal policy concerns the management of parking rates. Understandably, adjusting parking rates is a very controversial topic among public leaders, downtown stakeholders and users. However, if parking rates are not routinely reviewed and adjusted within the context of a clear, fair and objective policy framework; then when rates are eventually adjusted, the incremental rate increase can be substantial as a long period of time (i.e., years) passes before fiscal challenges within a parking system and/or political jurisdiction necessitate fee/rate increases. Consequently, justifiable increases are at times reactive rather than strategic and policy based. Similarly, the financial systems that support parking are adversely impacted when normal costs of operation are not addressed. According to South San Francisco staff, parking meter rates were last adjusted in 2012

Best practices parking management would suggest that parking rates are routinely adjusted (up or down) to assure the following:

- Cover normal annual increases in operating costs of the system for which a fee is assessed (e.g., on-street meter system, off-street lot and/or garage).
- Provide for future need. This would include normal capital planning and projected growth in the system.
- Reflect market demand. This would use the 85% occupancy standard as a decision-making trigger for adjusting rates.
- Consider rates in place in comparable cities to maintain competitiveness.

A. Parking Meter Rates (on and off-street)

Hourly rates in South San Francisco currently range from \$0.50 - \$1.00 per hour. Error! Reference source not found. below provides insight into rate systems in place in some other California cities for on street parking. As the table shows, South San Francisco’s current on-street rates are on the lower to middle range of rates for other California cities. This table, however, is not intended to reflect “comparable cities,” though eventually establishing a list of cities that South San Francisco would use to track its “peer market” in the future is definitely worth considering (and is discussed below).

The national average for on-street hourly parking is \$1.67 per hour, based on a long-standing annual national survey of rates conducted by Colliers International. This rate is “downtown” based, which provides South San Francisco with a good sense of the overall market (in California and nationally).

Table 1: On-street Hourly Rates – California Cities

City	Hourly Rate	Hourly Rate	Hourly Rate
	1 – 2 Hours (short term - primary visitor)	3 – 6 Hours (mid-range stay)	6+ Hours (Long term stay)
Berkeley, CA	\$1.50	N/A	N/A
Fresno, CA	\$0.75	N/A	N/A
Los Angeles, CA	\$1.00 - \$4.00	\$1.00 - \$4.00	\$1.00 - \$4.00
Oakland, CA	\$2.00	\$2.00	\$2.00
Pasadena, CA	\$1.00	\$1.00	\$1.00
Redwood City, CA	\$0.25 - \$0.50	\$0.25 - \$0.50	\$0.25 - \$0.50
Sacramento, CA	\$1.50	\$1.50	\$1.50
Santa Cruz, CA	\$0.75	\$1.25	\$2.00
San Diego, CA	\$1.25	\$1.25	\$1.25
San Francisco, CA	\$2.00 - \$3.50	\$1.75 - \$3.25	N/A
San Jose, CA	\$1.00	N/A	N/A
San Luis Obispo, CA	\$0.75 - \$1.50	\$0.75 - \$1.50	\$0.75 - \$1.50
San Mateo, CA	\$0.50	\$1.00	\$0.25
Santa Rosa, CA	\$1.00	\$1.00	\$1.00
South San Francisco, CA	\$0.50 - \$1.00	N/A	N/A
Ventura, CA	\$1.00	\$1.50	N/A
National Average - Per Colliers International	\$1.67		

1. Policy Framework (on-street metered parking)

South San Francisco should develop and adopt a parking rate policy that would be reflected in code. New policy would (at minimum):

- Establish the 85% Occupancy Standard as the base measure for evaluating system performance. In other words, as occupancies exceed 85%; the need to evaluate rate adjustments is reasonable based on the desire to maximize access for customers, visitors and employees.
- Establish “rate ranges,” within which rates can be adjusted *administratively* based on operational need and/or actual parking demand. This would specifically amend 11.44.015 (d) Parking Meter Rates.

- Establish an initial rate range of \$0.25 - \$2.00 per hour. This range will likely cover all existing parking need for the near to mid-term.
- Allow rates to be adjusted in increments of up to \$0.25 per hour by the City Manager/Parking Coordinator utilizing operational and performance/demand criteria outlined below.
- Require that when parking “cap” is achieved, new rate ranges would be brought to City Council for review, revision and adoption.
- Establish a recommended minimum schedule for updating the parking inventory and occupancy data necessary to inform periodic adjustments in parking rates. The consultant would suggest a schedule that is not less than once every 24 months. With improved technology over time, this schedule could be accelerated to provide more frequent data collection necessary to support rate review.
- Establish evaluative criteria for rate review that are both operational (Level 1) and performance/demand based (Level 2).
- Require annual parking performance reports to the City Council.

The overall policy framework should be supported through a review process that includes the following:

2. Operational Review (Level 1)

- The true cost necessary to cover the normal operating cost of the parking inventory. This would include the cost of supplies, operating fees, maintenance, support and operation of the on-street pay-to-park system as well as the reasonable cost of financing debt (meters and lots/garages). This would not include the cost of enforcement based on the premise that citation revenue (and therefore citation rates) should be calibrated to cover enforcement operations.
- Cost recovery would be the base hourly rate plus adjustments to cover the costs of inflation within operating cost expenses. [NOTE: It is assumed here that the City is making every effort to manage expenses and cost efficiencies related to operating costs.]
- Reasonable increments necessary to ensure continued growth and replacement of the operating system itself. This would include turnover of equipment due to life cycle replacement, new technologies and/or other factors of growth in the operating system.
- Level 1 suggests that rate increases may be necessary – to cover normal operating costs – even at times when occupancies are less than 85%.¹

3. Performance/Demand (Level 2)

- Sustained occupancies in excess of 85% (i.e., market demand). Based on resources, technology and communications systems, rates can be expressed at various levels of granularity (e.g., parking zone, by parking facility/lot and/or at the block face).

¹ Given that South San Francisco’s rates have not been adjusted in several years, simple inflation related to the “cost of doing business” has not been addressed, particularly as it relates to parking fund deficits or surpluses.

- Consistency with comparable cities. To this end, South San Francisco should identify a set of reasonable comparable business areas and routinely track their rate performance over time for on-street systems.

Overall, it is essential that the issue of rate calibration be viewed as a standard operating procedure within the overall parking management system. The approach outlined here supports the intent of the policy and is structured to allow such decision-making to take place within a specifically defined process and schedule that is data based, designed to support the fiscal health of the parking system and not politicized.

B. Parking Permits

Currently, South San Francisco issues a variety of permit types, with fees ranging from \$0 to \$40 per permit/per month (an annual permit is also available). These permits allow employees use of off-street parking facilities. **Table** provides insight into rate systems in place in some other California cities for off-street monthly parking. As the table shows, South San Francisco’s current off-street rates are on the lower to middle range of rates for other California cities. This table, however, is not intended to reflect “comparable cities,” though eventually establishing a list of cities that South San Francisco would use to track its “peer market” in the future is definitely worth considering (as was discussed with on-street rates above).

Table 2: Off-street Monthly Rates – Select California Cities*

City	Monthly Rate
Bakersfield, CA	\$55
Fresno, CA	\$60
Laguna Beach, CA	\$55 - \$75
Oakland, CA	\$100 - \$220
Redwood City, CA	\$30 - \$60
Sacramento, CA	\$110 - \$185
San Diego, CA	\$135 - \$260
San Luis Obispo, CA	\$40
Santa Cruz, CA	\$25 - \$31
San Mateo, CA	\$126 per quarter (= \$42 per month)
Santa Monica, CA	\$27 - \$82.50
Santa Rosa, CA	\$85 - \$140
South San Francisco, CA	\$0 - \$40
Ventura, CA	\$75

* Sources: Internet reviews and consultant calls to cities.

Initial research on the part of the consultant team finds that there is not a clear policy or procedure that directs the *monthly parking permit* program. For this reason it is recommended that the City create a new section of the code for off-street monthly permits that would include the following elements (1 – 3 below).

1. Policy Framework (off-street monthly parking permits)

South San Francisco should develop and adopt a monthly parking permit policy that would be reflected in code. New policy would (at minimum):

- Establish the 85% Occupancy Standard as the base measure for evaluating the rate for monthly parking and the number of permits issued. In other words, as occupancies exceed 85% in City facilities; the need to evaluate rate adjustments is reasonable based on the desire to balance access for customers, visitors and employees by facility.
- Establish “rate ranges,” within which rates for monthly parking permits can be adjusted *administratively* based on operational need and/or actual parking demand.
- Establish an initial rate range of \$0 - \$100 per month. This range will likely cover all existing monthly parking need for the near to mid-term. Monthly rates can be translated into quarterly or annual rates as an option that the City can provide as a means to minimize the administrative costs of managing monthly permits. However, the option to provide permits on a monthly basis should be available.
- Allow monthly rates to be adjusted in increments of up to \$10.00 per month by the City Manager/Parking Manager utilizing operational and performance/demand criteria outlined below.
- Re-structure current off-street parking rates to reflect actual demand in parking facilities, providing a lower rate option in underutilized facilities and higher monthly fees in high demand and constrained parking facilities.
- Require that when the parking “cap” is achieved, new rate ranges would be brought to City Council for review, revision and adoption.
- Establish a recommended minimum schedule for updating the off-street parking inventory and occupancy data necessary to inform periodic adjustments in monthly parking rates. The consultant would suggest a schedule that is not less than once every 24 months. With improved technology over time, this schedule could be accelerated to provide more frequent data collection necessary to support rate review.
- Establish evaluative criteria for rate review that are both operational (Level 1) and performance/demand based (Level 2).
- Require annual parking performance reports to the City Council.

The overall policy framework for monthly parking permits should be supported through a review process that includes the following:

2. Operational Review (Level 1)

- The true cost necessary to cover the normal operating cost of the off-street parking inventory. This would include the cost of supplies, operating fees, maintenance, support and operation of the off-street pay-to-park system as well as the reasonable cost of financing debt (lots/garages). This would not include the cost of enforcement based on the premise that citation revenue (and therefore citation rates) should be calibrated to cover enforcement operations.

Cost recovery would be the base monthly permit rate plus adjustments to cover the costs of inflation within operating cost expenses. [NOTE: It is assumed here that the City is making every effort to manage expenses and cost efficiencies related to operating costs.]

- Reasonable increments necessary to ensure continued growth and replacement of the operating system itself. This would include turnover of equipment due to life cycle replacement, new technologies and/or other factors of growth in the operating system.
- Level 1 suggests that rate increases may be necessary – to cover normal operating costs – even at times when occupancies are less than 85%.

3. Performance/Demand (Level 2)

- Sustained occupancies in excess of 85% (i.e., market demand). Based on resources, technology and communications systems, monthly parking rates can be expressed at various levels of granularity (e.g., parking zone and/or by parking facility/lot).
- Consistency with comparable cities. To this end, South San Francisco should identify a set of reasonable comparable business areas and routinely track their monthly permit rate performance over time for off-street systems.
- As with the on-street and off-street meter systems, it is essential that the issue of rate calibration be viewed as a standard operating procedure within the overall parking management system. In short, the City of South San Francisco should consider the following in managing its monthly parking permit program.
 - Adjust rates as occupancy demands increase to move monthly parking demand to available stalls and as a means to influence employee options that could include transit, biking, carpooling and walking.
 - Use the 85% Occupancy Standard as a tool to manage rates, occupancy and system performance.
 - Stratify rates between lots based on type of stall (i.e., general access versus reserved) and occupancy data.

C. Enforcement/Citation Rates

The cost of managing the parking enforcement system should not be combined with that of the on-street or off-street parking systems. Citation revenue should cover all operating costs and future needs within the enforcement system (e.g., new personnel, new technologies, system replacements). In other words, parkers who obey the rules of parking in South San Francisco should not be burdened, through their parking rate, to cover the cost of enforcing those who violate the rules. As such, while the enforcement program should be included within the “downtown parking fund,” its expenses and revenues should be carried as separate line items within the fund. The cost of the program should be fully burdened in the citation rate.

Establishing the appropriate rate for parking citations should be based on three criteria. These include:

1. Break even cost for maintaining existing operations, which includes administration, operating personnel, back office and equipment.
2. Future system needs (i.e., reasonable costs associated with system replacement, technology improvements and appropriate system growth).
3. Increments as necessary to support meeting targeted goals for rate of violation, less than 9% with an ideal range of 5% - 7% per best practices and capture rate for compliance, at 40% - 50%.

Downtown Bend Parking Study

Downtown Stakeholder Engagement Summary

August 2016

Downtown Business Engagement on DSAC Draft Guiding Principles

The DSAC sought initial feedback from businesses located in Downtown Bend on the DSAC's Draft Guiding Principles during a series of four coffee klatches hosted at downtown businesses in August. This engagement was targeted to the Downtown community to help the DSAC get a better sense of whether the group was on track in its understanding of Downtown needs and priorities around parking. Further public engagement efforts will take place in the near future and will target additional stakeholder and community input.

Targeted Initial Outreach: Downtown Business Community

- **Guiding Principles**: Engagement focused on sharing the DSAC Draft Guiding Principles with businesses to solicit feedback.
- **120 Businesses and Offices Visited**: Approximate number of businesses and offices visited in Downtown Bend to share information and dates for the downtown business coffee klatches and the Downtown Bend Parking Study.
- **4 Coffee Klatches and 1 Downtown Bend Business Association (DBBA) Meeting**: Four coffee klatches took place in August (two at the Looney Bean Coffee House and two at J-Dub Bar & Grill) for businesses downtown. Coffee klatches were held on Tuesday, August 16 at 8:30am, Wednesday, August 17 at 6:30pm, and Wednesday, August 24 at 8:30am and 5:30pm. The Downtown Bend Business Association also invited a project representative to present the draft Guiding Principles and solicit feedback at their August 30 meeting. The Project Team partnered with the DBBA to get the word out about the coffee klatches.
- **16 Participants and 200 Stakeholders Engaged**: In addition to the many business owners, managers, employees, and office workers whom project team members spoke with when they walked around the downtown to encourage participation in the Downtown Parking Study and the coffee klatches, 16 individuals attended at least one of the coffee klatches or the DBBA meeting on the Draft Guiding Principles. Information about the Parking Study and how to stay updated and engaged was shared with over 200 downtown stakeholders via a handout provided during business visits and email messages to Downtown Parking Study and DBBA electronic mailing lists, which included links to the project website.
- **Feedback Solicited via Discussion and Feedback Form**: Stakeholder comments were captured in discussions as well as in written feedback forms at the klatches and DBBA meeting.

Coffee Klatch and DBBA Meeting Participant General Feedback: DSAC Draft Guiding Principles

- Participants indicated they generally supported the DSAC Draft Guiding Principles and individuals said they found them detailed and **considerate of many needs and interests**.
- Participants were **supportive of the priority users identified** in the Draft Guiding Principles.
- Some participants indicated they felt it was important to highlight that any Parking Management Plan would need to be a **public-private partnership** to be successful. (There was some concern shared about how the roles of the public and private sectors were separated out in the first section of the Draft Guiding Principles document.)
- Participants said they felt **good communication and education** in the community, businesses, and with visitors would be critical to success.
- Communications and outreach efforts around any adopted plan will need to **focus on the positives** of the plan, rather than enforcement.
- Future **communication systems** need to **consider all users**, including those who do not own or do not use technology such as smart phones, for example.
- **Broad stakeholder input** needs to be incorporated into the DSAC process, both from within the Economic Improvement District and the immediately adjacent areas downtown.
- Consider **engaging with law enforcement early** in the process to identify any feasibility concerns around enforcement.
- Participants were generally **supportive** of a data driven decision-making system and the **85% Occupancy Standard**.
- The DSAC needs to be **creative in identifying a parking plan for employees**. Concerns focused on the following:
 - The need to attract and keep high quality employees,
 - Costs to employees and businesses for employee parking,
 - The many types of employees downtown, including those who may park a small or limited number of hours each week,
 - Safety concerns of employees, especially those working early or late hours, and
 - The use of effective incentives or enforcement around employee parking.
- Participants were highly supportive of the notion of **supporting bicycle or electronic vehicle parking** and needed infrastructure to support these modes. Some participants said parking for these modes should be incorporated into any increase in the parking supply downtown.
- Participants indicated they would prefer **more incentives** to increase appropriate or preferred uses of the parking system, **rather than a more punitive focused system** of enforcement.
- **Concerns were noted around the meaning of a financially viable system**. Participants did not want to rule out the possibility of some subsidization of parking if a financially self-sustaining system would price out customers or high quality employees.

Specific Feedback by Guiding Principle

Guiding Principle

1.City Role and Coordination a) Primary Role (City of Bend) and b) Primary Role (Private Sector)

Stakeholder Feedback

- Some participants said they felt that separating out the roles of the City and private sector in the first section of the Guiding Principles takes away from the needed partnership of the public and private sectors in parking management downtown.

Guiding Principles (*Communication*)

1.City Role and Coordination, d) Effective Communications. High-quality, user-friendly communications to ensure easy access for customers and visitors to appropriate and available parking near their destination.

4.Information Systems, Customer Based, a) Product Quality. Provide and manage a safe, reliable, user-friendly and attractive on- and off-street parking and communications system. This will be provided in a manner that complements the quality of downtown and attracts visitors and customers to downtown.

4.Customer Based, c) Branding & Wayfinding. Augment and expand the existing wayfinding system for the downtown that links parking assets and provides directional guidance, preferably under a common brand/logo.

Stakeholder Feedback

- Participants were very supportive of improved and effective signage and communications.

Comment themes:

- Consider expanding the parking plan area to include wayfinding outside of the downtown area (include wayfinding to the downtown area as well).
- Consider all types of users, including those less comfortable or without access to technology.

1.City Role and Coordination, e) Stakeholder Support. Ensure that a representative body of affected private and public constituents routinely informs decision-making.

Stakeholder Feedback

Comment themes:

- Need representation from property owners or others immediately east of the core of Downtown Bend.
- Consider engaging law enforcement early in the development and feasibility of any plan.

Guiding Principle

2. Priority Users a) On-Street System (downtown). The most convenient on-street parking will be prioritized for the customer/visitor (short-term trip).

2. Priority Users b) On-Street System (immediately adjacent neighborhoods). The most convenient on-street parking will be prioritized for residents and their guests.

2. Priority Users c) Off-street System. Coordinate off-street parking resources (public and private) to meet employee and downtown resident demand that cannot be met by safe and reliable walking, biking, riding transit, and carpooling/ridesharing.

Stakeholder Feedback

- Participants were generally supportive of the identified priority users in the Draft Guiding Principles.

Comment themes:

- The DSAC needs to be creative in identifying a parking plan for employees. Concerns focused on the need to attract and keep high quality employees, costs to employees and businesses for employee parking, the many types of employees downtown including those who may park a small or limited number of hours, safety concerns of employees working early or late day hours, and the use of effective incentives or enforcement around employee parking.
- Downtown employees are some of the downtown businesses best customers as well.
- Consider defining the priority user of the on-street system as tourists first, followed by local downtown customers.
- Options are needed for people to park close to their intended downtown destinations, especially if they have physical needs that are not covered by ADA requirements.

Guiding Principle

3. Active Capacity Management, a) Optimize Utilization. Manage the public parking system using the 85% Occupancy Standard to inform and guide decision-making.

Stakeholder Feedback

- Participants were generally supportive of the use of the 85% Occupancy Standard to inform and guide decision-making.

Comment themes:

- The project needs to share with the community whether a problem actually exists with downtown parking based on the data and the 85% Occupancy Standard.
- Lead with statistics and metrics to help inform community discussion.

Guiding Principle

3. Active Capacity Management, c) Shared Off-street Parking. Encourage shared parking in areas where parking is underutilized. This will require an active partnership and effective communication with owners of private parking supplies.

Stakeholder Feedback

Comment theme:

- A Parking Management Plan will need real flexibility in developing any opportunities involving privately held off-street parking. Private lot owners may not be interested in this option.

Active Capacity Management, d) Capacity Expansions. Capacity will be created through strategic management of existing supplies (public and private), reasonable enforcement, leveraging parking with alternative modes, and new supply.

Stakeholder Feedback

Comment themes:

- Some participants indicated they would be amenable to adding parking downtown supply if some of that parking were bicycle parking.
- Some participants indicated they would like consideration of electric vehicle parking in the Guiding Principles or the Parking Plan.

Guiding Principle

4. Customer Based, b) System Communications. Improve existing and create new information resources (outreach, education, maps, websites, apps, etc.) for use by the public and private sectors. Communications systems must be uniform and strategically coordinated.

Stakeholder Feedback

- Participants were very supportive of improved communications systems for downtown parking users.

Comment themes:

- There need to be multiple communication systems to accommodate many types of users, including those less comfortable or without access to technology, such as smart phones.
- Marketing and education of any new Parking Plan needs to promote the positive attributes of any new policies or plan and should not focus on the enforcement or punitive aspects of parking management.
- Focus education on frequent users of downtown, such as local residents and delivery drivers.
- Educational information needs to be simple, short, and easy to read and understand. Guiding Principles could emphasize the need for effective communications in this way.

Guiding Principle

4. Information Systems (Supply & Customer-based), Customer Based, a) Product Quality.

Provide and manage a safe, reliable, user-friendly and attractive on- and off-street parking and communications system. This will be provided in a manner that complements the quality of downtown and attracts visitors and customers to downtown.

Stakeholder Feedback

Comment themes:

- Participants noted a need for safe parking areas throughout downtown for employees and visitors.
- Parking enforcement should not be highly punitive, but serve as a gentle reminder of policy and rules. Incentives are preferred for better compliance.

Guiding Principle

5. Integration with Other Modes b) Bicycle Parking. Increase bike parking on- and off-street to enhance the broader bicycle network.

Stakeholder Feedback

- Participants were generally supportive of increased bicycle parking infrastructure.

Comment themes:

- More bicycle parking is needed. Many businesses have asked for bike corrals in front of their businesses.
- Any bicycle parking needs to be located in highly visible locations to reduce or prevent theft.
- Bicycle corrals contribute to ADA identified needs on downtown sidewalks by removing the bicycle parking from the sidewalk where pedestrians travel.

Guiding Principle

7. Financial Viability, a) Fiscal Stewardship. All parking operations must be financially sustainable.

Stakeholder Feedback

- Participants expressed some concerns about a financially self-sustainable system pricing out customers and employees.

Comment themes:

- Participants had concerns about **passing costs potentially onto customers**, effectively dissuading customers from visiting downtown.
- Participants had concerns about **passing costs potentially onto employees**, possibly making it cost prohibitive for employees to work and park downtown.
- Some participants did not want to leave out the **possibility of some public financial support** for parking, contending that the City benefits from an economically successful downtown and would not benefit from pricing out potential visitors or others from downtown.
- Some participants suggested the DSAC consider a **cost-benefit analysis on using a private parking enforcement company, rather than a publicly run system.**

Other Comments

- **Recreational Vehicle, Tour Bus, and Oversize Vehicles.**
 - Bend is a tourist destination and we may need to consider where drivers can park RVs or tour buses when visiting Downtown Bend
 - Guiding Principles do not address parking management for oversize vehicles such as long or tall passenger trucks or vans.
- **Small Vehicles**
 - Participants were interested in whether the plan will specifically accommodate smaller one- or two-person vehicles such as motorcycles, scooters, and very small vehicles, such as “Smart Cars”.
- **Commercial Delivery Loading Zones Needs**
 - Commercial loading zones and policies need to be addressed. There may be a need for additional loading zone or policies or agreements on loading zone use and timing among businesses.
- **Business Owner and Manager Outreach**
 - Parking information and options needs to be well understood by businesses. Many business owners and managers were not well informed about parking options downtown.
- **Long-term Parking Considerations**
 - There are visitors and others who park long-term (multiple days without moving) in the immediately adjacent neighborhoods to participate in bicycle tours or other events.
- **Manage Expectations**
 - The City has embarked on other **parking management studies in the past** and not implemented recommendations. How is this different?
 - There are **existing policies** (fees-in-lieu for example) that need to be referenced in any effort.
- **Intermittent Parking Constraints**
 - Some business owners commented that they sometimes felt constrained by current parking enforcement. Owners or employees visiting a business for a drop-off or check-in in the morning, for example, who then return to downtown for another visit to the business or a meal in the afternoon **are not permitted to park in the same area in the same day.**



**Downtown Parking Management Study
Community Open House
May 11, 2017
Comment Report**

Table of Contents

Introduction	1
Next Steps	1
Community Outreach.....	1
Participation.....	2
Participation by Bend Neighborhood	2
Participation by Preferred Mode of Commuting	2
Participation by Age.....	2
Open House Content.....	2
Community Input	3
Community Input on Draft Strategies Themes	3
Community Input on Full “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management”	4
Attachment A: Extended Comments Submitted on “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management”	i
Attachment B: Open House Display Boards.....	iv
Attachment C: Comment Card.....	vi

Introduction

Downtown Bend is a vibrant commercial and residential area. People come to downtown to experience an environment that is unique, active, and diverse. A well-managed parking system helps make it safe, easy, and convenient for them to do so.

Over the past 13 months, the Downtown Stakeholder Advisory Committee (DSAC), with help from other community stakeholders, has discussed strategies for parking management in the area. The DSAC and the City held a Community Open House on Thursday, May 11, 2017, to share DSAC draft strategies and seek input from the community. The event was held at the Deschutes Brewery Bend Public House Tap Room in Downtown Bend at 1044 NW Bond Street. The project team, along with eight DSAC members, were on hand at the Open House to provide information and answer questions. For those unable to attend the event, community members were invited to provide comments or questions on the draft strategies in advance of the Open House and through May 12, 2017.

Open house attendees were invited to review display boards highlighting the major themes of the draft strategies. In addition, the project team provided a presentation twice during the evening on the data findings of the study and the draft parking management strategies. Full copies of the draft strategies were also provided online and in-person at the Open House. Attendees were asked to note support, concerns, comments, or questions on moderated display boards, as well as on Comment Cards at the Open House. Again, community members unable to attend the event were invited to submit comments to City Hall on the draft strategies in writing or via email.

Next Steps

Community input on the strategies will supplement the “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management” document and the accompanying project team report.

The Bend City Council will receive the City of Bend, Oregon Downtown Strategic Parking Management Plan once complete and make a determination on its adoption.

Community Outreach

The project team utilized a number of tools to promote the Open House. Outreach efforts included the use of social media, press releases, email blasts, and community fliers.

An event was created on the City of Bend Facebook page and information about the Open House was posted on Facebook, Twitter, as well as the neighborhood social networking platform Next Door. The project website was updated with information about the Open House and other opportunities to provide input. The City circulated press releases to its media list. The project team worked with the Downtown Bend Business Association (DBBA), to send out multiple emails to the DBBA electronic subscription lists about the Open House and opportunities to comment. The DBBA also disseminated flyers the project team produced throughout downtown. In addition, the City and project team sent email announcements about the Open House to the Bend neighborhood associations, interested parties lists and other contacts, and the City created a calendar event on the City of Bend website.

Participation

The Open House was attended by over 15 people, with six additional people providing comment via email. Seven comment cards were received at the Open House. Local television news stations KTVZ and KBND both ran stories on the event on their broadcasts.

Information on participants to the Open House that opted to provide demographic information can be found below.

Participation by Bend Neighborhood

Which neighborhood do you live in?	Number of Participants
Boyd Acres	1
River West	1
Mountain View	2
Southwest Bend	1
Other	1

Which neighborhood do you work in?	Number of Participants
Boyd Acres	1
Old Bend/Downtown	3
Southwest Bend	1
Not employed	1

Participation by Preferred Mode of Commuting

(Some participants indicated multiple modes and this is reflected in the totals below):

Transportation	Number of Participants
Drive alone	4
Bike	2
Walk	2
Take transit	0
Carpool	0

Participation by Age:

Age (in years)	Number of Participants
Under 18	0
18-29 years old	0
30-49 years old	2
50-64 years old	3
65 + years old	1

Open House Content

Open house participants were asked to review and comment on 1) themes identified in the DSAC draft strategies and 2) the full "Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management" document. Participants were asked to comment directly on the Open House display boards and complete a Comment Card.

Community Input

Community Input on Draft Strategies Themes

Open House attendees were first encouraged to comment on the Draft Strategies Themes from the DSAC draft strategies listed below. The following are the survey responses from the Open House Comment Cards on the identified themes. *(A summary and full list of community comments on the complete “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management” document captured via Comment Card, email, and written are included later in the document.)*

Draft Strategies Themes for Community Input
Make parking easier by getting the right car to the right parking space, based on downtown needs. Prioritize downtown visitors/customers for on-street parking.
Encourage downtown long-term parkers to use off-street parking.
Identify creative ideas and partnerships for off-street, long-term parking and employee parking, as well as event parking. Strategies include maximizing publicly controlled lots, partnering with the private sector, supporting multi-modal transportation downtown, and other strategies.
Create a safe and easy-to-use downtown parking system that is well understood by visitors, businesses, and residents. Include multi-modal (bicycle, pedestrian, transit, and motorized vehicle) options in planning and integrate these options into the parking system.
Consider collecting data for a parking management study for the neighborhoods immediately adjacent to downtown.
Develop criteria for evaluating parking management now and in the future. Implement parking strategies one step at a time, not all at once.

Community Responses

Participants were generally very supportive of the DSAC draft strategy themes.

- Participants who submitted Comment Cards all noted that they felt making parking easier by getting the right car to the right parking space and prioritizing visitors/customers for on-street parking were both “very important.”
- In addition, almost all participants who submitted Comment Cards indicated it was “very important” to identify creative ideas and partnerships for off-street parking for long-term parkers, including maximizing publicly controlled lots, partnering with the private sector, and supporting multi-modal transportation downtown, with only one participant not indicating a level of support for this theme.
- Participants also noted the importance of creating a safe and easy-to-use parking system with five participants indicating they considered this “very important” and two participants “neutral” on the theme.
- The strategy to include multi-modal options in planning and integration of the parking system was viewed as “very important” by four participants, with one participant indicating this was “unimportant” in planning, and another two participants not indicating a preference on this theme.
- Four participants indicated they felt it was “very important” or “somewhat important” to consider collecting data for a parking management study in the neighborhoods immediately adjacent to downtown, with three participants not indicating any preference.
- Four participants indicated they felt it was “very important” or “somewhat important” to develop criteria for evaluating parking management now and in the future and to implement strategies one step at a time, rather than all at once. Two participants did not indicate a preference and one participant indicated “neutral” on the theme.

Community Input on Full “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management”

Community members were also encouraged to provide comments on the full “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management” at both the Open House or by providing comment via email or in writing to City Hall.

Participants appeared supportive of the strategies detailed in the “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management.” Participants commented on the draft strategies and offered their own context and experience as input. Community comments received are provided in full below:

Customer first parking management philosophy in the downtown core and customer/visitor parking needs

- At the VERY least, you need to abolish the allowance of downtown employees to rotate their cars throughout their immediate area of employment. This is damaging the ability of offices to conduct business in the downtown with their clients who need to come in efficiently for 1-2 hour appointments.
- Or to start immediately a measure to heavily ticket employees who rotate cars among two-hour spaces.
- Retain two- or three-hour free customer parking as much as possible.
- Locals avoid downtown due to “pay to park” and the fines that come with going over two hours. Locals continually relay they want at least three-hour parking so they can shop, eat, get haircut, etc. They get penalized driving from place to place.
- Don’t take away free parking, maybe extend to three-hour in some places?
- Need three-hour parking on Bond Street/Wall Street. People want to eat...shop...get services.
- People feel “penalized” for coming downtown and getting parking tickets!
- Do not penalize customers for coming downtown, some free parking is needed.

Safe and accessible parking for employee and other long-term parkers

- Provide better employee parking options.
- Put the onus on businesses/employers to provide parking outside of the central business district. Eliminate “permit” systems for their use of two-hour slots.
- City should give free off-site parking for employees and do not take away some free parking for customers.
- I used to work downtown and fortunately the owner of the business paid for parking spaces in the lot behind our building. Since we worked alone during non-busy times during the year it was a comfort to walk outside the door and get into your car safely. We never used the public parking spaces.
- Love the idea of free parking for employees. I currently pay for all of my staff parking.
- Guaranteed and subsidized parking spaces in the covered garage, or at the nearest leasable lot, for full and part time employees of a downtown business or its owners.
- Planning for development and leasing of adjacent parking appropriate land sites for subsidized monthly rental of spaces by owners, employees, at a discounted rate....not just for employees with a \$15 or lower wage.

Integrate transit and multi-modal into parking management planning

- Incentivize non-motorized transportation. Clean up transit system to make it attractive to users – not just disadvantages (homeless) rider on vouchers.
- An electric shuttle bus service for the downtown during all events of a specific size, holiday or venue. Shuttle could be from an official public location not being used on a weekend, or a parking garage. During street fairs, marathons, concerts, holidaysetc. bus is partially paid for by donation, sponsors advertising banners, etc. (or it is paid for by event venue organizers.)
- Resorts (Sunriver) be required to offer Uber or similar shuttles to the downtown 3-4 times per day.
- Free or cheap shuttle between high volume areas for tourists.
- Focus on mass transit and park and ride opportunities outside of central business district.
- Transit stops should be outside of travel lanes, so as to not impede traffic flow.
- Free or subsidized bus passes for employees.
- More buses.
- Carpool lots with free bus shuttles.
- Park next to Suites Hotel on Bond Street and shuttle customers to downtown stores and Old Mill.
- Maybe develop/expand parking areas around Old Mill and ten minute shuttles that run back and forth from downtown to Old Mill area. Anything to reduce traffic foot print in the downtown area.
- Develop bicycle facilities.
- Make secure bike parking in central business district.
- Bike, walkers not applicable with parking. Does not make sense to me.
- Bend is a cold, icy, snowy climate. Biking works better in other climates, realistically not top priority for this climate.

Parking management costs and infrastructure development

- Parking should be self-sufficient including capital improvement costs should be borne by Bend business, those who benefit from increases in “customers.”
- Acknowledge that Bend is growing too fast, put on brakes. Parking and infrastructure deficiencies will be less of a problem.
- Paid numbered meters for all mainstream downtown streets with 2-hour max.
- Thus \$ per month 300, or close to \$ 3600 or more in parking permits. This is a significant overhead for most of these businesses.....and it is not a pass thru salary issue.
- Lot near Sora Sushi- make parking charge fee.
- Also, Bend streets are in need of a redesign. The streets that exist were fine when the town was 20,000 people, but they are not adequate today, and certainly will not handle future traffic.
- Single source management – good.

Parking garage management

- Owners of downtown properties be given priority of RESERVED subsidized/ discounted parking use in garage or closest nearby affiliated lot for their primary signing tenants, and primary employees. This was what was promised in writing at the time of issuing the development permits and in all the original measures to proceed with the downtown garage build out. We were promised this was to be addressed 10 years ago, Paid development fees for the structure, yet long term parking fees in the garage still mount

up to \$600 per employee, per year. A small business in the downtown may average 5-6 employees or more.

- Oxford give us our space back. Build their own parking off Colorado to valet cars.

Communications and Signage

- Entrance signage for all public lots needs consistency. Signage is key to a multi-prong approach.
- Signage super important. Communication/incentives – key!

Immediately Adjacent Neighborhoods Parking Management

- Management strategies implemented in downtown will directly affect adjacent neighborhoods.
- Consider expanding neighborhood studies to industrial area at Crux, Gear Fix, etc.

Large vehicle parking

- One recommendation—vehicles over a certain length cannot use our angled parking spots—too many “trucks” are jutting into the driving lanes.
- I believe a huge concern that needs to be addressed is parking spaces used by large or long vehicles. Extended cab trucks and long SUVs should be required to park elsewhere. A line should be placed at the length of a normal car length and if a larger or longer vehicle parks there it should be cited. There is barely enough room for the two lanes of traffic to make it down the road let alone a bicyclist. People have to swerve into the other lane to get by many of the long trucks. It is a very dangerous situation including dealing with tourists popping out into traffic to cross the road. Please remedy this. The other day I noticed a large camper van with its front wheels on top of the sidewalk and the rear was still in the traffic lane. It makes it very difficult for someone backing out of a parking space to see behind or around that vehicle. Again, please remedy this situation, it is a hazard. Yes, customers first but with reasonable and safe parking.

Please see “Attachment A” for extended comments on parking strategies.

Attachment A: Extended Comments Submitted on “Downtown Stakeholder Advisory Committee Draft Strategies for Downtown Parking Management”

Thank you for your involvement in the parking decisions and strategies that staff has presented. I’m sorry I could not have been at the meeting yesterday, but had a conflict with the time.

It is critical that the entire Drake Park Historic District be included in the strategic parking and plan.

The area of study and implementation excludes the 400 and 500 blocks of Congress and State Street and for certain these streets will be impacted by increased parking if they are not added to the area plan for parking limitations. It’s just too easy for parking to shift one block if the other nearby blocks have time limits applied.

While some of the strategies and implementation seem like they will work, I do not endorse the removal of the 2 hour parking over time. Old habits will reoccur and newcomers to the Bend area (“Entrepreneurs” flocking to our town for free services) will clog our streets again. Also it is unclear who will be allowed to have permits: Only residents of the neighborhood? Or non-residents also? And did the study discover who is parking for longer periods? Is it workers downtown, RVs/vans/passenger cars staying for extended periods, tourists, City staff? It should be mandatory that all City staff park in the parking garage, freeing up more spaces closer to downtown, and keeping those worker’s vehicles out of nearby neighborhoods.

Please note that the study also does not refer to or understand the circulation of parking for the services offered at the Family Kitchen. “Fairy Path” is a pedestrian only continuation of Idaho and the “Entrepreneurs” will almost assuredly park (as they already do) even more consistently on Congress and/or State and walk to access the Family Kitchen. The Drake Park Historic District already feels the pressure of this group, and it will only get worse.

It is more important than ever to protect The Drake Park Historic District and the downtown core. We do not want to become an afflicted inner city where committed families are moving to the periphery of town for refuge. Please ensure that the ENTIRE Drake Park Historic District is included for the parking plan and let me know when one or more of these strategies will be put into place (did I read 48 months??). The downtown neighborhoods have endured for over 10 years— it’s time to make a change.

Thank you for your time.

Basically a suggestion to consider parking as a symptom of a flawed approach to urban transportation rather than a problem to be solved in itself - 'building a more elaborate infrastructure of roads and parking facilities only encourages more of the same. We feed the beast instead of taming it.'

Transportation in Bend or How to stop feeding the Beast.

“The average car moves just 5% of the time. To improve cities, focus on the other 95%”

Urban transportation technology is undergoing disruptive change across the country and across the globe. Instead of increased numbers of personal vehicles, rented people movers, soon to be autonomous, are reducing the need for personal vehicles, autonomous door-to-door public transportation systems are being piloted and the need to dedicate prime real estate for parking is diminishing steadily. Safety is a main driver and beneficiary of such change as autonomous vehicles will eliminate traffic violations – red light running, DUII and speeding, distracted driving.

The thinking around parking, congestion, infrastructure development and roadway maintenance in Bend assumes that the volume of traffic will inevitably increase with the growth of our town and tourist economy.

Solutions that try to manage increased volume of traffic are not only enormously expensive, both in capital and maintenance costs, but are unlikely to resolve the issues of safety, congestion, air/noise pollution and roadway wear and tear. The underlying problem never goes away. In fact, building a more elaborate infrastructure of roads and parking facilities only encourages more of the same. We feed the beast instead of taming it. A different future can be created for our town. Bend can be a pioneer in this revolution of urban transportation.

Stop Feeding the Beast

Reduce the number of vehicles on our roads. Make personally owned vehicles a needless and costly indulgence in Bend by creating the conditions for alternatives with comparable or better convenience and cost – public and privately owned and managed. There are carrots and sticks to get the ball rolling.

Carrots. A suitable vehicle can be summoned for door to door transportation within 'x' minutes of a need to get from A to B at 'y' \$ cost.. 'Suitable vehicle', 'x' and 'y' need to be determined so:

– invite the major players in the transportation revolution to use Bend as a test bed.

- Invest in solutions that reflect the revolution in transportation technologies.

Sticks. Make the use of personal vehicles reflect the true cost of using Bend roads and parking. Rented transportation has a big advantage in that it need not be parked - which is only a boon where parking is both difficult to find and expensive.

- Decrease downtown parking.
- Introduce a congestion charge.
- Install parking meters with variable pricing.

Safety for all road users comes from unimpaired, law abiding behavior on our roads. Law enforcement needs police presence. Bend is already down from 6 traffic officers and a sergeant to two officers and a sergeant and is struggling to recruit police officers. Capitalize on technology to multiply our law enforcement presence.

- Install speed cameras across Bend.
- Increase the deployment of red light cameras.

An Opportunity to Lead the Way.

Bend can be a pioneer in urban transportation and, agreed, you can spot a pioneer by the arrows in their back. It will take vision and political courage to embark on a new course of action. But we won't even be in the vanguard of this revolution globally. Many cities around the world have already taken such steps and started the move to revolutionize their urban transportation. Bend Councilors and City Management have the chance to kill the Beast with bold, innovative leadership. Do they have the will?

References.

Sacred Spaces.– The Economist Feb 6th 2017.

- <http://www.economist.com/news/briefing/21720269-dont-let-people-park-free-how-not-create-traffic-jams-pollution-and-urban-sprawl>

Americans and their Cars – The Economist, Jan 8th, 2015

- <http://www.economist.com/news/united-states/21638132-free-parking-not-all-its-cracked-up-be-race-space>

Aparkalypse now. The perilous politics of parking – The Economist February 6th, 2017

- <http://www.economist.com/news/leaders/21720281-average-car-moves-just-5-time-improve-cities-focus-other-95-perilous>

Three Revolutions in Urban Transportation

- <https://www.itdp.org/3rs-in-urban-transport/>

5 steps to an urban transportation revolution

- <https://www.greenbiz.com/article/5-steps-us-urban-transportation-revolution>

The Third Transportation Revolution: Lyft's Vision for the Next Ten Years and Beyond

- <https://medium.com/@johnzimmer/the-third-transportation-revolution-27860f05fa91>

Attachment B: Open House Display Boards



CITY OF BEND

Welcome!

Downtown Parking Study

Community Open House



CITY OF BEND

Downtown Parking Study Map



City of Bend - Downtown Bend

2018

Parking Study Area
 Downtown Improvement District
 Best Parking District

Rick Willigens, Consultant
 Planning & Development



CITY OF BEND

What is the Downtown Parking Study?

In 2002, Bend conducted a Downtown Parking study. Since that time downtown commercial square footage has increased an estimated 50 percent, and the downtown core has expanded outward. However, the way we park has remained relatively unchanged.

During this study, we have updated our information (data) about parking supply and demand. A community advisory committee, the Downtown Stakeholder Advisory Committee (DSAC), has worked with the project team for the past year to evaluate the data and develop draft strategies to better serve downtown businesses, residents, and people who come downtown.



CITY OF BEND

We want your input!

The Downtown Stakeholder Advisory Committee (DSAC) has developed a set of draft strategies for downtown parking management. The DSAC has been listening to downtown stakeholders and community members throughout the process. Now we want to share information about the study and get your feedback on some key concepts.

Step One
Walk around and take a look at the various boards. Tell us what you think. Feel free to write directly on the poster boards.

Step Two
Fill out a Comment Card.

Next Steps
We'll use the feedback we hear from you to refine the DSAC draft strategies. Then the recommendations will go to City Council!

Tell us what you think about the draft strategies below.

Make parking easier by getting the right car to the right parking space, based on downtown needs.

Prioritize downtown visitors/customers for on-street parking. Encourage downtown long-term parkers to use off-street parking.

Tell us what you think about the draft strategies below.



Identify creative ideas and partnerships for off-street, long-term parking and employee parking, as well as event parking. Strategies include maximizing publicly controlled lots, partnering with the private sector, supporting multi-modal transportation downtown, and other strategies.

Tell us what you think about the draft strategies below.



Create a safe and easy-to-use downtown parking system that is well understood by visitors, businesses, and residents.

Tell us what you think about the draft strategies below.



Include multi-modal (bicycle, pedestrian, transit, and motorized vehicle) options in planning and integrate these options into the parking system.

Tell us what you think about the draft strategies below.



Consider collecting data for a parking management study for the neighborhoods immediately adjacent to downtown.

Tell us what you think about the draft strategies below.

Develop criteria for evaluating parking management now and in the future. Implement parking strategies one step at a time, not all at once.



CITY OF BEND

Other Thoughts or Questions?

Thank you!

Attachment C: Comment Card

Downtown Parking Study Community Open House Comment Card

Thank you for attending! Please take a few minutes to provide us with your comments. Your comments will be reviewed by the project team and will inform refinement of the draft parking strategies for Downtown Bend. If you can't complete the form today, please feel free to bring your comments in writing to the Economic Development Department at Bend City Hall at 710 NW Wall Street, Bend, Oregon 97703 or send your comments by email to Kathy Montgomery at kmontgomery@bendoregon.gov by May 12, 2017, at 5:00 pm.

The Downtown Stakeholder Advisory Committee (DSAC) has developed a set of draft strategies for downtown parking management. The DSAC has been listening to downtown stakeholders and community members throughout the process. Now they want to get your feedback on some key concepts.

1. Make parking easier by getting the right car to the right parking space, based on downtown needs. Prioritize downtown visitors/customers for on-street parking. Encourage downtown long-term parkers to use off-street parking.

Very important	Somewhat important	Neutral	Unimportant	Very unimportant
<input type="checkbox"/>				

Additional thoughts:

2. Identify creative ideas and partnerships for off-street, long-term parking and employee parking, as well as event parking. Strategies include maximizing publicly controlled lots, partnering with the private sector, supporting multi-modal transportation downtown, and other strategies.

Very important	Somewhat important	Neutral	Unimportant	Very unimportant
<input type="checkbox"/>				

Additional thoughts:

3. Create a safe and easy-to-use downtown parking system that is well understood by visitors, businesses, and residents.

Very important	Somewhat important	Neutral	Unimportant	Very unimportant
<input type="checkbox"/>				

Additional thoughts:

4. Include multi-modal (bicycle, pedestrian, transit, and motorized vehicle) options in planning and integrate these options into the parking system.

Very important	Somewhat important	Neutral	Unimportant	Very unimportant
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Additional Thoughts:

5. Consider collecting data for a parking management study for the neighborhoods immediately adjacent to downtown.

Very important	Somewhat important	Neutral	Unimportant	Very unimportant
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Additional Thoughts:

6. Develop criteria for evaluating parking management now and in the future. Implement parking strategies one step at a time, not all at once.

Very important	Somewhat important	Neutral	Unimportant	Very unimportant
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Additional Thoughts:

7. Additional Questions/Comments?

Tell us more about yourself!

Which Bend neighborhood do you live in?			Which Bend neighborhood do you work in?		
<input type="checkbox"/> Awbrey Butte	<input type="checkbox"/> Old Bend/ Downtown	<input type="checkbox"/> Southeast Bend	<input type="checkbox"/> Awbrey Butte	<input type="checkbox"/> Old Bend/ Downtown	<input type="checkbox"/> Southeast Bend
<input type="checkbox"/> Boyd Acres	<input type="checkbox"/> Old Farm District	<input type="checkbox"/> Southern Crossing	<input type="checkbox"/> Boyd Acres	<input type="checkbox"/> Old Farm District	<input type="checkbox"/> Southern Crossing
<input type="checkbox"/> Century West	<input type="checkbox"/> Orchard District	<input type="checkbox"/> Southwest Bend	<input type="checkbox"/> Century West	<input type="checkbox"/> Orchard District	<input type="checkbox"/> Southwest Bend
<input type="checkbox"/> Larkspur	<input type="checkbox"/> River West	<input type="checkbox"/> Summit West	<input type="checkbox"/> Larkspur	<input type="checkbox"/> River West	<input type="checkbox"/> Summit West
<input type="checkbox"/> Mountain View		<input type="checkbox"/> I don't know	<input type="checkbox"/> Mountain View		<input type="checkbox"/> I don't know

How do you commute to work?	What is your age?
<input type="checkbox"/> Drive alone	<input type="checkbox"/> Under 18 years old
<input type="checkbox"/> Bike	<input type="checkbox"/> 18-29 years old
<input type="checkbox"/> Walk	<input type="checkbox"/> 30-49 years old
<input type="checkbox"/> Take transit	<input type="checkbox"/> 50-65 years old
<input type="checkbox"/> Carpool	<input type="checkbox"/> Over 65 years old
<input type="checkbox"/> Work at home	
<input type="checkbox"/> I don't know	